SOUTHLAND TIMES - STRENGTHENING TO 67% NBS - INVERCARGILL FEASIBILITY ESTIMATE



SUMMARY

	INDICATIVE F	ANGE
	\$ LOW	\$ HIGH
01 LAND & PROPERTY	EXCLUDED	EXCLUDED
LAND & PROPERTY COSTS	EXCLUDED	EXCLUDED
02 ENABLING WORKS	0	0
03 CONSTRUCTION COSTS	5,110,000	5,908,000
04 SERVICES CONNECTIONS	25,000	31,000
05 EXTERNAL WORKS	Existing	Existing
06 ABNORMALS	100,000	125,000
TOTAL CONSTRUCTION COST	5,235,000	6,064,000
07 RESOURCE CONSENT & BUILDING CONSENT	66,000	76,000
08 DEVELOPMENT CONTRIBUTIONS	EXCLUDED	EXCLUDED
09 PROFESSIONAL FEES	795,000	921,000
10 PROJECT CONTINGENCY	1,220,000	1,413,000
11 ESCALATION	219,000	260,000
TOTAL ON-COSTS	2,300,000	2,670,000
TOTAL INDICATIVE PROJECT COST RANGE	\$7,535,000	\$8,734,000

Clarifications:

- Costs are indicative only at this stage for discussion
- Costs exclude FF&E
- Indicative cost estimate priced at current rates as at 1Q19
- Professional Fees have been included at 15% (Including PM)
- Building Consent has been included at 1.5%
- Project Contingency has been included at 20%

Exclusions:

- GST
- Escalation
- Land Cost
- Statutory Fees
- Ground remediation, rock excavation, soft spots
- Removal of significant ground obstructions
- External Works (Landscaping, Carparking, Site Services)
- Development Management / Internal Development Costs
- Artwork
- Sales, Marketing and Leasing
- Finance and Holdings Costs
- Legal fees
- Any local or central Government taxes, duties, fees, rates or levies which are, or may become, payable
- Ground investigation and any works required arising from this
- Stormwater attenuation
- Renewable energy technologies
- Grey water reticulation systems
- Black water on site treatment

SOUTHLAND TIMES - STRENGTHENING TO 67% NBS - INVERCARGILL FEASIBILITY ESTIMATE



FEASIBILITY ESTIMATE DETAIL

		INDICATIVE RANGE									
							\$ LOW				\$ HIGH
	Enabling Works				'						
	Allowance for Façade Retainment	1	Item				Excluded				Excluded
	Subtotal - Façade Retainment		m2			\$	-			\$	-
	Demolition										
	Internally Fitout - Ground Floor										
	Demolish internal partitions and linings	326	m2	\$	35	\$	11,410	\$	40	\$	13,040
	Demolish single door & frame	8	No	\$	55	\$	440	\$	60	\$	480
	Demolish double door & frame	3	No	\$	75	\$	225	\$	80	\$	240
	Demolish existing joinery units	1	Item	\$	1,500	\$	1,500	\$	1,750	\$	1,750
	Demolish existing floor coverings	588	m2	\$	5	\$	2,941	\$	8	\$	4,41
	Demolish existing ceiling finishes	588	m2	\$	13	\$	7,351	\$	15	\$	8,822
	Internally Services - Ground Floor										
	Demolish existing plumbing fittings	1	Item	\$	2,000	\$	2,000	\$	2,500	\$	2,500
	Demolish existing HVAC services	588	Item	\$	10	\$	5,881	\$	13	\$	7,35
	Demolish existing electrical services	588	m2	\$	5	\$	2,941	\$	8	\$	4,41
	Demolish existing fire services	588	m2	\$	5	\$	2,941	\$	8	\$	4,41
	Internally Fitout - First Floor										
	Demolish internal partitions and linings	310	m2	\$	35	\$	10,850	\$	40	\$	12,40
	Demolish single door & frame	8	No	\$	55	\$	440	\$	60	\$	48
	Demolish double door & frame	1	No	\$	75	\$	75	\$	80	\$	8
	Demolish existing joinery units	1	Item	\$	1,500	\$	1,500	\$		\$	1,75
	Demolish existing floor coverings	588	m2	\$	5	\$	2,941	\$	8	\$	4,41
	Demolish existing ceiling finishes	588	m2	\$	13	\$	7,351	\$	15	\$	8,82
	Internally Services - First Floor										
	Demolish existing plumbing fittings	1	Item	\$	2,000	\$	2,000	\$	2,500	\$	2,50
	Demolish existing HVAC services	588	Item	\$	10	\$	5,881	\$	13	\$	7,35
	Demolish existing electrical services	588	m2	\$	5	\$	2,941	\$	8	\$	4,41
	Demolish existing fire services	588	m2	\$	5	\$	2,941	\$	8	\$	4,41
	Internally Fitout - Second Floor	42.4	?	۲.	25	ć	14.040	۲.	40	¢	16.06
	Demolish internal partitions and linings	424	m2	\$	35	\$	14,840	\$	40	\$	16,96
	Demolish single door & frame	20	No	\$	55 75	\$	1,100	\$	60	\$	1,20
	Demolish double door & frame	1	No	\$	75 1 500	\$	75	\$	80	\$	8
	Demolish existing joinery units	1	Item	\$	1,500	\$	1,500	\$	1,750	\$	1,75
	Demolish existing floor coverings	588	m2	\$	5	\$	2,941	\$	8	\$	4,41
	Demolish existing ceiling finishes	588	m2	\$	13	\$	7,351	\$	15	\$	8,82
	Internally Services - Second Floor		14	۲.	2.000		2 25-		2 500		
	Demolish existing plumbing fittings		Item		2,000	\$	2,000	\$	2,500	\$	2,50
	Demolish existing HVAC services	588	Item	\$	10	\$	5,881		13	\$	7,35
	Demolish existing electrical services	588	m2	\$	5	\$	2,941		8	\$	4,41
	Demolish existing fire services	588	m2	\$	5	\$	2,941	Ş	8	\$	4,41
Ī	Subtotal - Demolition		m2			\$	116,116			\$	145,92

3.2 Strengthening Works - BMC Report - Strengthening to 67% NBS - Based on Discussion With Warren Holt BMC - noting 67% scheme would effectively be almost identical with some minor changes to spacing of Fixing and no need for infilling of existing window (previously including in Windows & Doors)

Diaphragm to V	/all Arrangement
----------------	------------------

First Floor Diaphragm Repairs						
De-construct existing timber flooring to perimeter of floor plate	186	m2	\$ 100	\$ 18,624	\$ 135	\$ 25,142
Fabricated 200 x 100 x 8 L brackets with M16 chemset anchors @	248	No	\$ 150	\$ 37,200	\$ 60	\$ 14,880
300 x 50 Boundary Joist and intermediate nog	138	m	\$ 45	\$ 6,228	\$ 50	\$ 6,920
350 x 50 solid blocking cut between existing floor joists	53	m	\$ 55	\$ 2,904	\$ 65	\$ 3,432
15 thick Ecoply Plywood 1200 wide to diaphragm perimeter	186	m2	\$ 95	\$ 17,693	\$ 105	\$ 19,555

Southland times - strengthening to 67% NBS - invercargill ${\it FEASIBILITY} \ {\it ESTIMATE}$



						INDICATIVE RANGE					
							\$ LOW				\$ HIGH
					,						
	Strengthening Works - BMC Report - Strengthening to 67% NBS - Ba										
	be almost identical with some minor changes to spacing of Fixing a	nd no nee	ed for	infilli	ng of exi	sting	window (previo	usly	includi	ng in	Windows &
<u>.</u>	Doors)										
ç	Second Floor Diaphragm Repairs										
_	De-construct existing timber flooring to perimeter of floor plate	186	m2	\$	100	\$	18,624	\$	135	\$	25,142
	Fabricated 200 x 100 x 8 L brackets with M16 chemset anchors @	220	No	\$	150	\$	33,000	\$	60	\$	13,200
3	300 x 50 Boundary Joist and intermediate nog	138	m	\$	45	\$	6,228	\$	50	\$	6,920
3	350 x 50 solid blocking cut between existing floor joists	53	m	\$	55	\$	2,904	\$	65	\$	3,432
1	15 thick Ecoply Plywood 1200 wide to diaphragm perimeter	186	m2	\$	95	\$	17,693	\$	105	\$	19,555
_	Roof Diaphragm Repairs Install M16 chemset anchors at 800 crs	44	No	\$	40	\$	1,760	¢	50	\$	2,200
	Allowance for removal of existing ceilings to allow access	34	m2	\$	35	\$	1,190		40	\$	1,360
,	Allowance for removal of existing ceilings to allow access	34	1112	Y	33	Y	1,150	Y	40	Y	1,300
F	Parapet Restraint - Externally										
	Remove roofing to permit access to roof trusses	240	m2	\$	15	\$	3,600	\$	20	\$	4,800
1	Install 150 PFC strong back including Python MT fixings	2,592	kg	\$	15	\$	38,880	\$	20	\$	51,840
ľ	M12 chemset anchors @ 1000 chs	200	no	\$	25	\$	5,000		30	\$	6,000
	50 x 5 CHS struts @ 3400 crs to match existing trusses	36	no	\$	275	\$	9,900		325	\$	11,700
A	Allowance for roofing reinstatement including Dektite flashings	240	m2	\$	80	\$	19,200	\$	100	\$	24,000
	Facado Potainment - Eiret Floor										
	Façade Retainment - First Floor 140 x 45 SG8 strongback studs @ 400 crs	1,052	m	\$	20	\$	21,040	\$	25	\$	26,300
	140 x 45 SG8 dwang@ 400 crs	1,052	m	\$	23	\$	23,625		27	\$	28,350
	Python ties @400 crs vertically with 75x50x5 EA bracket	3,156	no	\$	35	\$	•	\$	40	\$	126,240
	Allowance for lining and finishing to exterior walls	420	m2	\$	75	\$	31,500		85	\$	35,700
	0					Ċ	,,,,,,	Ċ		•	,
F	Façade Retainment - Second Floor										
1	140 x 45 SG8 strongback studs @ 400 crs	1,315	m	\$	15	\$	19,725	\$	20	\$	26,300
	140 x 45 SG8 dwang@ 400 crs	840	m	\$	23	\$	18,900		27	\$	22,680
	Python ties @400 crs vertically with 75x50x5 EA bracket	2,630	no	\$	35	\$	92,050		40	\$	105,200
F	Allowance for lining and finishing to exterior walls	525	m2	\$	75	\$	39,375	\$	85	\$	44,625
9	Subtotal -Strengthening Works		m2			\$	597,303			\$	655,474
3.4	Structural Walls										
(Costs included in Item 3 Strengthening Works										
(Subtotal -Structural Walls		m2			\$		$\overline{}$		Ś	
	Structural Walls		1112			<u> </u>		<u> </u>		Ψ	
	Upper Floors										
(Costs included in Item 3 Strengthening Works										
[Subtotal -Upper Floors		m2			\$		т		\$	
<u> </u>	Subtotal -Opper Floors		1112			٠	<u>-</u>			٦	
3.6 F	Roof										
(Costs included in Item 3 Strengthening Works										
_											
S	Subtotal -Roof		m2			\$	-	L		\$	-
3.7 E	External Works										
١	Works to Existing Envelope										
	Allowance to prep and clean existing façade	1,607	m2	\$	25	\$	40,175	\$	30	\$	48,210
	Allowance for stripping & re-pointing existing masonry walls	1,607	m2	\$	40	\$	64,280	\$	50	\$	80,350
A	Allowance for making good existing plaster mouldings	1	Item	\$	5,000	\$	5,000	\$	6,000	\$	6,000
_	Subtotal -External Walls		m2			\$	109,455	$\overline{}$		\$	134,560

Southland times - strengthening to 67% NBS - invercargill ${\it FEASIBILITY} \ {\it ESTIMATE}$



						INDICATIVE RANGE					
							\$ LOW			\$ HIGH	
					ı						
3.8	Windows & Doors										
	Allowance to repair, ease and painting existing	1	Item	\$	15,000	\$	15 000	\$ 20,000	\$	20,000	
	Allowance to repair, case and painting existing	-	100111	7	13,000	Y	15,000	¥ 20,000	Y	20,000	
ľ	Subtotal -Windows & Doors		m2			\$	15,000		\$	20,000	
	Subtotal Williams & Soois					<u> </u>	13,000		١,٧	20,000	
3.9	Stairs & Balustrades										
			14	,	F0 000	,	50.000	¢ 60 000		50.000	
	Allowance to make good existing to suit new layout	1	Item	\$	50,000	\$	50,000	\$ 60,000	\$	60,000	
1								1	1 4		
	Subtotal - Stairs & Balustrades		m2			\$	50,000		\$	60,000	
3.10	Internal Partitions										
	Allowance to make good existing stair & lift walls	1	Item	\$	15,000	\$	15,000	\$ 20,000	\$	20,000	
	Subtotal - Internal Partitions		m2			\$	15,000		\$	20,000	
3.11	Internal Doors										
	Allowance to make good existing doors	1	Item	¢	7,500	\$	7 500	\$ 10,000	¢	10,000	
	Allowance to make good existing doors	_	iteiii	۲	7,300	۲	7,300	7 10,000	Ţ	10,000	
ſ	Subtotal - Internal Partitions					\$	7,500		\$	10.000	
ļ	Subtotal - Internal Partitions		m2			Þ	7,500		Ş	10,000	
	Floor Finishes										
	Allowance for new floor finishes	1,764	m2	\$	75	\$	132,323	\$ 85	\$	149,966	
	Subtotal - Floor Finishes		m2			\$	132,323		\$	149,966	
3.13	Wall Finishes										
	Included in items 3 & 10										
	medded in items 5 & 10										
ľ	Subtotal - Wall Finishes		m2			\$	_		\$	_	
ļ	Subtotul - Wall Fillishes		1112			<u> </u>			١,٧		
244											
	Ceiling Finishes										
	Allowance for new suspended ceiling	1,764	m2	\$	85	\$	149,966	\$ 95	\$	167,609	
	Subtotal - Ceiling Finishes		m2			\$	149,966		\$	167,609	
3.15	Fitting & Fixtures										
	Allowance for tea points per floor	3	No	ς	7,500	¢	22 500	\$ 9,000	\$	27,000	
	Allowance for tea points per moor	3	NO	۲	7,300	٧	22,300	\$ 5,000	Ţ	27,000	
ſ	Subtotal - Fitting & Fixtures		m2			\$	22,500		\$	27.000	
	Justotai - rittilig & ristuics		IIIZ			þ	22,500		۲	27,000	
24-											
3.16	Sanitary Plumbing										
	Allowance for replacement existing fittings new H&C pipework	1	Item	ć	20,000	ċ	20,000	\$ 25,000	ć	25,000	
	Allowance for replacement existing fittings new flac pipework		пеш	ڔ	20,000	٦	20,000	\$ 23,000	Ą	23,000	
l	Subtotal - Sanitary Plumbing		m2			\$	20,000		\$	25,000	
	· · · ·					•	•	•		•	
3 17	Mechanical Services										
	Allowance for replacement of existing plant and equipment with	1,764	m2	\$	275	\$	485,183	\$ 325	\$	573,398	
	heat recovery type VRF system						·				
	HI AC Unit to IT / Data Room		Item		7,500	\$	7,500	\$ 8,500		8,500	
			_	_	20	4	F2 020	\$ 35	\$	61,751	
	BMS System	1,764	m2	\$	30	\$	52,929	رر ب	۲	01,731	
	BMS System Builders Work in Connection	1,764 5	m2 %	\$	30	\$ \$	52,929 27,290	ý 33	\$	32,190	
	•			\$	30			, JJ			
	•			\$ 	30			, 33			

Southland times - strengthening to 67% NBS - invercargill $\mbox{{\bf FEASIBILITY} ESTIMATE}$



						INDICATIVE RANGE								
							\$ LOW		Ī	\$ HIGH				
					'									
3.18	Fire Services													
	Allowance for replacement of existing plant and equipment	1,764	m2	\$	50	\$	88,215	\$ 60	\$	105,858				
							·			•				
	Subtotal - Fire Services		m2			\$	88,215		\$	105,858				
	Subtotal The Services		2			<u> </u>	00,213		1 7	100,000				
3.19	Electrical Services													
	Main Switchboard	1,764	m2	\$	25	\$	44,108			52,929				
	Distributions Boards	1,764	m2	\$	10	\$	17,643	\$ 13		22,054				
	Submains & Metering	1,764	m2	\$	5	\$	8,822			13,232				
	Cable Trays & Reticulation	1,764	m2	\$	5	\$	8,822	\$ 8		13,232				
	General & Emergency Lighting	1,764	m2	\$	65	\$	114,680	\$ 70		123,501				
	General power reticulation	1,764	m2	\$	20	\$	35,286	\$ 20	\$	35,286				
	Sesimic Bracing / Testing & Commissioning	1,764	m2	\$	5	\$	8,822	\$ 5	\$	8,822				
	Builders Work in Connection	5	%			\$	11,910		\$	13,460				
	Subtotal - Electrical Services		m2			\$	250,091		\$	282,516				
	Subtotal Electrical Sciences		2			<u> </u>	230,031		٢_	202,510				
2 20														
3.20	Lift & Escalators Allowages for minor refurbishment of existing lift car	1	Item	ć	19,000	ć	10,000	¢ 24 000	ć	24 000				
	Allowance for minor refurbishment of existing lift car	1	item	Ş	19,000	Þ	19,000	\$ 24,000	Ş	24,000				
	Subtotal - Lift & Escalators		m2			\$	19,000		\$	24,000				
3.21	Special Services													
	Allowance for Security System	1	Item	Ś	7,500	\$	7.500	\$ 9,000	\$	9,000				
	Communication Distribution Framework		Item		17,500			\$ 20,000		20,000				
	Subtotal - Special Services		m2			\$	25,000		\$	29,000				
3.22	Drainage Services													
	Existing													
	Subtotal - Electrical Services		m2			\$	-		\$	-				
									•					
3 23	External Works													
J.25	Existing													
	LASTING													
	Subtotal - External Works	-	m2			\$	-		\$	-				
2 24	Preliminary & General Charges	10	%			\$	439,000		\$	507,000				
	Contractors Margin	6	%			۶ \$	290,000		۶ \$	335,000				
	Contractors Margin	O .	70			Ų	230,000		Ą	333,000				
3.26	Incoming Service Connections													
	Power					\$	7,500		\$	10,000				
	Water					\$	6,500		\$	9,000				
	Drainage						Existing			Existing				
	Data, Telephone					\$	11,000		\$	12,000				
6	Abnormals													
-	Site Factors - Location						Excluded			Excluded				
	Site Factors - Sloping Site						Excluded			Excluded				
	Site Factors - Geotechnical Issues						Excluded			Excluded				
	Site Factors - Asbestos Removal					\$	100,000		\$	125,000				
	Firewalls to Boundaries					-	Excluded		7	Excluded				
	Primary Infrastructure Upgrades						Excluded			Excluded				
	Subtotal - Constructions Costs	1,764	m2	\$	2,968	\$	5,235,000	\$ 3,438	ć	6,064,000				

Southland times - strengthening to 67% NBS - invercargill $\mbox{{\bf FEASIBILITY} ESTIMATE}$



						IND	ICA	TIVE RA	NGE	
						\$ LOW				\$ HIGH
Z	Consent & Legal Resource & Building Consent Development Contributions			1.25%	\$	65,438 Excluded		1.25%	\$	75,800 Excluded
	Subtotal - Consent & Legal	1,764	m2	\$ 37	\$	66,000	\$	43	\$	76,000
<u>9</u>	Professional Fees PM Architectural Fees Quantity Surveyor Structural Engineer Mechanical Engineer Electrical Engineer Acoustic Engineer Other			15.00%	\$	795,000		15.00%	\$	921,000
	Subtotal - Professional Fees	1,764	m2	\$ 451	\$	795,000	\$	522	\$	921,000
<u>10</u>	Contingency Contingency Subtotal - On Costs	1,764	m2	\$ 20.0%	\$ \$	1,219,200 1,220,000	\$	20.0%	·	1,412,200 1,413,000
11	Escalation Escalation on construction, fees etc. up to tender from 1Q19 till 3Q19 Escalation on construction during construction at 50% of project duration (Say 12 months construction)	2% 2%			\$	124,460 93,791			\$	144,162 108,643
	Subtotal - Escalation	1,764	m2	\$ 124	\$	219,000	\$	147	\$	260,000
	TOTAL INDICATIVE PROJECT COST RANGE	1,764	m2	\$ 4,272	\$	7,535,000	\$	4,951	\$	8,734,000