

# southland MUSEUM AND ART GALLERY

NIHO O TE TANIWHA

Options Report

CONFIDENTIAL

November 2020

# Contents

- 1. INTRODUCTION ..... 3
- 2. EXECUTIVE SUMMARY..... 4
- 3. THE PROJECT BRIEF..... 6
- 4. DESIGN..... 8
- 5. OPTION ANALYSIS..... 10
- 6. COST ANALYSIS ..... 13
- 7. INDICATIVE TIMEFRAMES..... 15
- 8. NEXT STEPS ..... 16

# Appendices

- Appendix A Holmes Seismic Strengthening Report
- Appendix B Engeo Geotechnical Report
- Appendix C Warren and Mahoney Report
- Appendix D Powell Fenwick Fire Engineering Memo
- Appendix E Powel Fenwick Mechanical and Electrical Memo
- Appendix F RLB Cost Summary

# Version History


| Version     | Name        | Date             |
|-------------|-------------|------------------|
| V.1.1 Final | Tess Browne | 25 November 2020 |
|             |             |                  |

# Southland Museum and Art Gallery: Options Report

## 1. INTRODUCTION

### Background and Context

The Southland Museum and Art Gallery Niho o te Taniwha (referred to as the Pyramid in this report) was closed to the Public in 2018 due to its status as an Earthquake Prone Building. Consequently, the Invercargill City Council (ICC) engaged a project team to complete a report detailing the work and costs associated with re-opening the Pyramid. This report explores the options and identifies possible scenarios for ICC to consider in relation to the Pyramid.



**Note:** The option to strengthen the Pyramid to 100% NBS was not pursued further as it was deemed too complex from a construction perspective with a high cost premium and reduced building flexibility.

**Note:** Tim Walker Report relates to content in the Tim Walker Associates Strategic Review Reinventing the Southland Museum 2019.

## 2. EXECUTIVE SUMMARY

### Current Position

Prior to its closure, SMAG operated from a building referred to as the Pyramid. The Pyramid is made up of 4 different buildings that have been built in and around each other from 1942 through to a major redevelopment in 1990 to create the current three – level, pyramid shaped structure with a gross floor area of approximately 4,572m<sup>2</sup> and a total height of 22m. We note:

- The building sits below 34% NBS and is deemed earthquake prone. The main structural challenge is that each of the buildings behaves and moves independently of each other and in an earthquake event, the buildings will crash into each other causing significant damage
- Over the years maintenance and refurbishment works have been deferred while a decision was made on the building's future. These works are significant and have been addressed in this report to ensure Council has a clear understanding of the issues

### Our Approach

The project team was initially appointed to identify the minimum requirements to achieve seismic compliance enabling the Pyramid to re-open. On appointment, the team completed a site inspection in late August 2020. We then went through an information gathering phase where we reviewed all previous reports prepared for the building to identify information gaps and agree the scope of work.

Through this process, items identified included:

- **Importance Level 3.** The Pyramid needs to achieve Importance Level 3 seismic resilience as it is a structure that may contain crowds, have contents of high value to the community or pose a risk to large numbers of people in proximity
- **100%NBS.** A strengthening option to 100% NBS for the Pyramid was requested but could not be achieved due to design and ground conditions along with prohibitive costs
- **Refurbishment.** Over the years, work has been deferred and the general appearance internally is of the building being tired and old
- **Building Services.** Across the board, buildings services are nearing their end of life and there are inadequate environmental controls within spaces for the Collection which do not meet current museum standards.
- **Operating Costs.** Operating costs in the Pyramid will be high due to the inefficient and poor condition of building services.
- **Information technology** services are inadequate and not aligned with modern buildings
- **Layouts.** Floor plans have been adjusted over time to address the changing needs of the museum which has compromised interior layouts and circulation
- **Roof.** Despite maintenance work, the roof continues to leak
- **Storage.** There are serious issues with storage and access to storage including larger items which cannot be easily moved
- **Service Access.** Service access is difficult, there is no loading bay therefore the delivery, removal and setting up of exhibition space is difficult

Noting the above comments, we agreed the scope of work would be to assess a range of options from the minimum works to re-open the building (seismic strengthening only) through to full refurbishment of the Pyramid along with options for a replacement building. These options address costs and proposed timeframes to complete and are summarised below:



| Option   | Option A – 34% NBS and Minimum Refurbishment   | Option B – 67% NBS and Minimum Refurbishment   | Option C – 67% NBS and Full Refurbishment  | Option D – New Build (Location TBC) as per existing floor area   | Option E – New Build (location TBC) as per Tim Walker floor area   |
|--|--|--|--|--|--|
| <b>Makes the Building Safe?</b>                                    | <b>Address’s immediate life safety issues</b>  | <b>Significantly improves immediate life safety</b>  | <b>Significantly improves immediate life safety</b>  | <b>Yes</b>   | <b>Yes</b>   |
| <b>Deliver a Resilient Building?</b>                               | <b>Low level of seismic resilience</b><br>Highly likely building will be damaged and need internal repair after a significant earthquake. Demolition could be inevitable | <b>Moderate level seismic of resilience</b><br>Reduces but does not remove likelihood of future building closures after a significant earthquake | <b>Moderate level of seismic resilience</b><br>Reduces but does not remove likelihood of future building closures after a significant earthquake | <b>High level of seismic resilience</b><br>Reduced risk of building closure after a significant earthquake                 | <b>High level of seismic resilience</b><br>Reduced risk of building closure after a significant earthquake |
| <b>Address Deferred Refurbishment including building services?</b> | <b>NO</b><br>Refurbishment limited to areas of the building where strengthening work will be required  | <b>No</b><br>Refurbishment limited to areas of the building where strengthening work will be required  | <b>Yes</b>   | <b>Yes</b>   | <b>Yes</b>   |
| <b>Improves accessibility?</b>                                     | <b>Minor Improvement</b><br>Comply with building code only (ANARP)   | <b>Minor improvement</b><br>Comply with building code only (ANARP)   | <b>Significant improvement</b><br>Could be constraints with existing building  | <b>Yes</b><br>Best practice standards  | <b>Yes</b><br>Best practice standards  |
| <b>Future proofs the museum service?</b>                           | <b>No</b><br>Strengthening work will impact current layout to accommodate new structural requirements  | <b>No</b><br>Strengthening work will impact current layout to accommodate new structural requirements  | <b>Significant Improvement</b> but there may be compromises in layout to accommodate new structure requirements                                  | <b>Yes</b>   | <b>Yes</b>   |
| <b>Address’s Roof Issues?</b>                                      | <b>Yes</b>   | <b>Yes</b>   | <b>Yes</b>   | <b>Yes</b>   | <b>Yes</b>   |
| <b>Address’s storage concerns?</b>                                 | <b>No</b>  | <b>No</b>  | <b>Minor Improvement</b><br>Could make storage more efficient through design solutions   | <b>Moderate Improvement</b><br>New building layout will ensure efficient design which could resolve current storage issues | <b>Yes</b>   |
| <b>Estimated Cost</b>  | <b>\$25.3M</b>   | <b>\$26.6M</b>   | <b>\$52.5M</b>   | <b>\$75.4M</b>   | <b>\$85.5M</b>   |
| <b>Timeframes</b>  | <b>27 Months</b>   | <b>27 Months</b>   | <b>37 Months</b>   | <b>48 Months</b><br>*potential to be longer in a different location to the Pyramid   | <b>48 Months</b><br>*potential to be longer in a different location to the Pyramid                         |

### Key considerations

- Option A and B enable the Pyramid to be re-opened but the current building issues associated with deferred maintenance / end of life services will continue to be problematic and funding will have to be set aside to stage the works over a number of years which will be disruptive. This is the cheapest option with the shortest timeframe but delivers the least optimal outcome.
- Option C provides a moderate level of building resilience and address's refurbishment / building services requirements. This option is mid-range in terms of cost and programme.
- Option D and E will provide Council with a purpose built, seismically resilience building future proofed museum however it comes with the highest cost and longest timeframe for delivery.

### Next Steps

Once a preferred option has been identified a design and service level brief will be required to ensure the building is developed will align with Councils vision for the future museum

The brief will set the vision for the project and inform the next phases of procurement, design development, construction, and fitout to ensure the projects objectives are met

Establishment of a project governance structure will be critical to support development of the design and service brief.

## 3. THE PROJECT BRIEF

### Structural Strengthening and Minimum Refurbishment Works (Option A and B)

At the outset of the project, the brief was clear – identify the minimum requirements to re-open SMAG whilst achieving seismic compliance with New Building Standards.

Under this option, scope was limited to the following areas:

- Exploration of structural strengthening options to achieve 34, 67 or 100% NBS. The NBS % is a rating given to a building expressed as a percentage of New Building Standards (NBS) achieved based on an assessment of the seismic performance. It is relation to the performance of a new building on the same site with respect to life safety. The three % values are industry adopted limits which help categorise buildings into three risk profiles:
  - <33% is High Risk
  - Between 33 and 67 is Moderate Risk
  - Greater than 67% is Low Risk
- Geotechnical investigations to understand ground conditions and existing foundations
- Refurbishment works required to remediate areas of the building that were strengthened only, no further refurbishment / betterment work was to be considered
- Compliance with the Building Code as any strengthening work would trigger a building consent, specifically:
  - Fire Safety
  - Emergency egress
  - Accessibility

The project team was instructed **NOT** to consider the following factors when assessing this option:

- Any architectural changes to improve the existing layout
- Full refurbishment of the building. Refurbishment limited to the areas impacted by strengthening works only
- Replacement of the existing building services beyond localised areas impacted by the strengthening works. No consideration of Whole of Life Costs or ongoing maintenance requirements for the building's services
- Improved vertical access via stairs and lifts
- Changes to the current environmental control system
- IT upgrade
- Acoustic improvements
- Compliance with Museum Standards
- New Exhibition space

### **67% NBS and Full Refurbishment / New Build (Option C, D, and E)**

Once the project team completed an assessment of options A and B, ICC expanded the project brief and requested the team consider the following possibilities:

- Structurally strengthen the Pyramid to 67% NBS and complete a full refurbishment of the building to incorporate all the exclusions previously listed
- Demolish the Pyramid Building and construct a replacement building with the same area as the current museum (4,572 sqm). In terms of location, the construction cost difference between building on the same footprint as the Pyramid or at a new location in Invercargill was marginal. However, there are some nuances around remaining in the current location versus moving to a new location which are discussed further in the report (Section 5, Options Analysis)
- Demolish the Pyramid building and construct a replacement building with the same footprint identified in the Tim Walker report (5,300 sqm). In terms of location, the construction cost difference between building on the footprint of the Pyramid or at a new location in Invercargill was marginal. However, there are some nuances around remaining in the current location

versus moving to a new location which are discussed further in the report (Section 5, Options Analysis)

Under option C, D and E, the items excluded from the original brief now been allowed for and the costs associated with Options C, D and E are comprehensive and would future proof the building

### **Key Considerations**

Factors considered when assessing each of the options above included:

- **Life Safety.** Is the building safe to occupy?
- **Building resilience.** Following an earthquake, is the structural strengthening sufficient to enable the building to re-open with minimal repairs
- **Deferred Maintenance.** Resolution of existing building issues including HVAC, electrical and IT
- **Improved Accessibility.** Does the work provide improved accessibility access?
- **Building Flexibility.** Does the work future proof the building and provide opportunities for a 21<sup>st</sup> century space?
- **Roof Issues.** Will the work improve the issues with the roof and ongoing leaks?
- **Storage.** Will the work address storage problems?

## 4. DESIGN

The project team comprised of:

- The Building Intelligence Group – Project Managers
- Holmes Consulting - Structural Engineers
- Engeo – Geotechnical Engineers
- Rider Levett Bucknell – Quantity Surveyors
- Warren and Mahoney – Architectural Services
- Powell Fenwick – Building Services (Mechanical, Electrical, Fire)

### Structural Remediation

Holmes Consulting was appointed to assess the Pyramid and provide a structural solution summarised below as follows:

#### Strengthening to 34% and 67% NBS

- The structural analysis confirmed the Pyramid building can be strengthened to 34 and 67% NBS. Strengthening will include new reinforced concrete walls, new reinforced concrete foundation beams and new connections to the ceiling diaphragm. The primary differences between the 34% and 67% schemes is the 67% scheme will require:
  - Additional concrete walls and foundation beams
  - Increased first and second floor concrete slab diaphragm strengthening

Please refer to Holmes Consulting Structural Report (Appendix A) for detailed engineering information including proposed location of new walls and foundations.

#### Strengthening to 100% NBS

- Achieving 100% NBS seismic rating would involve significant modifications to the strengthening scheme proposed for the Pyramid that would have serious implications on the functionality of the building.
- In addition, geotechnical analysis has noted that liquefaction of the ground below the building could become an issue as ground shaking approaches 100%NBS. To achieve 100% NBS on the Pyramid, its likely ground improvement or significant foundation work would be required under the building.

- Taking the structural and geotechnical factors into account, the option to strengthen the Pyramid to 100% NBS was not pursued further as it was deemed too complex from a construction perspective with a high cost premium and reduced building flexibility.

### Pyramid Cladding Structure

As part of the seismic assessment of the Pyramid structure a deficiency in the snow loading capacity of the steel frame was identified. Addressing these deficiencies is mandatory to comply with the snow loading section of the NZ Building Code. To address the snow loading deficiency, the scope of work is invasive and will include:

- New SHS strut members around equal angle x-bracing around the base of the Pyramid steel frame
- Base plate connection strengthening of the existing steel frame to the concrete perimeter frame
- Removal of the Pyramid cladding will be required to provide access to strengthen these connections. Replacement of new roofing material has been included within the cost estimates

### Geotechnical

Engeo Consulting was appointed to complete geotechnical investigations. Their findings are included at Appendix B and summarised as follows:

- Current foundation conditions including type and bearing capacity of existing foundations
- Liquefaction susceptibility assessment
- Geotechnical parameters for design of new foundations to support structural strengthening works

Work completed by Engeo include observation of two test pits to a depth of 2.0-2.5m and monitoring of Cone Penetrometer Tests to depths between 7.1 – 7.5m and their findings concluded:

- Liquefaction is unlikely at 34% NBS and very minor liquefaction anticipated at 67% NBS. Liquefaction will be a consideration at 100% NBS.
- Foundation conditions are reasonably good, and they will not drive the structural design

## Architectural

Warren and Mahoney were appointed to provide a scope of architectural and interior refurbishment that would be required for 34% and 67% NBS only. Their scope assumed the current museum layout was to remain unchanged and museum displays and BOH layouts were not altered. They were limited to identification of:

- Refurbishment works required in areas of the building where structural strengthening was to occur
- Compliance with NZ Building Code in particular accessibility, fire and upgrades associated with those services.

Please refer to Warren and Mahoney's report at Appendix C which identifies refurbishment works required as a result of the structural strengthening works. The output from these reports has been incorporated into the cost estimates for these options.

Under options C, D and E it should be noted Warren and Mahoney did not provide any architectural input into their preparation. Option C has been prepared using the information from option A and B and square meter rates were used for option D and E

## Building Services Design

Powell Fenwick, the Building Services Engineers have prepared a design memo addressing fire compliance, mechanical and electrical requirements (see Appendix D+E). Under fire compliance the report identifies the work required to comply with NZ Building Code. The building services memo identifies work required to address NZ Building Code requirements and also identifies additional work required to address "fit for purpose" issues.

It should be noted sustainable design principles have not been considered for option A and B but the estimates for option C, D and E do allow for some sustainable design principles to be explored.

## 5. OPTION ANALYSIS

The Pyramid building is earthquake prone and while not functionally obsolete, presents significant operational and financial challenges. While some of these challenges have been considered earlier in this report, we provide additional context around the options presented relevant to these challenges.

### Option A – 34% NBS and Minimal Refurbishment

Under this option the building would be strengthened to 34% NBS allowing it to re-open. This option address's the structural issues of highest concern but given the low seismic resilience the building is likely to be damaged and in need of significant repair or demolition after an earthquake.

The strengthening work required would include:

- Installation of additional foundations and structural walls to support the building
- Tying of existing floors together and connecting them to new walls
- Strengthening of the roof frame and replacement of the roof material
- Upgrade to the fire safety system to comply with the NZ Building Code
- Improved accessibility compliance (ANARP)
- Refurbishment limited to areas where structural walls occurred – ceilings and floors

| Advantages   | Disadvantages   |
|--|---|
| Lowest cost option                                     | 34% NBS - Low level building resilience – could be a risk remediation work required to the building following an earthquake |
| New roof which will address ongoing maintenance issues | Minimum refurbishment works – building will look and feel the same following an earthquake. No future proofing              |
|  | Will not address historic issues associated with access, storage, HVAC system, accessibility, IT                            |
|  | Will not meet museum standards for storage collection   |
|  | Once building is open, work will continually be required to maintain building services                                      |
|  | Significant cost to only achieve 34% NBS with minimal refurbishment work  |
|  | Structural remediation projects are inherently risky and have a higher risk of cost blowouts.                               |

### Option B – 67% NBS and Minimal Refurbishment

Under this option the building would be strengthened to approximately 67% New Building Standard. This option addresses the structural issues of highest concern and increases the buildings ability to withstand an earthquake. It will also reduce the repair requirements to the building following an earthquake.

The strengthening work required would include:

- Installation of new foundations and structural walls to support the building.
- Tying existing floors together and connecting them to new walls (over and above the 34% option)
- Removal of all brickwork from the 1940's building
- Strengthening of the roof frame and replacement of the roof material
- Upgrade to the fire safety system to comply with the NZ Building Code
- Improved accessibility compliance (ANARP)
- Refurbishment limited to areas where structural walls occurred – ceilings and floors

| Advantages   | Disadvantages  |
|--|--|
| Higher NBS rating and increased building resilience    | Minimum refurbishment works – building will look and feel the same following an earthquake. No future proofing |
| New roof which will address ongoing maintenance issues | Increase to number of structural walls which could potentially impact functionality of layout                  |
|  | Will not address historic issues associated with access, storage, HVAC system, accessibility, IT               |
|  | Will not meet museum standards for storage collection  |
|  | Once building is open, work will continually be required to maintain building services                         |
|  | Significant cost to only achieve 67% NBS with minimal refurbishment work                                       |
|  | Structural remediation projects are inherently risky and have a higher risk of cost blowouts                   |

### Option C- 67% NBS and Full Refurbishment

Under this option the building would be strengthened to 67% New Building Standard and fully refurbished throughout. The structural works would be as per the information presented under Option B and the refurbishment scope would include:

- Full interior refurbishment including replacement of the Café
- Replacement of the existing Heating Ventilation and Air Conditioning System – upgrade would include compliance with museum standards
- Replacement of electrical services including new lighting throughout
- Upgrade to Fire Protection System
- Improved vertical circulation including new stairs and accessible lift
- Full IT upgrade
- New exhibition fitout
- New furniture, fittings and equipment (FF+E)
- General future proofing and durability

| Advantages  | Disadvantages  |
|---|--|
| Higher NBS rating and increased building resilience   | Increase to number of structural walls could potentially impact functionality of layout this but should be resolvable through design however compromises may be required               |
| New roof which will address ongoing maintenance issues  | Availability of storage is identified as an issue for staff. The refurbished building would be the same size as the existing building therefore storage may continue to be problematic |
| Fully refurbished building which will address all existing issues including access, HAVAC, accessibility. IT. | Structural remediation and refurbishment projects are inherently risky and have a much higher chance of cost blowouts.   |
| New exhibition fitout and FFE   |  |

### Option D - Demolish Pyramid Building - Replacement Building with the same area as Existing Museum

No design information has been prepared for this option. Costs have been developed on a sqm basis and assume a “mid-range” level of construction and fitout. As costs for both options are identical, they have been grouped together but there are some nuances highlighted as follows:



#### Demolish the Pyramid and construct a new building on the same footprint at Queens Park

- This option assumes the existing Pyramid would be demolished and a replacement building positioned within the existing footprint.

The Park Site Reserves Management Act allows for this option to be implemented and it would comply with the District Plan.

| Advantages   | Disadvantages   |
|--|---|
| 100% NBS rating to Importance Level 3 Standard. High level of building resilience                      | Demolition works can be risky and there can be unforeseen costs associated with environmental issues such as asbestos/contaminated ground |
| New building will be designed efficiently to reflect requirements of a 21 <sup>st</sup> century museum | Could potentially be ongoing storage issues as the floor area is not increasing but this could be resolved through design                 |
| None of the constraints associated with refurbishing an existing building                              |   |



#### Demolish the Pyramid and construct a new building in the CBD

- For the purposes of this option, it is assumed a new building would be located within the Priority Redevelopment area of the CBD which includes the Invercargill Central Development.
- A museum would be considered a communal activity under the District Plan and thereby permitted in the City Centre but subject to compliance with specific design standards.
- **Should this option be taken forward, we would strongly recommend ICC undertake some initial space and location planning to determine suitability of site options for this activity.**



| Advantages   | Disadvantages   |
|--|---|
| 100% NBS rating to Importance Level 3 Standard. High level of building resilience                      | Demolition works can be risky and there can be unforeseen costs associated with environmental issues such as asbestos / contaminated ground |
| New building will be designed efficiently to reflect requirements of a 21 <sup>st</sup> Century museum | Potential design constraints associated with a CBD development which would need to be tested before committing to this option               |
| None of the constraints associated with refurbishing an existing building                              | Could potentially be ongoing storage issues as the floor area is not increasing but this could be resolved through design                   |

### Option E - Demolish Pyramid Building and Replacement Building with the Floor Area identified in the Tim Walker Report

No design information has been prepared for this option. Costs have been developed on a sqm basis and assume a “mid-range” level of construction and fitout. As costs for both options are identical, they have been grouped together but there are some nuances highlighted as follows:

1

#### Demolish the Pyramid and construct a new building on a larger footprint at Queens Park

- This option assumes the existing Pyramid would be demolished and a replacement building positioned within the same area as the existing building. The Park Site Reserves Management Act allows for this option to be implemented and an amendment has been introduced to extend the existing footprint. This option will comply with the District Plan.

| Advantages   | Disadvantages  |
|--|--|
| 100% NBS rating to Importance Level 3 Standard. High level of building resilience                      | Demolition works can be risky and there can be unforeseen costs associated with environmental issues                                 |
| New building will be designed efficiently to reflect requirements of a 21 <sup>st</sup> century museum | Increased building footprint results in increased construction costs – requirement for additional floor area should be stress tested |
| None of the constraints associated with refurbishing an existing building                              |  |

2

#### Demolish the Pyramid and construct a new building in the CBD

- For the purposes of this option, it is assumed a new building would be located within the Priority redevelopment area of the CBD which includes the Invercargill Central development.
- A museum would be considered a communal activity under the District Plan and thereby permitted in the City Centre. Albeit subject to compliance with specific design standards.
- Should this option be taken forward, we would strongly recommend ICC undertake some initial space and location planning to determine suitability of site options for this activity.**

| Advantages   | Disadvantages  |
|--|--|
| 100% NBS rating to Importance Level 3 Standard. High level of building resilience                      | Demolition works can be risky and there can be unforeseen costs associated with environmental issues                                 |
| New building will be designed efficiently to reflect requirements of a 21 <sup>st</sup> Century museum | Potential design constraints associated with the CBD development which would need to be tested before committing to this option      |
| None of the constraints associated with refurbishing an existing building                              | Increased building footprint results in increased construction costs – requirement for additional floor area should be stress tested |

## 6. COST ANALYSIS

Cost estimates for each option have been prepared by Rider Levett Bucknell (RLB) and is included at Appendix F. Please also refer to RLB’s exclusions associated with each option.

### General Commentary

- Across all options, an allowance of \$4.5M has been identified to address collection storage requirements for the existing collection. This allowance is untested and should be viewed as an indicative figure only until the scope is resolved
- Option A, B and C carry a high proportion of risk due to the nature of refurbishment works. To address this, the quantity surveyor has accounted for risk in their estimate and project contingencies, but further design work will need to be carried out to verify the figures presented. The next phase of design will need to focus on the refurbishment component of option C as the structural costs are more clearly understood.
- Under option D and E, the quantity surveyor has estimated the project using “medium range” sqm rates.
- Option C, D and E have an allowance for Museum fitout, Furniture Fittings and Equipment and IT upgrades. The allowances have been benchmarked by RLB based on recent experience, but the scope could be refined once the brief becomes clearer
- **Under option D and E should Council decide to relocate from Queens Park, purchase price for land will need to be a consideration and is currently excluded**
- Costs have been escalated to Quarter 4 2024, should the project extend beyond that period additional costs will be incurred
- All prices are exclusive of GST

### Summary of Capital Costs

A summary of the development costs associated with each option are detailed below and further analysis is provided in the sections below.

|                         | Option A – 34% NBS and Minimum Refurbishment | Option B – 67% NBS and Minimum Refurbishment | Option C – 67% NBS and Full Refurbishment | Option D – New Build (Location TBC) | Option E – New Build as per Tim Walker area |
|-------------------------|--|--|---|-------------------------------------|---|
| <b>Gross Floor Area</b> | 4,572 sqm                                    | 4,572 sqm                                    | 4,572 sqm                                 | 4,572 sqm                           | 5,300 sqm                                   |
| <b>Capital Cost</b>     | \$25.36M                                     | \$26.67M                                     | \$52.52M                                  | \$75.48M                            | \$85.5M                                     |

**Option A – 34% NBS and Minimal Refurbishment**

| Item                        | Total           |
|-----------------------------|-----------------|
| Construction Works          | \$13.31M        |
| Temporary Storage           | \$4.5M          |
| Market Escalation (Q4 2024) | \$1.35M         |
| Professional Fees           | \$2.75M         |
| Local Authority Charges     | \$450K          |
| Contingency                 | \$3M            |
| <b>TOTAL</b>                | <b>\$25.36M</b> |

**Option B – 67% NBS and Minimal Refurbishment**

| Item                        | Total           |
|-----------------------------|-----------------|
| Construction Works          | \$14.19M        |
| Temporary Storage           | \$4.5M          |
| Market Escalation (Q4 2024) | \$1.43M         |
| Professional Fees           | \$2.9M          |
| Local Authority Charges     | \$450K          |
| Contingency                 | \$3.2M          |
| <b>TOTAL</b>                | <b>\$26.67M</b> |

**Option C – 67% NBS and Full Refurbishment**

| Item                        | Total           |
|-----------------------------|-----------------|
| Construction Works          | \$26.69M        |
| Specialist Fitout Works     | \$7.9M          |
| Temporary Storage           | \$4.5M          |
| Market Escalation (Q4 2024) | \$2.45M         |
| Professional Fees           | \$4.6M          |
| Local Authority Charges     | \$620K          |
| Contingency                 | \$5.76M         |
| <b>TOTAL</b>                | <b>\$52.52M</b> |

**Option D - Demolish Pyramid Building - Replacement Building with the same area as Existing Museum**

| Item                        | Total           |
|-----------------------------|-----------------|
| Construction Works          | \$36.38M        |
| Specialist Fitout Works     | \$7.9M          |
| Temporary Storage           | \$4.5M          |
| Market Escalation (Q4 2024) | \$5.37M         |
| Professional Fees           | \$7.8M          |
| Local Authority Charges     | \$950K          |
| Contingency                 | \$12.58M        |
| <b>TOTAL</b>                | <b>\$75.48M</b> |

**Option E - Demolish Pyramid Building and Replacement Building with the Floor Area identified in the Tim Walker Report**

| Item                        | Total           |
|-----------------------------|-----------------|
| Construction Works          | \$41.74M        |
| Specialist Fitout Works     | \$9.13M         |
| Temporary Storage           | \$4.5M          |
| Market Escalation (Q4 2024) | \$6.09M         |
| Professional Fees           | \$8.76M         |
| Local Authority Charges     | \$1.08K         |
| Contingency                 | \$14.26M        |
| <b>TOTAL</b>                | <b>\$85.56M</b> |

## 7. INDICATIVE TIMEFRAMES

To assist with decision making, indicative timeframes have been provided for each option and are summarised below:

### Option A and B

- Option A and B are grouped together and have the shortest timeframe of all options (2 years and 3 months).
- The shorter timeframe is because no refurbishment work is proposed therefore a reduced design period is envisaged as there would be minimal engagement with stakeholder groups

### Option C

- The programme proposed for option C is 3 years. This extension to option a and b reflects the refurbishment works to the building.
- Key to achieving this timeframe would be the establishment of a project governance process and stakeholder management plan to clearly understand design and service level requirements enabling design to progress. Well understood project approval gateways will also be critical.

### Option D and E

The timeframe proposed for option D and E is 4 years. This may seem long, but a new building introduces additional steps including:

- Resolution of design options (no constraints associated with existing building) to ensure a more functional, fit-for-purpose and future proofed museum
- Demolition of the Pyramid (if the museum remains at Queens Park) before construction can commence on a new building
- Resolution of design requirements / interface with other buildings / projects if the museum moved into the CBD
- Should the Museum move to another location there could also be a risk the programme could extend beyond 48 months as a new site will need to be identified which could slow the overall process

| Option                            | A         | B         | C         | D         | E         |
|-----------------------------------|-----------|-----------|-----------|-----------|-----------|
| <b>Designs</b>                    | 8 months  | 8 months  | 11 months | 14 months | 14 months |
| <b>Tendering &amp; Consenting</b> | 4 months  | 4 months  | 4 months  | 4 months  | 4 months  |
| <b>Construction</b>               | 15 months | 15 months | 21 months | 28 months | 28 months |
| <b>Duration</b>                   | 27 months | 27 months | 37 months | 46 months | 46 months |

### General


It is assumed, the museum collection will be removed from the Pyramid and relocated into storage in parallel with design development under each of the options provided. This will be critical to maintaining programme and Council should not overlook this package of work as it will be time consuming.

## 8. NEXT STEPS

Once a preferred option has been identified a design and service level brief will be required to ensure the building to be developed will align with Council vision for the future museum

The brief will set the vision for the project and inform the next phases of procurement, design development, construction, and fitout to ensure the projects objectives are met

Establishment of a project governance structure will be critical to support development of the design and service brief.



# Southland Museum & Art Gallery

108 Gala Street  
Queens Park  
Invercargill 9810

## Seismic Strengthening Options Summary Report

**Report**

Southland Museum & Art Gallery - Seismic Strengthening Options Summary Report

Prepared For:  
Invercargill City Council

Date: 13 November 2020  
Project No: 140859.13  
Revision No: 1

Prepared By:



Mark Hannah  
PROJECT ENGINEER  
Holmes Consulting LP

Reviewed By:



Tony Galavazi  
BUSINESS MANAGER  
Holmes Consulting LP



### Report Issue Register

| DATE       | REV. NO. | REASON FOR ISSUE |
|------------|----------|------------------|
| 13/11/2020 | 1        | Information      |
|            |          |                  |
|            |          |                  |
|            |          |                  |
|            |          |                  |
|            |          |                  |
|            |          |                  |
|            |          |                  |
|            |          |                  |
|            |          |                  |

## CONTENTS

|     |   |   |
|-----|---|---|
| 1   | Introduction .....                          | 1 |
| 2   | Limitations .....                           | 1 |
| 3   | Building Areas .....                        | 1 |
| 4   | 1940s Section .....                         | 2 |
| 4.1 | 34% NBS Strengthening Scheme .....          | 3 |
| 4.2 | 67% NBS Strengthening Scheme .....          | 3 |
| 4.3 | 100% NBS Strengthening Scheme .....         | 3 |
| 5   | 1988 and 1960s Section .....                | 4 |
| 5.1 | 34% NBS Seismic Strengthening Scheme .....  | 4 |
| 5.2 | 67% NBS Seismic Strengthening Scheme .....  | 5 |
| 5.3 | 100% NBS Seismic Strengthening Scheme ..... | 5 |
| 6   | Pyramid Cladding Structure .....            | 5 |
| 6.1 | Strengthening Scheme .....                  | 5 |
| 7   | Conclusion.....                             | 6 |

## APPENDIX A – Seismic Strengthening Sketches

## **1 INTRODUCTION**

Holmes Consulting LP have been engaged by Invercargill City Council to conduct a detailed structural review of the Southland Museum and Art Gallery building in Invercargill.

The extent of work to date has involved:

- A detailed review of the available existing structural drawings and reports
- Observations of the exposed structure via a site visit and further visual observations available from the provided Matterport scan
- Assessing the capacity of the existing building
- Providing high level strengthening schemes targeting 34, 67 and 100% NBS seismic capacity

## **2 LIMITATIONS**

Findings presented as a part of this project are for the sole use of Invercargill City Council in its evaluation of the subject properties. The findings are not intended for use by other parties, and may not contain sufficient information for the purposes of other parties or other uses.

Our observations have been visual only and are limited to representative samples. Our observations have been restricted to structural aspects only. Waterproofing elements, electrical and mechanical equipment, fire protection and safety systems, service connections, water supplies and sanitary fittings have not been inspected or reviewed, and secondary elements such as windows and fittings have not generally been reviewed.

Our professional services are performed using a degree of care and skill normally exercised, under similar circumstances, by reputable consultants practicing in this field at this time. No other warranty, expressed or implied, is made as to the professional advice presented in this report.

## **3 BUILDING AREAS**

For our assessment and strengthening schemes we have addressed the building as 3 separate areas:

- the original 1940s building
- the combination of the 1988 and 1960s sections of the building which encapsulates the 1940s building
- the lightweight pyramid cladding structure which covers all the building areas

Refer to Figure 1 for a depiction of the respective building areas.

This division of building areas has been chosen following the decision to keep the 1940s structure seismically separated from the rest of the building. The 1960s and 1988 areas of the building are flexible frame structures which behave differently to the stiffer 1940s wall structure. The floor levels of the 1940s section of the building do not align with the rest of the structure which would make connecting the 1940s section to the rest of the building problematic. This led to the decision to keep these sections of the building seismically separated.




Figure 1 - Designation of building areas at ground floor

#### 4 1940S SECTION

The 1940s section of the building is the oldest section. It is a 2-storey reinforced concrete frame and wall structure. It has a timber framed roof which is supported by reinforced concrete walls and columns. It has a reinforced concrete floor at the suspended first-floor level and a suspended timber floor at ground level. The building is founded on concrete pad footings located under the concrete walls.

Seismic loads are transmitted by the timber roof and the first-floor concrete diaphragm to the perimeter reinforced concrete walls which then provide the lateral load resisting system.

The building is clad with an external layer of brick veneer and it is unknown how well this has been connected to the reinforced concrete structure.

#### **4.1 34% NBS Strengthening Scheme**

The 1940s building was assessed using the NZSEE Seismic Assessment Guidelines (2017) and found to have a seismic capacity of less than 34% NBS.

To achieve 34% NBS seismic strength the following strengthening works are required:

- New reinforced concrete walls cast against the interior face of the existing walls throughout the building at both levels
- New reinforced concrete foundation beams under the majority of the perimeter walls and central lobby / stair area
- Strengthening of the first-floor concrete slab – details to be confirmed but will likely involve drilling and epoxying and/or chasing and grouting reinforcing bars into the concrete slab
- New reinforced concrete overlay to the first-floor concrete slab at the east and west ends of the building
- New flat plywood ceiling diaphragm at the underside of the existing timber roof members
- New steel collector beams / straps to connect the new plywood ceiling diaphragm to the new concrete walls
- Either fixing the existing brick veneer to the new existing reinforced concrete walls with Helifix brick ties or similar, or the removal of the brick veneer. The extent of this can be modified with some areas of the veneer fixed and others removed as desired.

Refer to the appended structural sketches SSK11-15 for the 34%NBS seismic strengthening scheme plans.

#### **4.2 67% NBS Strengthening Scheme**

To achieve 67% NBS seismic strength the following strengthening works in addition to or modifying the 34% NBS scheme are required:

- Removal of the brick veneer around the building perimeter to reduce the seismic weight of the building
- Either remove the existing brick / concrete parapet to roof level or brace it back into the roof with new steel bracing structure

Refer to the appended structural sketches SSK16-20 for the 67%NBS seismic strengthening scheme plans.

#### **4.3 100% NBS Strengthening Scheme**

The aim of achieving 100% NBS seismic strengthening was not pursued in the same level of detail as 34% and 67% NBS as it would involve significant modifications to the strengthening scheme. A plywood roof diaphragm would not provide adequate capacity and steel bracing or similar would be required. Additionally, all existing walls would need to be braced to accommodate out-of-plane (face loading) demands.

Initial geotechnical analysis has noted that liquefaction of the ground below the building could become an issue as ground shaking approaches 100%NBS. The %NBS strength of the building is dependent on the ground conditions and it is likely that ground improvement or significant foundation works would be required to achieve a seismic strength of 100%NBS accounting for the liquefaction risk.

## **5 1988 AND 1960S SECTION**

In the 1960s an addition was made to the existing 1940s structure. This addition was constructed using reinforced concrete frames with a concrete Double Tee floor at the first floor. The structure was founded on concrete pad foundations. This addition was not connected to the 1940s structure but was constructed with a nominal 50mm (to be confirmed) separation between the buildings.

In 1988 a larger addition was constructed. This addition encapsulated the existing 1940s and 1960s buildings by constructing a reinforced concrete frame structure around the existing building. A new Rib-and-Timber concrete floor was added to the north-east area where a structure had been constructed in 1959 but was removed as part of this 1988 addition. A new concrete Rib-and-Timber floor was added at the second-floor level that extended over the existing 1940s and 1960s roofs.

The 1988 construction was tied into the 1960s addition, but seismic separations were maintained around the 1940s building, effectively leaving the 1940s building as an independent structure inside the rest of the building.

### **5.1 34% NBS Seismic Strengthening Scheme**

The 1988 and 1960s sections of the building were assessed using the NZSEE Seismic Assessment Guidelines (2017) and found to have a seismic capacity of less than 34% NBS.

To achieve 34% NBS seismic strength the following strengthening works are required:

- New reinforced concrete walls cast between the existing concrete frames throughout the building at both levels. The location of these walls has been chosen to minimise disruption to the current operable space
- New reinforced concrete foundation beams under all new concrete walls
- Removal of the existing infill walls in the north gallery space at the ground floor level
- Tying of the 1960s Double Tee reinforced concrete first-floor slab to the surrounding concrete frames and 1988 Rib-and-Timber concrete floor slab
- Localised chasing of a steel plate or reinforcing bars around the existing stair void in the 1960s first floor slab
- New concrete collector beams to the first and second floor slabs between the concrete ribs / Double Tee webs
- New concrete collector beam to the perimeter of the building cast above and tied into the existing perimeter frame
- Investigation and potential widening of the existing seismic separation between the 1988 and 1940s areas of the building

Refer to the appended structural sketches SSK6, 7 and 21-23 for the 34%NBS seismic strengthening scheme plans.

## 5.2 67% NBS Seismic Strengthening Scheme

To achieve 67% NBS seismic strength the following strengthening works in addition to or modifying the 34% NBS scheme are required:

- Additional concrete walls and accompanying foundation beams throughout the building
- Increased first and second floor concrete slab diaphragm strengthening

Details of the diaphragm strengthening are to be confirmed. The extent of the strengthening required will be dependent on calculations that are completed during the Developed Design phase of the project.

Refer to the appended structural sketches SSK24-25 for the 34%NBS seismic strengthening scheme plans.

## 5.3 100% NBS Seismic Strengthening Scheme

The 100% NBS seismic strengthening scheme was not pursued for the 1960s/1988 section of the building in detail as the overall building capacity would be limited by the 1940s section of the building as the lowest seismic rating for a building area must be used for the whole building.

Additional reinforced concrete walls and foundations would likely be required if 100% NBS seismic strengthening were to be pursued. Significant additional strengthening to the first and second floor concrete slab diaphragms would be required.

As with the 1940s section of the building, the strength of the 1960s/1988 section would also be dependent on the liquefaction risk at near 100%NBS ground shaking levels. The foundations for this area of the building are localised reinforced concrete pads under the columns which may be susceptible to differential settlements should liquefaction occur. To achieve 100%NBS seismic strength it is likely that ground improvement and / or strengthening the foundations with connecting beams between the existing pads would be required.

## 6 PYRAMID CLADDING STRUCTURE

As part of the 1988 construction work a lightweight pyramid shaped cladding roof structure was constructed over the full building envelope. This structure is constructed with lightweight cladding panels which are supported on a steel frame. The steel frame is supported by the reinforced concrete perimeter frame constructed in 1988.

### 6.1 Strengthening Scheme

As part of the seismic assessment of the pyramid structure a deficiency in the snow loading capacity of the steel frame was identified. Addressing these deficiencies is mandatory to comply with the snow loading section of the Building Code. The benefit of completing this work is that the seismic strength of the pyramid steel support frame becomes greater than 100% NBS.

To address the snow loading deficiency the following strengthening work is required:

- New SHS strut members and equal angle x-bracing around the base of the pyramid steel frame
- Base plate connection strengthening of the existing steel frame to the concrete perimeter frame. Removal of the pyramid cladding will be required to provide access to be able to strengthen these connections between the steel frames and the concrete perimeter frame.

A new lightweight cladding system is being considered as part of the architectural works for the pyramid. To accommodate the change in cladding system new steel purlins will be required to support the cladding and span over the existing steel frame.

Refer to the appended structural sketches SSK08-09 for the seismic strengthening scheme plans.



## **7 CONCLUSION**


Preliminary options have been presented in this report for achieving 34% NBS and 67% NBS seismic strengthening for the Southland Museum and Art Gallery in Invercargill. During the consultation process the investigation of 100% NBS seismic strengthening was discontinued due to the step change in the amount of structural strengthening required and potential geotechnical issues with liquefaction.

We typically recommend our clients consider strengthening to at least 67%NBS, although we appreciate the final decision depends on a number of factors. The information we have provided in this report will help to inform this decision, but the level of seismic strengthening chosen is at the discretion of Invercargill City Council.

Our strengthening design is currently at a Preliminary Design level of detail. This has confirmed the major structural components and given descriptions of the likely detail. To achieve a Building Consent and For Construction documents we will need to progress the design through the Developed and Detailed Design stages.


**Appendix A - Seismic Strengthening Sketches**





EXISTING BUILDING STRUCTURE






Note - upper level pyramid support steel hidden for clarity

STAGE 1 - REMOVAL OF 1959 WALLS






Note - upper level pyramid support steel hidden for clarity

STAGE 2 - GROUND FLOOR WALLS






Note - upper level pyramid support steel hidden for clarity

STAGE 3 - FIRST FLOOR WALLS





## 34%NBS with Brick Veneer




### Legend:

FP1 - 2500x2500x600 deep insitu concrete foundation pad. Allow for 120kg/m<sup>3</sup> reinforcing.

FB1 - 1200x600 deep insitu concrete foundation beam. Allow for 110kg/m<sup>3</sup> longitudinal reinforcing and 35kg/m<sup>3</sup> stirrup reinforcing.


FB2 - 2000x600 deep insitu concrete foundation beam. Allow for 100kg/m<sup>3</sup> longitudinal reinforcing and 35kg/m<sup>3</sup> stirrup reinforcing.



|  |  |                         |
|--|--|-------------------------|
|  | PROJECT: <u>Southland Museum Redevelopment</u> |                         |
|  | JOB NO: <u>140859.13</u>                       | DATE: <u>14/10/2020</u> |
|  | SSK: <u>11</u>                                 | REV: <u>1</u>           |



## 34%NBS with Brick Veneer



### Legend:

IW1 - 200 thick insitu concrete skin wall.  
Allow for 120kg/m<sup>3</sup> reinforcing.


### Note:

Fix existing brick veneer to existing concrete wall. e.g. Helifix fasteners or drill and epoxy threaded rod at 400crs e.w. Alternatively, remove brick veneer.

Ground Floor Plan

|  |  |
|--|--|
|  | PROJECT: <u>Southland Museum Redevelopment</u>   |
|  | JOB NO: <u>140859.13</u> DATE: <u>14/10/2020</u> |
|  | SSK: <u>12</u> REV: <u>1</u>                     |

# 34%NBS with Brick Veneer



200mm thick concrete overlay on existing concrete floor. Allow for 120kg/m<sup>3</sup> reinforcing.

New concrete skin walls shown in blue dashed. Refer first floor plan attached.

Strengthen existing insitu concrete diaphragm. T.B.C. Likely to include drill and epoxy bars and chasing and grouting of bars into existing concrete floor.


200mm thick concrete overlay on existing concrete floor. Allow for 120kg/m<sup>3</sup> reinforcing.

First Floor Concrete Diaphragm Plan

Note:  
Fix existing brick veneer to existing concrete wall. e.g. Helifix fasteners or drill and epoxy threaded rod at 400crs e.w.  
Alternatively, remove brick veneer.

|  |  |
|--|--|
|  | PROJECT: <u>Southland Museum Redevelopment</u>   |
|  | JOB NO: <u>140859.13</u> DATE: <u>14/10/2020</u> |
|  | SSK: <u>13</u> REV: <u>1</u>                     |

# 34%NBS with Brick Veneer



### Legend:

IW1 - 200 thick insitu concrete skin wall.  
Allow for 120kg/m<sup>3</sup> reinforcing.


### First Floor Walls Plan

### Note:

Fix existing brick veneer to existing concrete wall. e.g. Helifix fasteners or drill and epoxy threaded rod at 400crs e.w. Alternatively, remove brick veneer.

|  |  |
|--|--|
|  | PROJECT: <u>Southland Museum Redevelopment</u>   |
|  | JOB NO: <u>140859.13</u> DATE: <u>14/10/2020</u> |
|  | SSK: <u>14</u> REV: <u>1</u>                     |

# 34%NBS with Brick Veneer



Roof Plan


**Note:**

Fix existing brick veneer to existing concrete wall. e.g. Helifix fasteners or drill and epoxy threaded rod at 400crs e.w. Alternatively, remove brick veneer.

|  |  |
|--|--|
|  | PROJECT: <u>Southland Museum Redevelopment</u>   |
|  | JOB NO: <u>140859.13</u> DATE: <u>14/10/2020</u> |
|  | SSK: <u>15</u> REV: <u>1</u>                     |



## 67%NBS Without Brick Veneer



### Legend:

FP2 - 3500x3500x1000 deep insitu concrete foundation pad. Allow for 120kg/m<sup>3</sup> reinforcing.


FB3 - 1200x800 deep insitu concrete foundation beam. Allow for 100kg/m<sup>3</sup> longitudinal reinforcing and 35kg/m<sup>3</sup> stirrup reinforcing.

FB4 - 2000x1000 deep insitu concrete foundation beam. Allow for 100kg/m<sup>3</sup> longitudinal reinforcing and 35kg/m<sup>3</sup> stirrup reinforcing.

Note:  
Existing brick veneer to be removed.

|  |  |
|--|--|
|  | PROJECT: <u>Southland Museum Redevelopment</u>   |
|  | JOB NO: <u>140859.13</u> DATE: <u>14/10/2020</u> |
|  | SSK: <u>16</u> REV: <u>1</u>                     |

# 67%NBS Without Brick Veneer



### Legend:

IW1 - 200 thick insitu concrete skin wall.  
Allow for 140kg/m<sup>3</sup> reinforcing.

### Note:


Existing brick veneer to be removed.



Ground Floor Plan

|  |  |
|--|--|
|  | PROJECT: <u>Southland Museum Redevelopment</u>   |
|  | JOB NO: <u>140859.13</u> DATE: <u>14/10/2020</u> |
|  | SSK: <u>17</u> REV: <u>1</u>                     |

# 67%NBS Without Brick Veneer




**Note:**  
Existing brick veneer to be removed.

First Floor Concrete Diaphragm Plan

|  |  |
|--|--|
|  | PROJECT: <u>Southland Museum Redevelopment</u>   |
|  | JOB NO: <u>140859.13</u> DATE: <u>14/10/2020</u> |
|  | SSK: <u>18</u> REV: <u>1</u>                     |

# 67%NBS Without Brick Veneer




### Legend:

IW1 - 200 thick insitu concrete skin wall.  
Allow for 140kg/m<sup>3</sup> reinforcing.

### First Floor Walls Plan


### Note:

Existing brick veneer to be removed.

|   |  |
|---|--|
|  | PROJECT: <u>Southland Museum Redevelopment</u>   |
|   | JOB NO: <u>140859.13</u> DATE: <u>14/10/2020</u> |
|   | SSK: <u>19</u> REV: <u>1</u>                     |




# 67%NBS Without Brick Veneer



Roof Plan






Note:  
Existing brick veneer to be removed.

|  |  |
|--|--|
|  | PROJECT: <u>Southland Museum Redevelopment</u>   |
|  | JOB NO: <u>140859.13</u> DATE: <u>14/10/2020</u> |
|  | SSK: <u>20</u> REV: <u>1</u>                     |



Location of 250mm thick insitu concrete walls  
Wall reinforcing content - allow for 140kg/m<sup>3</sup>

0.6m deep insitu concrete foundation beams under new concrete walls. Typically extends 1m beyond the column at each end of the wall.  
For 34%NBS total beam width = 2m  
Allow for 70 kg/m<sup>3</sup> longitudinal reinforcing  
55 kg/m<sup>3</sup> stirrups



The provisions of the Invercargill City Bylaws override anything that is inconsistent in this Specification & must be complied with.

| AMENDMENTS |  |  |  | Date | Initial |
|------------|--|--|--|------|---------|
| No.        |  |  |  |      |         |
|            |  |  |  |      |         |
|            |  |  |  |      |         |
|            |  |  |  |      |         |
|            |  |  |  |      |         |
|            |  |  |  |      |         |
|            |  |  |  |      |         |
|            |  |  |  |      |         |
|            |  |  |  |      |         |

**Royds Consulting Engineers & Planners**  
Gardner

Royds Garden Limited  
Christchurch, Dunedin, Invercargill,  
Balmuccia, Auckland, Gisborne,  
Dunedin, Timaru, Greymouth,  
Benmore, Palmerston North

| F.B. | Initials | Date   | TR  | Initials | Date |
|------|----------|--------|-----|----------|------|
| SURV |          |        |     |          |      |
| DGN  | NUR/TLH  | Dec 08 | CH  |          |      |
| DR   | GWK      | Dec 05 | APP |          |      |

**SOUTHLAND MUSEUM & ART GALLERY TRUST BOARD**  
BUILDING REDEVELOPMENT STAGE 1


FOUNDATION PLAN (LEVEL 1)


**Holmes** PROJECT: Southland Museum & Art Gallery  
JOB NO: 140859.13 DATE: 16/10/2020  
SSK: 06 REV: 4








 Location of 250mm thick insitu concrete walls below stopping at this level


 New concrete collector beam cast between ribs of floor units - refer to SSK-022 for indicative detailing  
Allow to drill and epoxy reinforcing through any existing columns or beams on these lines

 New concrete collector beam cast above the existing perimeter frame - refer to SSK-023 for indicative detailing

NOTES

- SEATINGS = INERSPAN UNITS ~ 60mm
- SHELL BEAMS ~ 30mm
- REFER TO STAIR DETAILS SHEETS
- GSB2 - 13 # 14
- FLOOR LIVE LOAD = 4KPa
- REFER TO "R" DETAILS FOR HOLDING DOWN BOLTS

ORIGINAL SIZE mm



**2nd Floor 34% Seismic Strengthening Scheme**

**Holmes** PROJECT: Southland Museum & Art Gallery  
 JOB NO: 140859.13 DATE: 16/10/2020  
 SSK: 021 REV: 4

| No. | AMENDMENTS | Date | Initial |
|-----|------------|------|---------|
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |

**Royds Consulting Engineers & Planners**  
 Royds Gordon Limited  
 Christchurch, Dunedin, Invercargill, Blenheim, Alexandra, Gisborne, Oamaru, Timaru, Greymouth, Benheim, Palmerston North

| F.B. | Initials | Date   | Initials | Date         |
|------|----------|--------|----------|--------------|
| SURV |          |        |          |              |
| DGN  | M.J.H.   | Dec 08 | CH       |              |
| DR   | N.C.S.   | Dec 08 | APP      | M.J.H. 2. 09 |

CLIENT: **SOUTHLAND MUSEUM & ART GALLERY TRUST BOARD**

JOB NAME: **BUILDING REDEVELOPMENT STAGE 1**

**2ND FLOOR PLAN (LEVEL 3)**

SCALES: 1:100



Project Name: Southland Museum and Art Gallery


Project No: 140859.13

Author: MAH

Revision: 1

Date: 16/10/20

No: SSk-022



### TYPICAL CONCRETE COLLECTOR BEAM BETWEEN RIBS

- Indicative, for pricing only
- Sizes and reinforcing quantities TBC in detailed design
- Detail will be similar for between existing TT units between grids 2-5 at first suspended level



Project Name: Southland Museum and Art Gallery


Project No: 140859.B

Author: MAH

Revision: 1

Date: 16/10/20

No: SSk-023



### TYPICAL CONCRETE COLLECTOR TIE AROUND PERIMETER

- Indicative design for pricing only
- Allow to drill & epoxy the new tie into the existing beams








——— Location of 250mm thick insitu concrete walls  
 Wall reinforcing content - allow for 140kg/m<sup>3</sup>  
- - - - - Location of 250mm thick insitu concrete walls  
 below stopping at this level

ORIGINAL SIZE mm

300  
200  
150  
100  
50  
30  
10  
0



**NOTES**  
 SEATINGS - INTERSPAN PLANKS 60mm  
 SHELL BEAMS 30mm  
 REFER TO STAIR DETAILS SHEETS  
 GSBZ - 13 & 14  
 FLOOR LIVE LOAD - 4KPa  
 REFER TO "R" DETAILS FOR HOLDING  
 DOWN BOLTS

| No. | AMENDMENTS | Date | Initial |
|-----|------------|------|---------|
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |
|     |            |      |         |

**Royds Consulting Engineers & Planners**  
 Royds Garden Limited  
 Christchurch, Dunedin, Invercargill,  
 Blenheim, Alexandra, Queenstown,  
 Oamaru, Timaru, Greymouth,  
 Benham, Palmerston North

| F.B. | Initials    | Date   | TR  | Initials | Date |
|------|-------------|--------|-----|----------|------|
| SURV |             |        | CH  |          |      |
| DGN  | M.J.H./T.H. | Dec 08 |     |          |      |
| DR   | G.V.        | Dec 09 | APP | M.J.H.   | 2-09 |

CLIENT: SOUTHLAND MUSEUM  
 AND ART GALLERY  
 TRUST BOARD  
 NAME: BUILDING REDEVELOPMENT  
 STAGE 1

TITLE: FIRST FLOOR SLAB  
 (LEVEL 2)


SCALES: 1:100

First Floor 67% Seismic Strengthening Scheme Wall Layout


**Holmes** PROJECT: Southland Museum & Art Gallery  
 JOB NO: 140859.13 DATE: 29/10/2020  
 SSK: 25 REV: 1


NOV  
 18/11/20






Plan of Proposed Strengthening of Pyramid Structure

|   |  |                         |
|---|--|-------------------------|
|  | PROJECT: <u>Southland Museum &amp; Art Gallery</u> |                         |
|   | JOB NO: <u>140859.13</u>                           | DATE: <u>29/09/2020</u> |
|   | SSK: <u>08</u>                                     | REV: <u>1</u>           |



Section through proposed strengthened 310UB/250UB base plate





**ENGEO**  
*Celebrating* 10 YEARS IN NZ

## Southland Museum and Art Gallery - Geotechnical Investigation

108 Gala Street  
Queens Park  
Invercargill

Submitted to:  
Invercargill City Council  
C/- The Building Intelligence Group  
173 Spey Street  
Invercargill 9810

**ENGEO Limited**  
25 Glenda Drive  
Frankton  
Queenstown 9371  
P +64 3 328 9012  
[www.engeo.co.nz](http://www.engeo.co.nz)

23.11.2020  
17651.000.000\_01



## Contents

|     |  |    |
|-----|--|----|
| 1   | Introduction.....                          | 3  |
| 2   | Project Background .....                   | 3  |
| 3   | Site Description.....                      | 4  |
| 4   | Background Geotechnical Information .....  | 4  |
| 4.1 | Published Geology.....                     | 4  |
| 4.2 | New Zealand Geotechnical Database.....     | 4  |
| 4.3 | Previous Geotechnical Investigations ..... | 5  |
| 5   | Site Investigations.....                   | 5  |
| 5.1 | Overview.....                              | 5  |
| 5.2 | Surficial Geology.....                     | 6  |
| 5.3 | Groundwater .....                          | 7  |
| 6   | Seismic Hazard.....                        | 7  |
| 6.1 | Soil Classification.....                   | 7  |
| 6.2 | Ground Shaking.....                        | 8  |
| 6.3 | Seismic Liquefaction Assessment.....       | 8  |
| 7   | Geotechnical Recommendations .....         | 9  |
| 8   | References .....                           | 11 |
| 9   | Limitations .....                          | 12 |

## Tables

|          |  |
|----------|--|
| Table 1: | Summary Investigation Information            |
| Table 2: | Typical Subsurface Geology                   |
| Table 3: | Summary of liquefaction analysis             |
| Table 4: | Generalised Ground Model and Soil Properties |
| Table 5: | Subgrade Modulus Values                      |
| Table 6: | Recommended Ultimate Bearing Capacities      |

## Figures

|           |  |
|-----------|--|
| Figure 1: | Published Geological Map of the Area (image modified from Turnbull & Allibone, 2003) |
|-----------|--|

## Appendices

|             |                                 |
|-------------|---------------------------------|
| Appendix 1: | Site Map                        |
| Appendix 2: | Third Party Geotechnical Data   |
| Appendix 3: | Test Pit Logs                   |
| Appendix 4: | Laboratory Testing Results      |
| Appendix 5: | Liquefaction Assessment Results |

### ENGEO Document Control:

|                    |   |                |                        |          |
|--------------------|---|----------------|------------------------|----------|
| Report Title       | Southland Museum and Art Gallery - Geotechnical Investigation Queens Park |                |                        |          |
| Project No.        | 17651.000.000   | Doc ID         | 01                     |          |
| Client             | Invercargill City Council   | Client Contact | C/- Tess Browne (TBIG) |          |
| Distribution (PDF) | The Building Intelligence Group   |                |                        |          |
| Date               | Revision Details/Status   | WP             | Author                 | Reviewer |
| 29/10/2020         | DRAFT   | JT             | BC / SM                | NC       |
| 23/11/2020         | Revision 0  | JT             | BC / SM                | AW       |

## 1 Introduction

ENGEO Ltd has been engaged by The Building Intelligence Group (TBIG) on behalf of the Invercargill City Council (ICC) to undertake a geotechnical investigation at the Southland Museum and Art Gallery (SMAG) in Invercargill (herein referred to as 'the site'). The purpose of the geotechnical investigation is to support an options assessment for earthquake strengthening of the SMAG building. ENGEO understands the building has been closed to the public due to earthquake risk since 2018.

Based on discussions with TBIG and the wider project team, our scope of work is to investigate the current foundation conditions, including the type and bearing capacity of existing foundations, provide geotechnical parameters for design of new foundations and to undertake a liquefaction susceptibility assessment. This scope will inform an options analysis for the degree of earthquake strengthening for the SMAG structure.

Investigations, analysis and reporting have been carried out in accordance with our revised proposal and signed agreement dated 14 August 2020 (ENGEO, 2020).

## 2 Project Background

The SMAG was first opened in 1942. Several additions and alterations were subsequently added, including a major redevelopment in 1990. Architectural drawings for the 1990 redevelopment (dated 14 April 1989) indicate that the SMAG, in its current design is a three-level, pyramid-shaped structure with a footprint of approximately 2,220 m<sup>2</sup> and a total height of approximately 24 m.

Opus International Consultants Ltd (Opus) - now WSP New Zealand Ltd., completed an engineering review of the structure in 2013. Opus later reviewed these findings, including a Detailed Seismic Assessment (DSA), following changes made to the Building Act in July 2017 (Opus, 2017). The 2017 DSA reiterated the findings of the original 2013 assessment, in that the SMAG has a seismic capacity of <34% New Building Standard (NBS). Consequently, the building was classified as being earthquake-prone. This was attributed to the deficiencies found in the design and construction of the building, primarily relating to how the additions and alterations interact with one-another under lateral seismic loading.

The SMAG was closed to the public in 2018. Consequently, the ICC have requested an options assessment to determine the following:

- Cost estimates to strengthen the building to 34% and 67%. This includes the methodology required to complete the works and the extent of refurbishments required.
- A comparison cost to construct a new building to 100% NBS.
- The compromises ICC will have to make if they simply strengthen the building and do not take the opportunity to make cosmetic changes as per the 2019 Tim Walker report (Tim Walker Associates, 2019).

This report by ENGEO supports the wider options assessment report requested by the ICC.




### 3 Site Description

The site is located at 108 Gala Street within the Queens Park area, Invercargill. It is legally described as Lot 3 DP 308322 (Appendix 1, Figure 1). The site currently comprises the pyramid-shaped SMAG building with an observatory attached on the western side, as well as associated parking and accessways. The site is approximately 0.49 ha in total area. Topography is typically flat-lying at an approximate elevation of 16 m RL. The Waihopai River is located approximately 1.2 km to the west of the site.

## 4 Background Geotechnical Information

### 4.1 Published Geology

Published geological maps of the area indicate that the site is anticipated to be underlain by Holocene-aged, unconsolidated gravel and sand deposits in alluvial terraces (**Error! Reference source not found.**) (Turnbull & Allibone, 2003).



**Figure 1: Published Geological Map of the Area (image modified from Turnbull & Allibone, 2003)**

Basement bedrock in this area is mapped as sandstone and mudstone of the Murihiku Terrane and is expected to be located at significant depths.

### 4.2 New Zealand Geotechnical Database

There are several locations of historical geotechnical investigation approximately 500 - 800 m from the site. ENGEO have reviewed geological logs for these, available on the New Zealand Geotechnical Database (NZGD). While this information can be useful in categorizing the regional surficial geology, it is important to acknowledge that due to spatial variability it cannot be relied upon for site-specific assessment or design.

We have summarised the relevant information obtained from the NZGD below:

- Fill is widespread across the Invercargill area from surface, typically to depths between 1 - 3 m. Fill types can include sandy gravels, reworked topsoil, refuse, sandy silts and also reclaimed soils in the vicinity of the Waihopai River.
- Underlying fills and / or the surficial topsoil in some central areas is a firm to stiff silt and / or clay deposit that has weathered to a yellow brown colour. This is interpreted to be of alluvial genesis, deposited in a lower energy environment to the underlying alluvial sands and gravels (Section 4.1 and below)
- A sequence of medium dense to very dense alluvial sands and gravels lie beneath the majority of the Invercargill area, typically from depths of between 3 – 5 m to depths in excess of 10 – 15 m.

Field data published in the NZGD are included in Appendix 2.

### 4.3 Previous Geotechnical Investigations

As part of the Request for Proposal (RFP) issued by the ICC for the SMAG options assessment, factual data from two well logs undertaken on the SMAG site were provided to ENGEO. These boreholes were drilled to a depth of 6 m using rotary drilling techniques. These boreholes were not drilled using geotechnical sampling methods nor were they logged accordingly. While the exact location of the boreholes is unknown, material descriptions are generally consistent with third party data from the NZGD (Section 4.2).

Borehole logs are included in Appendix 2.

## 5 Site Investigations

### 5.1 Overview

ENGEO completed site investigations on 9 September and 6 October 2020 comprising the following:

- Observation of two Test Pits (TP) to depths between 2.0 – 2.5 m.
- Monitoring of two Cone Penetrometer Tests (CPTs) to depths between 7.1 – 7.5 m.
- Completion of Dynamic Cone Penetrometers (DCPs) at each TP location.

TPs were logged in accordance with the New Zealand Geotechnical Society (NZGS) field-description of soil and rock guidelines. Grab samples were collected in TPs by ENGEO and tested for grain size analyses and Atterberg Limits (both per NZS 4402:1986) by Central Testing Laboratories. CPTs were completed by Ground Investigation Ltd with the results supplied to ENGEO.

Summary investigation data is included in Table 1 below.



**Table 1: Summary Investigation Information**

| Investigation ID | Latitude <sup>1</sup> | Longitude <sup>1</sup> | Elevation (m RL) <sup>2</sup> | Investigation Depth (m bgl) <sup>3</sup> | DCP Depth (m bgl) <sup>3</sup> |
|------------------|-----------------------|------------------------|-------------------------------|--|--------------------------------|
| SM-ENG20-TP01    | -46.40537             | 168.3533               | 16                            | 2.5                                      | 2.0                            |
| SM-ENG20-TP02    | -46.40503             | 168.35377              | 16                            | 2.0                                      | 2.0                            |
| SM-ENG20-CPT01   | -46.40523             | 168.35409              | 16                            | 7.1                                      | N/A                            |
| SM-ENG20-CPT02   | -46.40533             | 168.35331              | 16                            | 7.5                                      | N/A                            |

Notes:

<sup>1</sup> Investigation locations were surveyed using a GIS application on mobile device with a typical accuracy of +/- 3 – 4.5 m.

<sup>2</sup> No high resolution elevation data for the Invercargill area is available. Elevation is estimated from low resolution contours with an accuracy of +/- 3 m.

<sup>3</sup> bgl refers to 'below ground level', the level of ground surface at the time of the site investigation.

Investigations were located to avoid underground services and existing access-ways. Locations are shown in Appendix 1, Figure 1. TP logs (including DCPs) are included in Appendix 3, with CPT logs in Appendix 5.

ENGEO attempted to excavate test pits immediately adjacent to existing shallow foundations. The intention of this methodology was to inform the bearing depth, type and geometry of the structures foundations at the edge of the existing building and estimate current bearing pressures. Buried utilities and surface infrastructure prevented the safe excavation of test pits against the existing building footings and their bearing depth and geometry remains uncertain.

## 5.2 Surficial Geology

Test pit observations identified a surficial layer of uncontrolled granular fill on the northern and western sides of the site. This unit was found to a depth of 0.4 m and included a layer of deteriorated asphalt at approximately 0.3 m. TP02, undertaken on the northern side of the site, encountered a firm topsoil to a depth of 0.2 m with re-worked organic fill materials beneath. These materials comprised topsoil and fibrous organics with layers of gravel, refuse and burn-off waste.

Underlying the organics and fill materials, ENGEO observed a grey, alluvial silt and clay containing trace organics. This unit graded into a yellow brown alluvial silt that was stiff to very stiff and was observed to the termination depth of 2.0 m in both TPs.

Two grab samples were tested for grain size analyses (via sieve) and Atterberg limits from each TP. Results indicate the fines content of tested samples is >92%. One sample from TP02 was shown to be a high plasticity clay and the remainder were indicated to be low plastic clays with plasticity indices varying from 7 to 23, although on the silt/clay boundary. Laboratory results generally agree with the Soil Behavior Type (Robertson et al. 1986) inferred in the CPT data (Section 5.1). Laboratory results are included in Appendix 4.

Although not observed in TPs, the two CPTs and the two historic boreholes (Section 4.3) indicate that from between approximately 2.0 and 2.5 m bgl the alluvial silt and clay grades into a silty sand unit, likely characterised by interbedded layers of silt and sand. The CPTs and historic boreholes suggest

this unit is likely stiff / medium dense. Underlying this unit from a depth of approximately 4.5 m, CPTs and historic boreholes identified a medium dense to dense sandy gravel. This unit was encountered to the termination depth of investigations.

A summary of interpreted surficial geology beneath the site is presented in Table 2 below.

**Table 2: Typical Subsurface Geology**

| Geological Unit                           | Typical Depth (m bgl) | Typical Material Description                                  | Density / Consistency <sup>1</sup> |
|---|-----------------------|---|------------------------------------|
| Topsoil <sup>2</sup>                      | 0.0 - 0.2             | Organic silt, dark brown                                      | Firm                               |
| Granular Fill (uncontrolled) <sup>3</sup> | 0.0 – 0.4             | Sandy fine to coarse gravel, grey                             | Tightly packed                     |
| Alluvium (fine-grained) <sup>4</sup>      | 0.4 – 4.5             | Silt, some sand to sandy (sand content increasing with depth) | Firm / Stiff                       |
| Alluvium (coarse-grained)                 | 4.5 – 7.0 +           | Sand and gravel   | Dense to very dense                |

Notes:

1. Density is estimated from results of DCP and SPT testing. DCP testing in medium to coarse gravels is not always representative due to the potential for the DCP to bounce on individual clasts providing an inaccurate representation.
2. Topsoil and organic fill was only observed on the northern side of the site.
3. Granular fill was only observed on the eastern and western sides of the site.
4. Within this unit, a 0.4 m to 0.8 m thick layer of clayey silt/silty clay was encountered from 3.6m (CPT1), and 4.6 m (CPT2) depth.

The geology encountered during investigations is broadly consistent with the published literature and data obtained from the surrounding area (Sections 4.1 & 4.2).

### 5.3 Groundwater

Seepage was observed from 0.9 and 1.5 m depth in TP01 and TP02, respectively. Groundwater had risen (and stabilized) to 1.0 m bgl in TP01 by the time the TP had been completed (see TP01 log, Appendix 3). Additionally, the two CPTs estimated groundwater to be at 1.0 and 1.6 m bgl.

Based on the observations made during investigations, it is likely that the site groundwater level is approximately 1.0 – 2.0 m bgl. This is consistent with investigations ENGEO have undertaken in the Invercargill area and the anticipated regional groundwater table (per NZGD investigations, Section 4.2).

Interpretation of groundwater observations should be done with caution. The potential exists for perched water and seasonal fluctuations in levels. Should groundwater data be critical to design of new foundations, further investigation of groundwater elevations should be considered.

## 6 Seismic Hazard

### 6.1 Soil Classification

Based on the investigation information available, specifically the absence of information on the depth to bedrock, we consider the soil classification in line with NZS 1170.5:2004 to be 'Class D – Deep or Soft Soil Sites' for the purpose of seismic design.

## 6.2 Ground Shaking

The SMAG is classified as an Importance Level 3 building. According to NZS 1170.5:2004, Importance Level 3 buildings are required to be designed to resist earthquake shaking with an annual probability of exceedance of 1/1000 (i.e. 1000 year return period). This is the ultimate limit state (ULS) design seismic loading. Structures are expected to retain their structural integrity during the ULS earthquake, and not collapse or endanger life.

Furthermore, Importance Level 3 buildings should sustain little or no structural damage under a serviceability limit state (SLS) design load case, which is based on earthquake shaking with a 25 year return period.

Peak horizontal ground accelerations ( $a_{max}$ ) have been calculated in accordance with MBIE / NZGS Module 1 (2016) using the following formula:

$$a_{max} = C_{0,1000} R f g / 1.3$$

$$C_{0,1000} = 0.26 \text{ for Invercargill (Commentary to the NZTA Bridge Manual (2018) Table C6.1)}$$

$$R = 1.3 \text{ for a 1000 year return period event (NZS1170.5) (ULS)}$$

$$= 0.25 \text{ for a 25 year return period event (NZS1170.5) (SLS)}$$

$$f = 1.0 \text{ for Class D}$$

$$\text{Thus } a_{max} = 0.26 \times 0.25 \times 1 / 1.3 = 0.05 \text{ g (SLS)}$$

$$= 0.26 \times 1.3 \times 1 / 1.3 = 0.26 \text{ g (ULS)}$$

Note: This ULS  $a_{max}$  value represents 100% NBS. For ULS at 34 and 67% NBS,  $a_{max}$  is equal to 0.09 and 0.18 g respectively.

The effective earthquake magnitude can be taken as 6.1 for the Invercargill area.

## 6.3 Seismic Liquefaction Assessment

Soil liquefaction occurs when a saturated or partially saturated soil substantially loses strength and stiffness in response to an applied stress such as shaking during an earthquake or other sudden change in stress condition, in which material that is ordinarily a solid behaves like a liquid. A detailed liquefaction analysis was performed using the results of CPTs, utilising the method recommended by Boulanger and Idriss (2014) to determine the susceptibility of the subsoils to liquefaction and the method recommended by Zhang et al. (2002) to calculate vertical settlements.

A groundwater level of 1 m bgl was utilised for the liquefaction assessment.

The results of the liquefaction assessment indicate the following:

- No liquefaction is predicted under SLS conditions or 34% NBS ULS conditions.
- Some liquefaction is likely to occur in the alluvial units between 1.5 – 5.0 m bgl under 67 and 100% NBS ULS seismic loading, if saturated. Some cyclic softening of the clayey soils may also occur.

- Vertical settlement is predicted to be less than 15 mm under ULS seismic loading in all design load cases.

The analysis considers volumetric strain and does not account for ground loss due to ejecta. Owing to the shallow liquefiable layers and potentially liquefiable material below the groundwater table, sand boil formation and ejecta are likely to occur at the site under ULS shaking. Therefore, building settlements may exceed those calculated in the above analysis during ULS shaking.

In terms of the NZGS / MBIE guidelines (NZGS / MBIE, 2016), the expected level of liquefaction to occur corresponds to a Performance Level 'L0 - Insignificant' under SLS and 34% NBS loading and 'L2 – Moderate' under 67 and 100 % NBS ULS loading.

A summary of our analysis results are presented in Table 3.

**Table 3: Summary of liquefaction analysis**

| Investigation identifier | Calculated Vertical Settlement (mm) |                             |                             |                              |
|--------------------------|-------------------------------------|-----------------------------|-----------------------------|------------------------------|
|                          | SLS<br>M6.1, 0.05 g                 | 34% NBS ULS<br>M6.1, 0.09 g | 67% NBS ULS<br>M6.1, 0.18 g | 100% NBS ULS<br>M6.1, 0.26 g |
| SM-ENG20-CPT01           | Negligible                          | Negligible                  | 5                           | 10                           |
| SM-ENG20-CPT02           | Negligible                          | Negligible                  | 10                          | 15                           |

Settlements due to seismic liquefaction are estimated from free field estimates. Given the configuration and geometry of the existing building foundations are uncertain (Section 5.1), ENGEO has not completed an analysis of punching shear during a seismic event and the likelihood of a punching failure is anticipated to be low and not warrant further consideration. However, punching mechanisms should be considered during detailed design for new foundation elements.

The full liquefaction assessment results are presented in Appendix 5.

## 7 Geotechnical Recommendations

ENGEO developed a generalised ground model for the site to provide geotechnical parameters for design. This ground model is outlined in Table 4. We understand that these parameters may be used by the structural engineer to assess both static and seismic load cases.

**Table 4: Generalised Ground Model and Soil Properties**

| Generalised Depth Range <sup>1</sup> | Soil Type   | Unit Weight (kN/m <sup>3</sup> ) | Relative Density (%) | Undrained Shear Strength (kPa) | Poisson Ratio | Static Young's Modulus (MPa) <sup>2</sup> | Degraded Shear Modulus (MPa) (~0.1 to 0.5% strain) <sup>2</sup> |
|--------------------------------------|-------------|----------------------------------|----------------------|--------------------------------|---------------|---|---|
| 0.5 m to 2 m                         | Silt / Clay | 17                               | -                    | 50                             | 0.40          | 15  | 4   |
| 2 m to 4 m                           | Sand / Silt | 17                               | 60                   | -                              | 0.35          | 50  | 14  |

| Generalised Depth Range <sup>1</sup> | Soil Type     | Unit Weight (kN/m <sup>3</sup> ) | Relative Density, (%) | Undrained Shear Strength (kPa) | Poisson Ratio | Static Young's Modulus (MPa) <sup>2</sup> | Degraded Shear Modulus (MPa) (~0.1 to 0.5% strain) <sup>2</sup> |
|--------------------------------------|---------------|----------------------------------|-----------------------|--------------------------------|---------------|---|---|
| 4 m to 4.5 m                         | Clay          | 17                               | -                     | 80                             | 0.40          | 25  | 6   |
| 5 m to 10 m                          | Sand / Gravel | 18                               | 80 +                  | -                              | 0.35          | 100                                       | 28  |

<sup>1</sup>These are generalised depths. Actual depth and thickness of each layer encountered varied across investigation locations.

<sup>2</sup>Due to the uncertainty involved in estimating these parameters we recommend a range from 50% to 200% of the recommended value be checked where these parameters are used in design.

The provided Young's Modulus and shear modulus values are "static" or "degraded" values associated with shear strains on the order of 0.1 to 0.5%. We consider these parameters are generally suitable for use in both static and seismic assessments, acknowledging that under dynamic loading where shear strains are very low they are likely underestimating actual values.

ENGEO understand the project assessment for different building performance levels (Section 2) will require both assessment of existing foundation beams, and designing new foundation elements to support potential earthquake strengthening of the overall structure.

ENGEO recommend the following subgrade modulus values for a range of foundation beam widths, and a foundation beam depth of 0.5m. Due to the uncertainty in estimating these parameters we recommend checking a range of values 50% to 200% of the values presented in Table 5 in sensitivity analyses.

**Table 5: Subgrade Modulus Values**

| Foundation Beam Width (Depth of 0.5m) | Recommended Subgrade Modulus, $k_s$ |
|---------------------------------------|-------------------------------------|
| 0.5 m                                 | 35 kPa/mm                           |
| 1.0 m                                 | 40 kPa/mm                           |
| 1.5 m                                 | 40 kPa/mm                           |
| 2.0 m                                 | 35 kPa/mm                           |
| 2.5 m                                 | 30 kPa/mm                           |
| 3.0 m                                 | 25 kPa/mm                           |

Recommended bearing capacities and strength reduction factors are presented in Table 6.

**Table 6: Recommended Ultimate Bearing Capacities**

| Foundation Beam Type         | Foundation Beam Width (Depth of 0.5m) | Ultimate Geotechnical Bearing Capacity | Strength Reduction Factors             |
|------------------------------|---------------------------------------|--|--|
| Existing Foundation Elements | Up to 1.0 m wide                      | 200 kPa <sup>1</sup>                   | All Load Combinations – 1 <sup>1</sup> |
| New Foundation Elements      | Up to 1.0 m wide                      | 120 kPa <sup>1</sup>                   | SLS Loads – 0.33<br>ULS Loads – 0.5    |
|                              | 1.0 m to 1.5 m wide                   | 200 kPa                                |  |
|                              | Greater than 1.5 m wide               | 300 kPa                                |  |

<sup>1</sup>The different values recommended for similar sized existing and new foundation elements reflect the different approaches (outlined in Part C4 of MBIEs Seismic assessment of existing buildings guidance) for assessment versus design. The value provided for existing foundations represents a “best-estimate” or probable value while the value for new foundation elements represents a lower bound or reliable value for design.

It may be possible to refine (and likely increase) recommended bearing capacities with a better understanding of the existing foundation geometry and foundation performance to date (given this currently remains uncertain, Section 5.1). If the provided capacities are driving the foundation design we recommend additional work be carried out to further investigate the existing foundation depths and widths.

ENGEO recommend the in situ surficial soils are suitable for shallow foundations following the removal of any uncontrolled fill and / or organic material.

## 8 References

Boulanger, R.W., Idriss, I.M. (2014). CPT and SPT based liquefaction triggering procedures. Center for Geotechnical Modelling. Report No. UCD/CGM-14/01.

ENGEO (2020). <Topic> – Southland Museum Earthquake Strengthening ProjectQueens Park Invercargill\_Revision 1 (Ref. P2020.001.476\_03)

MBIE / NZGS (2016). Earthquake geotechnical engineering practice. Rev 0.

Opus International Consultants Ltd. (2017). Southland Museum and Art Gallery, Detailed Seismic Assessment – Review changes to the Building Act July 2017.

Tim Walker Associates (2019). Strategic Review: Reinventing the Southland Museum.

Turnbull, I. M., Allibone, A. H. (2003). Geology of the Murihiku area. Institute of Geological & Nuclear Sciences 1:250 000 geological map 20. Lower Hutt, New Zealand. Institute of Geological & Nuclear Sciences.

Zhang, G., Robertson, P.K., Brachman, R.W.I. (2002). Estimating liquefaction-induced ground settlements from CPT for level ground. Canadian Geotechnical Journal. 39: 1168 – 1180.

## 9 Limitations

- i. We have prepared this report in accordance with the brief as provided. This report has been prepared for the use of our client, Invercargill City Council, their professional advisers and the relevant Territorial Authorities in relation to the specified project brief described in this report. No liability is accepted for the use of any part of the report for any other purpose or by any other person or entity.
- ii. The recommendations in this report are based on the ground conditions indicated from published sources, site assessments and subsurface investigations described in this report based on accepted normal methods of site investigations. Only a limited amount of information has been collected to meet the specific financial and technical requirements of the client's brief and this report does not purport to completely describe all the site characteristics and properties. The nature and continuity of the ground between test locations has been inferred using experience and judgement and it should be appreciated that actual conditions could vary from the assumed model.
- iii. Subsurface conditions relevant to construction works should be assessed by contractors who can make their own interpretation of the factual data provided. They should perform any additional tests as necessary for their own purposes.
- iv. This Limitation should be read in conjunction with the Engineering NZ/ACENZ Standard Terms of Engagement.
- v. This report is not to be reproduced either wholly or in part without our prior written permission.

We trust that this information meets your current requirements. Please do not hesitate to contact the undersigned on (03) 328 9012 if you require any further information.

Report prepared by

Report reviewed by

**Sam Murray, MEngNZ**

Senior Geotechnical Engineer

**Neil Charters, CMEngNZ (CPEng)**


Principal Geotechnical Engineer

**Bradley Cosgrove**

Engineering Geologist

**APPENDIX 1:**  
Site Map





SM-ENG20-TP02

SM-ENG20-CPT02

SM-ENG20-TP01

SM-ENG20-CPT01



- Legend**
- Site Boundary
  - Cone Penetration Test
  - Test Pit

5 m




|   |  |              |              |
|---|--|--------------|--------------|
| Title: Site Investigation Plan            |  |              |              |
| Client: Invercargill City Council         |  | Drawn: BC    | Figure No: 1 |
| Project: Southland Museum and Art Gallery |  | Checked: SM  | Size: A4     |
| Date: 20-11-2020                          |  | Version: 2.0 |              |
| Proj No: 17651                            |  |              |              |




**APPENDIX 2:**


Third Party Geotechnical Data






**Key**

-  = Dynamic Probe Heavy Test (DPH)
- P** = Permanent Piezometer Installed

-  = Sonic Borehole



|                     |               |                   |     |         |
|---------------------|---------------|-------------------|-----|---------|
| CADFILE:            | Site Plan.xar | DRAWN:            | MB  | 07/2019 |
| SCALE: (AT A3 SIZE) | AS SHOWN      | DRAFTING CHECKED: | FAW | 07/2019 |
| PROJECT No.:        | 190061.01     | APPROVED:         | CEM | 07/2019 |



GEOTECHNICAL


WATER RESOURCES

PAVEMENTS

Southern Institute of Technology  
 Centre for Creative Industries  
 108 Tay Street, Invercargill  
 Site Plan

|         |          |      |   |
|---------|----------|------|---|
| FIG No: | FIGURE 1 | REV. | 1 |
|---------|----------|------|---|





|  |               |  |   |                      |               |       |    |         |                     |          |                  |     |         |              |           |          |     |         |  |
|--|---------------|--|---|----------------------|---------------|-------|----|---------|---------------------|----------|------------------|-----|---------|--------------|-----------|----------|-----|---------|--|
| <p><b>Key</b></p> <p>— = Observed geological contact</p> <p>- ? - = Inferred geological contact</p> <p>⊥ = DPH refusal</p> <p>---▼--- = Measured Water Level</p> |               | <p>Horizontal Scale 1:250</p> <p>0 5 10 (m)</p> <p>Vertical Scale 1:100</p> <p>0 1 2 3 4 5 (m)</p> | <table border="1"> <tr> <td>CADFILE:</td> <td>Site Plan.xar</td> <td>DRAWN</td> <td>MB</td> <td>07/2019</td> </tr> <tr> <td>SCALE: (AT A3 SIZE)</td> <td>AS SHOWN</td> <td>DRAFTING CHECKED</td> <td>FAW</td> <td>07/2019</td> </tr> <tr> <td>PROJECT No.:</td> <td>150214.02</td> <td>APPROVED</td> <td>CEM</td> <td>07/2019</td> </tr> </table> | CADFILE:             | Site Plan.xar | DRAWN | MB | 07/2019 | SCALE: (AT A3 SIZE) | AS SHOWN | DRAFTING CHECKED | FAW | 07/2019 | PROJECT No.: | 150214.02 | APPROVED | CEM | 07/2019 | <p><b>Southern Institute of Technology</b><br/>         Centre for Creative Industries<br/>         108 Tay Street, Invercargill<br/>         Cross Section A-A'</p> |
| CADFILE:   | Site Plan.xar | DRAWN  | MB  | 07/2019              |               |       |    |         |                     |          |                  |     |         |              |           |          |     |         |  |
| SCALE: (AT A3 SIZE)  | AS SHOWN      | DRAFTING CHECKED   | FAW   | 07/2019              |               |       |    |         |                     |          |                  |     |         |              |           |          |     |         |  |
| PROJECT No.:   | 150214.02     | APPROVED   | CEM   | 07/2019              |               |       |    |         |                     |          |                  |     |         |              |           |          |     |         |  |
| <p><b>GEOSOLVE</b><br/>ENGINEERING CONSULTANTS</p>   |               |  | <p>FIG No: <b>FIGURE 2</b></p>  | <p>REV. <b>1</b></p> |               |       |    |         |                     |          |                  |     |         |              |           |          |     |         |  |



DRILLHOLE No: BH01

DRILLHOLE LOG

SHEET ..... OF .....

|   |                                |  |                                     |
|---|--------------------------------|--|-------------------------------------|
| PROJECT: <i>St. Johns Church Site Investigation</i>                       | JOB No: <i>1906061-01</i>      | LOCATION: <i>108 Tau St, Wellington</i>  | HOLE LOCATION: <i>See Site plan</i> |
| CO-ORDINATES<br>mN <i>4849664</i> (NZTM)<br>mE <i>1242841</i> 3m accuracy | DRILL TYPE: <i>HD900 SONIC</i> | HOLE STARTED: <i>12/02/2019</i>          |                                     |
| DIRECTION: <i>0</i>   | DATUM: <i>Ground level</i>     | HOLE FINISHED: <i>13/07/2019</i>         |                                     |
| ANGLE FROM HORIZ: <i>0</i>  | R.L. GROUND: <i>0 m</i>        | DRILLED BY: <i>STRAIGHTS DILLIARD</i>    |                                     |
|   | R.L. COLLAR: <i>0 m</i>        | LOGGED BY: <i>mb</i> CHECKED: <i>MTW</i> |                                     |

| GEOLOGICAL UNIT        | DESCRIPTION OF CORE<br><small>SOIL: Classification, colour, consistency / density, moisture, plasticity</small>  | Sampling Method | Core Recovery (%) | Moisture Condition | Strength/Density Classification | RL (m) | Depth (m) | Graphic Log | Drillers Notes | TESTING                         |                                 |                   |                |             |        |             |          |  |
|------------------------|--|-----------------|-------------------|--------------------|---------------------------------|--------|-----------|-------------|----------------|---------------------------------|---------------------------------|-------------------|----------------|-------------|--------|-------------|----------|--|
|                        |  |                 |                   |                    |                                 |        |           |             |                | Hammer Efficiency: <i>54.67</i> | Borehole Diameter: <i>125mm</i> | Liner: <i>100</i> | Water Loss (%) | Water Level | Casing | riser/joint | Core Box |  |
| <i>FILL / TOPSOIL</i>  | <i>0-0m Organic silt with minor rust/rocks, and sand, trace gravel and concrete. Brown, soft, moist. Non plastic. Sand fine to coarse. Small but to coarse rounded.</i>                        | <i>SONIC</i>    | <i>100%</i>       | <i>MOIST</i>       | <i>SOFT</i>                     |        |           | <i>X</i>    |                |                                 |                                 |                   |                |             |        |             |          |  |
| <i>ALLUVIAL SILT</i>   | <i>0-2m Silt with trace sand, gravel and rounded yellow brown mottled shales, pebbles, smooth. Non plastic. Sand fine to coarse. Small but subrounded - rounded. Orange mottled siltstone.</i> | <i>SPT</i>      | <i>100%</i>       | <i>MOIST</i>       | <i>FIRM</i>                     |        |           | <i>X</i>    |                |                                 |                                 |                   |                |             |        |             |          |  |
| <i>ALLUVIAL SAND</i>   | <i>1-4m Silt with minor sand and trace angular yellow brown mottled shales, pebbles, smooth. Non plastic. Sand fine to coarse. Small but subrounded - rounded. Orange mottled siltstone.</i>   | <i>SPT</i>      | <i>100%</i>       | <i>MOIST-DET</i>   | <i>FIRM</i>                     |        |           | <i>X</i>    |                |                                 |                                 |                   |                |             |        |             |          |  |
| <i>ALLUVIAL SAND</i>   | <i>3-3m Coarse, fine to medium sand with some silt. Some grey, moist-wet. Small but to coarse rounded quartz.</i>  | <i>SONIC</i>    | <i>100%</i>       | <i>MOIST-DET</i>   | <i>FIRM</i>                     |        |           | <i>X</i>    |                |                                 |                                 |                   |                |             |        |             |          |  |
| <i>ALLUVIAL GRAVEL</i> | <i>2-9m Sandy fine to coarse GRAVEL with some silt. Grey orange mottled, dense, patterned. Well graded. Small fine to med. Siltier lower throughout.</i>                                       | <i>SPT</i>      | <i>100%</i>       | <i>MOIST-DET</i>   | <i>DENSE</i>                    |        |           | <i>0</i>    |                |                                 |                                 |                   |                |             |        |             |          |  |
| <i>ALLUVIAL GRAVEL</i> | <i>4-2m gravelly medium fine to medium.</i>  | <i>SPT</i>      | <i>100%</i>       | <i>MOIST-DET</i>   | <i>DENSE</i>                    |        |           | <i>0</i>    |                |                                 |                                 |                   |                |             |        |             |          |  |
| <i>ALLUVIAL GRAVEL</i> | <i>5-3m Silty, sandy fine to coarse GRAVEL. Grey mottled orange, white silt. an. fine, moist. Sand fine to coarse. Small rounded to subrounded, mainly quartz.</i>                             | <i>SPT</i>      | <i>100%</i>       | <i>MOIST-DET</i>   | <i>DENSE</i>                    |        |           | <i>0</i>    |                |                                 |                                 |                   |                |             |        |             |          |  |
| <i>ALLUVIAL SILT</i>   | <i>8-0m Coarsely, sandy SILT, Grey mottled orange and white, very stiff, subrounded coarse fine to coarse (mainly fine to medium coarse) (rounded some siltstone &amp; calcite).</i>           | <i>SONIC</i>    | <i>100%</i>       | <i>MOIST-DET</i>   | <i>DENSE</i>                    |        |           | <i>0</i>    |                |                                 |                                 |                   |                |             |        |             |          |  |
| <i>ALLUVIAL GRAVEL</i> | <i>8-8m Sandy fine to coarse GRAVEL with some silt. Grey mottled orange, very coarse, subrounded. Coarsely rounded to subrounded. Sand fine to coarse.</i>                                     | <i>SPT</i>      | <i>100%</i>       | <i>MOIST-DET</i>   | <i>DENSE</i>                    |        |           | <i>0</i>    |                |                                 |                                 |                   |                |             |        |             |          |  |

SPT @ 1.5m  
1, 0, 1, 2, 1, 1  
N=5


SPT @ 3-0m  
6, 12, 10, 9, 9, 11  
N=39

SPT @ 4-5m  
7, 10, 12, 12, 10, 9  
N=44

SPT @ 6-0m  
9, 12, 12, 17, 9  
N=50  
45mm remaining

SPT @ 7-5m  
7, 22, 25, 17, 8  
N=50  
120mm remaining

SPT @ 9-0m  
14, 16, 24, 26  
160mm remaining  
N=50+



COMMENTS: ALL SPT 'N' VALUES ARE UNCORRECTED

Survey Method:







**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,791 m** R.L.: **27 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,448 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |   | DEPTH (m) | GRAPHIC LOG  | SOIL / ROCK DESCRIPTION | GEOLOGICAL UNIT | R.L. (m) |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|---|-----------|--|-------------------------|-----------------|----------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT N                                   |           |  |                         |                 |          |
|            |                   | 0 %           | VE     |        |     |               |         |   | DBH1-0.4  | Asphalt.   |                         |                 |          |
|            |                   |               |        |        |     |               |         |   |           | Fine to coarse sandy fine to coarse GRAVEL; dark brownish grey; moist; non-plastic. Gravel; angular to sub-rounded; unweathered; basalt chips, brick fragments.    | Fill                    | 26.5            |          |
|            |                   |               |        |        |     |               |         |   |           |  |                         | 26.0            |          |
|            |                   |               |        |        |     |               |         |   |           |  |                         | 25.5            |          |
|            |                   |               |        |        |     |               |         |   |           |  |                         | 25.0            |          |
|            |                   |               |        |        |     |               |         |   |           |  |                         | 24.5            |          |
|            |                   |               |        |        |     |               |         |   |           |  |                         | 24.0            |          |
|            |                   | 89 %          | SPT    |        |     |               |         | 1<br>2<br>2<br>4<br>4<br>3<br>3<br>N=13 |           | Medium dense, silty fine to coarse sandy fine to coarse GRAVEL; light grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.       | Quaternary Alluvium     | 24.0            |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |   |           | Medium dense, fine to coarse sandy fine to coarse GRAVEL, trace silt; light grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. |                         | 23.5            |          |
|            |                   | 76 %          | SPT    |        |     |               |         | 2<br>2<br>3<br>3<br>7<br>7<br>N=20      |           | 4.30m, grey mottled orange   |                         | 23.0            |          |
|            |                   |               |        |        |     |               |         |   |           | 4.80m, light orange mottled grey   |                         | 22.5            |          |

DATE STARTED: 25/6/18 DRILLED BY: McNeill Drilling  
 DATE FINISHED: 25/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

COMMENTS:  
 Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 3.2m below ground level. SPT hammer efficiency = 87.8%.

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET

A4 Scale 1:25



**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,791 m** R.L.: **27 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,448 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |   | DEPTH (m) | GRAPHIC LOG | SOIL / ROCK DESCRIPTION   | GEOLOGICAL UNIT     | R.L. (m) |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|---|-----------|-------------|---|---------------------|----------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT 'N'   |           |             |   |                     |          |
|            |                   | 100 %         | Sonic  |        |     |               |         | 2<br>3<br>8<br>8<br>12<br>14<br>N=42              |           | 5.5         | Medium dense, fine to coarse sandy fine to coarse GRAVEL, trace silt; light orange mottled grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. | Quaternary Alluvium | 21.5     |
|            |                   | 89 %          | SPT    |        |     |               |         |   |           | 6.0         | from 6.00m, dense   |                     | 21.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         |   |           | 6.5         | 6.50m, light orange, oxidation  |                     | 20.5     |
|            |                   | 82 %          | SPT    |        |     |               |         | 9<br>10<br>12<br>9<br>7<br>9<br>N=37              |           | 7.0         |   |                     | 20.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         |   |           | 7.5         | 7.50m, dark orange  |                     | 19.5     |
|            |                   | 100 %         | Sonic  |        |     |               |         |   |           | 8.0         | "Dense", fine to coarse gravelly fine to coarse SAND; dark orange; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz.  |                     | 19.0     |
|            |                   | 78 %          | SPT    |        |     |               |         | 6<br>9<br>18<br>20<br>12<br>N=50+<br>for<br>200mm |           | 8.5         |   | 18.5                |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |   |           | 9.0         | "Dense" fine to coarse sandy fine to coarse GRAVEL; dark orange mottled grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.                    | 18.0                |          |
|            |                   |               |        |        |     |               |         |   |           | 9.5         | from 9.00m, very dense  | 17.5                |          |

DATE STARTED: 25/6/18 DRILLED BY: McNeill Drilling  
 DATE FINISHED: 25/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

COMMENTS:  
 Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 3.2m below ground level. SPT hammer efficiency = 87.8%.

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET





**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,791 m** R.L.: **27 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,448 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |         | DEPTH (m) | GRAPHIC LOG | SOIL / ROCK DESCRIPTION   | GEOLOGICAL UNIT | R.L. (m)   |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|---------|-----------|-------------|---|-----------------|--|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT 'N' |           |             |   |                 |  |
|            |                   | 100 %         | Sonic  |        |     |               |         | 4       |           | 10.5        | Very dense, fine to coarse sandy fine to coarse GRAVEL; dark orange mottled grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.  | 16.5            |  |
|            |                   | 78 %          | SPT    |        |     |               |         | 3       |           | 11.0        |   |                 | Very dense, fine to coarse gravelly fine to coarse SAND; dark orange; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz.            |
|            |                   | 100 %         | Sonic  |        |     |               |         | 19      |           | 11.5        | Dense, fine to coarse sandy fine to coarse GRAVEL; dark orange; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. Oxidisation.       | 15.5            |  |
|            |                   | 89 %          | SPT    |        |     |               |         | 18      |           | 12.0        |   |                 | Dense, fine to coarse SAND; some gravel; light orange mottled grey; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz. Oxidisation. |
|            |                   | 100 %         | Sonic  |        |     |               |         | 10      |           | 12.5        | Dense, fine to coarse gravelly fine to coarse SAND; light orange mottled grey; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz. Oxidisation. | 14.5            |  |
|            |                   | 89 %          | SPT    |        |     |               |         | 10      |           | 13.0        |   |                 | Dense, fine to coarse SAND; some gravel; light orange mottled grey; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz. Oxidisation. |
|            |                   | 100 %         | Sonic  |        |     |               |         | 10      |           | 13.5        | Dense, fine to coarse gravelly fine to coarse SAND; light orange mottled grey; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz. Oxidisation. | 13.5            |  |
|            |                   | 89 %          | SPT    |        |     |               |         | 9       |           | 14.0        |   |                 | Dense, fine to coarse SAND; some gravel; light orange mottled grey; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz. Oxidisation. |
|            |                   | 100 %         | Sonic  |        |     |               |         | 9       |           | 14.5        | Dense, fine to coarse gravelly fine to coarse SAND; light orange mottled grey; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz. Oxidisation. | 12.5            |  |
|            |                   | 100 %         | Sonic  |        |     |               |         | 9       |           | 14.5        |   |                 | Dense, fine to coarse SAND; some gravel; light orange mottled grey; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz. Oxidisation. |

DATE STARTED: 25/6/18 DRILLED BY: McNeill Drilling COMMENTS: Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 3.2m below ground level. SPT hammer efficiency = 87.8%.  
 DATE FINISHED: 25/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET



**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,791 m** R.L: **27 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,448 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        | IN-SITU TESTS |    |         | SAMPLES                                 | DEPTH (m) | GRAPHIC LOG                  | SOIL / ROCK DESCRIPTION  | GEOLOGICAL UNIT       | R.L (m) |        |
|------------|-------------------|---------------|--------|--------|---------------|----|---------|---|-----------|------------------------------|--|-----------------------|---------|--------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD           | SV | τ (kPa) |   |           |                              |  |                       |         | SPT N' |
|            |                   | 56 %          | SPT    |        |               |    |         | 17<br>21<br>29<br>N=50+<br>for<br>150mm |           |                              | Very dense, fine to coarse sandy fine to coarse GRAVEL; dark brownish orange; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. | Quaternary Alluvium   | 11.5    |        |
|            |                   | 100 %         | Sonic  |        |               |    |         |   |           | 15.65m, light greyish orange |  |                       | 11.0    |        |
|            |                   | 67 %          | SPT    |        |               |    |         | 7<br>9<br>9<br>11<br>11<br>12<br>N=43   |           | from 16.50m, medium dense    |  |                       | 10.5    |        |
|            |                   | 100 %         | Sonic  |        |               |    |         |   |           |                              | Medium dense, silty fine to coarse SAND; dark orange streaked black; moist, non-plastic.   | Gore Lignite Measures | 10.0    |        |
|            |                   | 100 %         | Sonic  |        |               |    |         |   |           |                              | Stiff, silty CLAY; dark brown streaked black; moist; high plasticity.  |                       |         |        |
|            |                   | 98 %          | SPT    |        |               |    |         | 3<br>8<br>8<br>8<br>9<br>11<br>N=36     |           |                              | Very stiff, LIGNITE; black; moist; non-plastic.  |                       |         | 9.5    |
|            |                   | 100 %         | Sonic  |        |               |    |         |   |           |                              | Medium dense, fine to coarse SAND, some silt; dark grey speckled black; moist; non-plastic.  |                       |         | 9.0    |
|            |                   |               |        |        |               |    |         |   |           |                              | 18.20m, saturated  |                       | 8.5     |        |
|            |                   |               |        |        |               |    |         |   |           |                              | Very stiff, LIGNITE, some clay; black; moist; non-plastic.   |                       | 8.0     |        |
|            |                   |               |        |        |               |    |         |   |           |                              | Dense, fine to coarse SAND, some silt, trace clay; dark grey; moist; non-plastic.  |                       | 7.5     |        |
|            |                   |               |        |        |               |    |         | 3<br>3<br>6<br>6<br>11<br>15<br>N=38    |           |                              | 19.80m, light grey   |                       |         |        |
|            |                   |               |        |        |               |    |         |   |           |                              | 19.90m, some gravel. Gravel: rounded to well rounded; weathered; quartz.   |                       |         |        |

DATE STARTED: 25/6/18 DRILLED BY: McNeill Drilling COMMENTS: Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 3.2m below ground level. SPT hammer efficiency = 87.8%.  
 DATE FINISHED: 25/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET



**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,791 m** R.L.: **27 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,448 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |         | DEPTH (m)                                   | GRAPHIC LOG          | SOIL / ROCK DESCRIPTION  | GEOLOGICAL UNIT | R.L. (m)          |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|---------|---|----------------------|--|-----------------|-------------------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT 'N' |   |                      |  |                 |                   |
|            |                   | 100 %         | Sonic  |        |     |               |         |         | 6<br>17<br>36<br>14<br>N=50+<br>for<br>90mm | 20.5                 | Dense, fine to coarse gravelly fine to coarse SAND, trace silt; light grey; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz.  |                 | 6.5               |
|            |                   | 49 %          | SPT    |        |     |               |         |         | 14<br>25<br>25<br>Bounce<br>for<br>5mm      | 21.0<br>21.5<br>22.0 | Very dense, fine to coarse sandy fine to coarse GRAVEL; light grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. |                 | 6.0<br>5.5<br>5.0 |
|            |                   | 100 %         | Sonic  |        |     |               |         |         | 21<br>31<br>30<br>Bounce<br>for<br>20mm     | 22.5<br>23.0<br>23.5 |  |                 | 4.5<br>4.0<br>3.5 |
|            |                   | 42 %          | SPT    |        |     |               |         |         |   | 24.0                 |  |                 | 3.0               |
|            |                   | 100 %         | Sonic  |        |     |               |         |         |   | 24.5                 | END OF LOG @ 24.45 m   |                 | 2.5               |
|            |                   | 36 %          | SPT    |        |     |               |         |         |   |                      |  |                 |                   |

DATE STARTED: 25/6/18 DRILLED BY: McNeill Drilling COMMENTS: Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 3.2m below ground level. SPT hammer efficiency = 87.8%.  
 DATE FINISHED: 25/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET



**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,779 m** R.L: **27 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,487 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |        | DEPTH (m) | GRAPHIC LOG   | SOIL / ROCK DESCRIPTION | GEOLOGICAL UNIT | R.L (m) |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|--------|-----------|---|-------------------------|-----------------|---------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT N' |           |   |                         |                 |         |
|            |                   | 0 %           | VE     |        |     |               |         |        |           | Concrete  |                         |                 |         |
|            |                   | 0 %           | VE     |        |     |               |         |        |           | Fine to coarse sandy silty CLAY, minor fine to medium gravel; light brownish orange; moist; low plasticity. Gravel: angular to sub-rounded; unweathered; basalt chips. Whole and partial bricks / fragments evident.    | Fill                    | 26.5            |         |
|            |                   | 0 %           | VE     |        |     |               |         |        |           | "Loose" silty fine to coarse gravelly fine to coarse SAND, some clay; dark reddish brown; moist; non-plastic. Gravel: angular to sub-rounded; unweathered; basalt chips and rounded to well rounded; weathered; quartz. | Fill                    | 26.0            |         |
|            |                   | 0 %           | VE     |        |     |               |         |        |           | "Loose" fine to coarse gravelly fine to coarse SAND, some silt; light grey speckled white; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz.  | Fill                    | 25.5            |         |
|            |                   | 0 %           | VE     |        |     |               |         |        |           | from 3.00m, medium dense<br>3.10m, oxidation  | Quaternary Alluvium     | 25.0            |         |
|            |                   | 0 %           | VE     |        |     |               |         |        |           | Medium dense, fine to coarse SAND, some silt; light grey mottled orange; moist; non-plastic.  | Quaternary Alluvium     | 24.5            |         |
|            |                   | 0 %           | VE     |        |     |               |         |        |           | Medium dense, fine to coarse sandy fine to coarse GRAVEL, minor silt; light grey mottled orange; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. Oxidation.                            | Quaternary Alluvium     | 24.0            |         |
|            |                   | 0 %           | VE     |        |     |               |         |        |           | 4.50m, light brownish orange  | Quaternary Alluvium     | 23.5            |         |
|            |                   | 0 %           | VE     |        |     |               |         |        |           |   | Quaternary Alluvium     | 23.0            |         |
|            |                   | 0 %           | VE     |        |     |               |         |        |           |   | Quaternary Alluvium     | 22.5            |         |

DATE STARTED: 28/6/18 DRILLED BY: McNeill Drilling  
 DATE FINISHED: 28/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: - / 90°

COMMENTS:  
 Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 2.8m below ground level. SPT hammer efficiency = 87.8%.

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET

A4 Scale 1:25

BECA LIB 1.074.018 Log BECA MACHINE BOREHOLE 5320381 - I.T. - DEE ST HOTEL.GPJ <<DrawingFile>> 30/07/2018 09:55 5.30.004 D:\gei\Lab and In Situ Tool - DGD\Lib Beas 1.074.2016-01-15 Proj Beas 1.07.2014-12-16



**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,779 m** R.L.: **27 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,487 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |   | DEPTH (m) | GRAPHIC LOG | SOIL / ROCK DESCRIPTION   | GEOLOGICAL UNIT     | R.L. (m) |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|---|-----------|-------------|---|---------------------|----------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT 'N'                                   |           |             |   |                     |          |
|            |                   | 100 %         | Sonic  |        |     |               |         | 7<br>10<br>7<br>7<br>13<br>21<br>N=48     |           | 5.5         | Medium dense, fine to coarse sandy fine to coarse GRAVEL, minor silt; light brownish orange; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. Oxidation. 5.15m, light reddish brown | Quaternary Alluvium | 21.5     |
|            |                   | 53 %          | SPT    |        |     |               |         |   |           | 6.0         | 5.50m, dark reddish brown   |                     | 21.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         | 8<br>9<br>10<br>11<br>12<br>12<br>N=45    |           | 6.5         | from 6.00m, very dense  |                     | 20.5     |
|            |                   | 69 %          | SPT    |        |     |               |         |   |           | 7.0         | 6.50m, light brownish grey  |                     | 20.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         | 9<br>13<br>29<br>21<br>N=50+<br>for 150mm |           | 8.0         | 8.20m, light greyish brown  |                     | 19.5     |
|            |                   | 47 %          | SPT    |        |     |               |         |   |           | 8.5         | 9.00m, light brownish orange speckled grey  |                     | 19.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         |   |           | 9.0         | Very dense, fine to coarse gravelly fine to coarse SAND, some silt; light brownish orange; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz.  | 18.5                |          |
|            |                   |               |        |        |     |               |         |   |           | 9.5         |   | 18.0                |          |
|            |                   |               |        |        |     |               |         |   |           |             |   | 17.5                |          |

DATE STARTED: 28/6/18 DRILLED BY: McNeill Drilling COMMENTS: Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 2.8m below ground level. SPT hammer efficiency = 87.8%.  
 DATE FINISHED: 28/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET



**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,779 m** R.L.: **27 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,487 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |  | DEPTH (m) | GRAPHIC LOG   | SOIL / ROCK DESCRIPTION  | GEOLOGICAL UNIT     | R.L. (m) |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|--|-----------|---|--|---------------------|----------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT 'N'  |           |   |  |                     |          |
|            |                   | 100 %         | Sonic  |        |     |               |         | 9<br>17<br>21<br>29<br>N=50+<br>for<br>145mm       |           | 10.5  | Very dense, fine to coarse gravelly fine to coarse SAND, some silt; light brownish orange; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz. 10.10m, light reddish brown | Quaternary Alluvium | 16.5     |
|            |                   | 38 %          | SPT    |        |     |               |         |  |           | 11.0  |  |                     | 16.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | 11.5  | 11.40m, light reddish grey   |                     | 15.5     |
|            |                   | 36 %          | SPT    |        |     |               |         | 6<br>14<br>19<br>20<br>11<br>N=50+<br>for<br>170mm |           | 12.0  | Very dense, fine to coarse sandy fine to coarse GRAVEL, minor silt; light brownish orange speckled grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.      |                     | 15.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | 12.5  | Very dense, fine to coarse gravelly fine to coarse SAND, some silt; light grey speckled orange; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz.                        |                     | 14.5     |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | 13.0  | Very dense, fine to coarse SAND, some gravel; light grey speckled orange; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz.  |                     | 14.0     |
|            |                   | 89 %          | SPT    |        |     |               |         | 2<br>4<br>8<br>11<br>12<br>11<br>N=42              |           | 13.5  | Very dense, fine to coarse gravelly fine to coarse SAND, trace silt; light greyish orange; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz. Oxidisation.                |                     | 13.5     |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | 14.0  | from 13.50m, dense<br>Dense, fine to coarse SAND, some gravel; light reddish orange speckled white; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz.                    |                     | 13.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | 14.5  | 13.95m, trace gravel<br>Dense, fine to coarse sandy fine to medium GRAVEL, trace silt; light reddish orange; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.  |                     | 12.5     |
|            |                   |               |        |        |     |               |         | 10   |           | 14.70m, light brownish grey speckled white, oxidation |  |                     |          |

DATE STARTED: **28/6/18** DRILLED BY: **McNeill Drilling** COMMENTS:  
 DATE FINISHED: **28/6/18** EQUIPMENT: **Sonic** Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 2.8m below ground level. SPT hammer efficiency = 87.8%.  
 LOGGED BY: **DD** DRILL METHOD: **Sonic/SPT/VE**  
 SHEAR VANE No: DRILL FLUID: **Water**  
 DIAMETER/INCLINATION: **- / 90°**

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET



**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,779 m R.L: 27 m**  
**E 1,242,487 m DATUM: MSL** COORDINATE ORIGIN: **hhGPS**  
 ACCURACY: **±5m**

| DRILLING   |                   |               |        |        | IN-SITU TESTS |    |         | SAMPLES   | DEPTH (m) | GRAPHIC LOG | SOIL / ROCK DESCRIPTION   | GEOLOGICAL UNIT       | R.L (m) |
|------------|-------------------|---------------|--------|--------|---------------|----|---------|---|-----------|-------------|---|-----------------------|---------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD           | SV | τ (kPa) |   |           |             |   |                       |         |
|            |                   | 49 %          | SPT    |        |               |    |         | 18<br>15<br>25<br>10<br>N=50+<br>for<br>160mm     |           |             | Very dense, fine to coarse sandy fine to medium GRAVEL, trace silt; light brownish grey speckled white; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. Oxidisation. | Quaternary Alluvium   | 11.5    |
|            |                   | 100 %         | Sonic  |        |               |    |         |   |           |             | 15.70m, light brownish orange, oxidisation  |                       | 11.0    |
|            |                   | 87 %          | SPT    |        |               |    |         | 3<br>11<br>17<br>27<br>6<br>N=50+<br>for<br>160mm |           |             | Very dense, fine to coarse sandy fine to coarse GRAVEL, some silt; light brownish orange; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.                            | Gore Lignite Measures | 10.5    |
|            |                   | 100 %         | Sonic  |        |               |    |         |   |           |             | 16.35m, minor clay; dark reddish orange; low plasticity   |                       | 10.0    |
|            |                   | 100 %         | Sonic  |        |               |    |         |   |           |             | Stiff, silty CLAY, trace fine sand; dark reddish orange streaked black; moist; high plasticity.   |                       |         |
|            |                   | 87 %          | SPT    |        |               |    |         | 2<br>6<br>9<br>12<br>14<br>14<br>N=49             |           |             | Very stiff, LIGNITE; black; moist; non-plastic.   |                       |         |
|            |                   | 60 %          | SPT    |        |               |    |         | 3<br>5<br>7<br>9<br>9<br>N=34                     |           |             | Medium dense, fine to coarse SAND; dark brownish grey; moist; non-plastic.  |                       |         |
|            |                   |               |        |        |               |    |         |   |           |             | from 18.00m, dense  |                       |         |
|            |                   |               |        |        |               |    |         |   |           |             | Stiff, silty CLAY, trace fine sand; dark greyish black; moist; high plasticity.   |                       |         |
|            |                   |               |        |        |               |    |         |   |           |             | Very stiff, LIGNITE, some clay; black; moist; non-plastic.  |                       |         |
|            |                   |               |        |        |               |    |         |   |           |             | Stiff, silty CLAY, trace fine sand; light grey streaked black; moist; high plasticity.  |                       |         |
|            |                   |               |        |        |               |    |         |   |           |             | Dense, fine to coarse SAND, trace clay; dark grey; moist; non-plastic.  |                       |         |

DATE STARTED: 28/6/18 DRILLED BY: McNeill Drilling  
 DATE FINISHED: 28/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

COMMENTS:  
 Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 2.8m below ground level. SPT hammer efficiency = 87.8%.

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET

A4 Scale 1:25

BECA LIB 1.074.GLB Log BECA MACHINE BOREHOLE 5320381 - I.T. - DEE ST HOTEL.GPJ <DrawingFile> 30/07/2018 09:55 5.30.04 D:\gei\Lab and In Situ Tool - DGD\Lib\Beca 1.074.2016-01-15.Pjt Beca 1.07.2014-12-16



**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,779 m** R.L.: **27 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,487 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |         | DEPTH (m)                              | GRAPHIC LOG  | SOIL / ROCK DESCRIPTION  | GEOLOGICAL UNIT       | R.L. (m)   |         |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|---------|--|--|--|-----------------------|--|---------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT 'N' |  |  |  |                       |  | SAMPLES |
|            |                   | 100 %         | Sonic  |        |     |               |         |         | 7<br>14<br>23<br>Bounce<br>for<br>5mm  | 20.5<br>21.0<br>21.5<br>22.0<br>22.5<br>23.0<br>23.5<br>24.0 | Dense, fine to coarse SAND, trace clay; dark grey; moist; non-plastic.<br>Very dense, fine to coarse sandy fine to coarse GRAVEL; light grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. | Gore Lignite Measures | 6.5<br>6.0<br>5.5<br>5.0<br>4.5<br>4.0<br>3.5<br>3.0 |         |
|            |                   | 49 %          | SPT    |        |     |               |         |         | 8<br>41<br>30<br>Bounce<br>for<br>35mm |  |  |                       |  |         |
|            |                   | 100 %         | Sonic  |        |     |               |         |         | 5<br>24<br>26<br>Bounce<br>for<br>15mm |  |  |                       |  |         |
|            |                   | 69 %          | SPT    |        |     |               |         |         |  |  |  |                       |  |         |
|            |                   | 100 %         | Sonic  |        |     |               |         |         |  |  |  |                       |  |         |
|            |                   | 53 %          | SPT    |        |     |               |         |         |  |  |  |                       |  |         |
|            |                   |               |        |        |     |               |         |         |  |  |  |                       |  |         |
|            |                   |               |        |        |     |               |         |         |  | 24.5   | END OF LOG @ 24.45 m   |                       |  | 2.5     |

DATE STARTED: 28/6/18 DRILLED BY: McNeill Drilling  
 DATE FINISHED: 28/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

COMMENTS:  
 Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 2.8m below ground level. SPT hammer efficiency = 87.8%.

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET

A4 Scale 1:25





**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,745 m** R.L.: **26 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,507 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |        | SAMPLES | DEPTH (m) | GRAPHIC LOG   | SOIL / ROCK DESCRIPTION | GEOLOGICAL UNIT | R.L. (m) |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|--------|---------|-----------|---|-------------------------|-----------------|----------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT N' |         |           |   |                         |                 |          |
|            |                   | 0 %           | VE     |        |     |               |         |        |         |           | Concrete  |                         |                 |          |
|            |                   |               |        |        |     |               |         |        |         |           | "Soft" fine to coarse sandy silty CLAY, minor fine to medium gravel; light brownish orange; moist; high plasticity. Gravel: angular to sub-rounded; unweathered; basalt chips, brick fragments.           |                         | 25.5            |          |
|            |                   |               |        |        |     |               |         |        |         |           | "Loose" clayey fine to coarse sandy fine to coarse GRAVEL, minor silt, minor clay; light brownish orange; moist; non-plastic. Gravel: angular to sub-rounded; unweathered; basalt chips, brick fragments. |                         | 25.0            |          |
|            |                   |               |        |        |     |               |         |        |         |           | 1.70m, light greyish orange   |                         |                 |          |
|            |                   |               |        |        |     |               |         |        |         |           | 2.00m, gravel: rounded to well rounded; weathered; quartz.  |                         | 24.0            |          |
|            |                   |               |        |        |     |               |         |        |         |           | 2.50m, light grey   |                         | 23.5            |          |
|            |                   |               |        |        |     |               |         |        |         |           | Medium dense, silty fine to coarse SAND, minor fine to coarse gravel; light grey speckled white; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz.                                  |                         | 23.0            |          |
|            |                   |               |        |        |     |               |         |        |         |           | Medium dense, fine to coarse sandy fine to coarse GRAVEL, minor silt; light grey speckled white; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.                         |                         |                 |          |
|            |                   |               |        |        |     |               |         |        |         |           | 3.40m, streaked orange  |                         | 22.5            |          |
|            |                   |               |        |        |     |               |         |        |         |           | 3.70m, trace silt, light brownish orange speckled grey  |                         |                 |          |
|            |                   |               |        |        |     |               |         |        |         |           | 4.20m, dark reddish brown   |                         | 22.0            |          |
|            |                   |               |        |        |     |               |         |        |         |           | from 4.50m, dense   |                         | 21.5            |          |

DATE STARTED: 27/6/18 DRILLED BY: McNeill Drilling COMMENTS: Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 2.2m below ground level. SPT hammer efficiency = 87.8%.  
 DATE FINISHED: 27/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET



**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,745 m** R.L.: **26 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,507 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |  | DEPTH (m) | GRAPHIC LOG                                   | SOIL / ROCK DESCRIPTION | GEOLOGICAL UNIT | R.L. (m) |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|--|-----------|---|-------------------------|-----------------|----------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT 'N'  |           |   |                         |                 |          |
|            |                   | 100 %         | Sonic  |        |     |               |         | 6<br>7<br>7<br>12<br>13<br>12<br>N=44                |           | 5.5 - 6.0m, light greyish brown               | Quaternary Alluvium     | 20.5            |          |
|            |                   | 93 %          | SPT    |        |     |               |         | 2<br>6<br>8<br>14<br>8<br>12<br>N=44                 |           | 7.5 - 8.0m, light greyish orange              |                         | 18.5            |          |
|            |                   | 100 %         | Sonic  |        |     |               |         | 5<br>6<br>11<br>13<br>12<br>14<br>N=50+<br>for 295mm |           | 8.30m, light greyish orange                   |                         | 17.5            |          |
|            |                   | 76 %          | SPT    |        |     |               |         |  |           | from 9.00m, very dense, light brownish orange |                         | 17.0            |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | 9.50m, light greyish brown                    |                         | 16.5            |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           |   |                         |                 |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           |   |                         |                 |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           |   |                         |                 |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           |   |                         |                 |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           |   |                         |                 |          |

DATE STARTED: 27/6/18 DRILLED BY: McNeill Drilling COMMENTS: Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 2.2m below ground level. SPT hammer efficiency = 87.8%.  
 DATE FINISHED: 27/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET



**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,745 m** R.L.: **26 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,507 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |   | DEPTH (m) | GRAPHIC LOG | SOIL / ROCK DESCRIPTION   | GEOLOGICAL UNIT | R.L. (m) |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|---|-----------|-------------|---|-----------------|----------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT 'N'   |           |             |   |                 |          |
|            |                   | 100 %         | Sonic  |        |     |               |         | 7<br>9<br>16<br>14<br>16<br>10<br>N=50+<br>for<br>280mm |           | 10.5        | Very dense, silty fine to coarse sandy fine to coarse GRAVEL; light greyish brown; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.   | 15.5            |          |
|            |                   | 76 %          | SPT    |        |     |               |         |   |           | 11.0        |   |                 |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |   |           | 11.5        | 11.20m, clay seam (30mm); light grey; moist; high plasticity<br>Very dense, silty fine to coarse sandy fine to coarse GRAVEL, some clay; light brownish orange; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.<br>11.40m, no clay | 14.5            |          |
|            |                   | 84 %          | SPT    |        |     |               |         | 5<br>6<br>10<br>10<br>11<br>N=37                        |           | 12.0        | Dense, fine to coarse SAND, minor silt; light greyish orange; moist; non-plastic.   |                 | 14.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         |   |           | 12.5        | Dense, fine to coarse sandy fine to coarse GRAVEL, minor silt; light brownish orange; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. Oxidisation.   | 13.5            |          |
|            |                   | 98 %          | SPT    |        |     |               |         | 4<br>8<br>12<br>19<br>19<br>N=50+<br>for<br>215mm       |           | 13.0        | 12.75m, dark brownish orange  |                 | 13.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         |   |           | 13.5        | 13.20m, light brownish orange   | 12.5            |          |
|            |                   |               |        |        |     |               |         |   |           | 14.0        | from 13.50m, very dense   |                 | 12.0     |
|            |                   |               |        |        |     |               |         |   |           | 14.5        | 14.15m, dark brown speckled orange  | 11.5            |          |
|            |                   |               |        |        |     |               |         |   |           |             | 14.35m, light greyish brown, oxidation  |                 |          |

Quaternary Alluvium

DATE STARTED: 27/6/18 DRILLED BY: McNeill Drilling COMMENTS: Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 2.2m below ground level. SPT hammer efficiency = 87.8%.  
 DATE FINISHED: 27/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET



**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,745 m** R.L.: **26 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,507 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        | IN-SITU TESTS |    |         | SAMPLES                                       | DEPTH (m) | GRAPHIC LOG | SOIL / ROCK DESCRIPTION  | GEOLOGICAL UNIT       | R.L. (m) |
|------------|-------------------|---------------|--------|--------|---------------|----|---------|---|-----------|-------------|--|-----------------------|----------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD           | SV | τ (kPa) |   |           |             |  |                       |          |
|            |                   | 76 %          | SPT    |        |               |    |         | 12<br>17<br>18<br>15<br>N=50+<br>for<br>180mm |           |             | Very dense, fine to coarse sandy fine to coarse GRAVEL, minor silt; light greyish brown; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. Oxidisation. | Quaternary Alluvium   | 10.5     |
|            |                   | 100 %         | Sonic  |        |               |    |         | 3<br>4<br>5<br>6<br>7<br>10<br>N=28           | DBH3-16.4 |             | Very stiff, LIGNITE, some clay; black; moist; non-plastic.   | Gore Lignite Measures | 10.0     |
|            |                   | 0 %           | SPT    |        |               |    |         | 3<br>4<br>5<br>6<br>7<br>10<br>N=28           |           |             | Medium dense, fine to coarse SAND, trace clay; dark brownish black; moist; non-plastic.  |                       | 9.5      |
|            |                   | 100 %         | Sonic  |        |               |    |         | 3<br>7<br>9<br>8<br>8<br>8<br>N=33            | DBH3-17.5 |             | Stiff, silty fine sandy CLAY; dark greyish black; moist; high plasticity.  |                       | 8.5      |
|            |                   | 56 %          | SPT    |        |               |    |         |   |           |             | Very stiff, LIGNITE, some clay; black; moist; low plasticity.  |                       | 8.0      |
|            |                   | 100 %         | Sonic  |        |               |    |         |   |           |             | Hard, silty fine sandy CLAY; dark greyish black; moist; high plasticity.   |                       | 7.5      |
|            |                   | 27 %          | SPT    |        |               |    |         |   | DBH3-19.0 |             | Dense, fine to coarse SAND, trace clay; light grey speckled white; moist; non-plastic.   | 7.0                   |          |
|            |                   |               |        |        |               |    |         |   |           |             | Dense, fine to coarse SAND, minor clay, minor silt; light grey speckled white; moist; non-plastic.   | 6.5                   |          |
|            |                   |               |        |        |               |    |         |   |           |             | 19.15m, trace fine to coarse gravel. Gravel: rounded to well rounded; weathered; quartz.   |                       |          |
|            |                   |               |        |        |               |    |         |   |           |             | Very dense, fine to coarse sandy fine to coarse GRAVEL; light grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.                                   |                       |          |

DATE STARTED: 27/6/18 DRILLED BY: McNeill Drilling COMMENTS: Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth. Borehole terminated at target depth. Groundwater encountered at 2.2m below ground level. SPT hammer efficiency = 87.8%.  
 DATE FINISHED: 27/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET



**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,745 m** R.L: **26 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,507 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |         | DEPTH (m) | GRAPHIC LOG | SOIL / ROCK DESCRIPTION  | GEOLOGICAL UNIT       | R.L (m) |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|---------|-----------|-------------|--|-----------------------|---------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT 'N' |           |             |  |                       |         |
|            |                   | 100 %         | Sonic  |        |     |               |         |         | 20        |             | Very dense, fine to coarse sandy fine to coarse GRAVEL; light grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. | Gore Lignite Measures | 5.5     |
|            |                   | 60 %          | SPT    |        |     |               |         |         | 21        |             |  |                       | 5.0     |
|            |                   |               |        |        |     |               |         |         | 23        |             |  |                       | 4.5     |
|            |                   |               |        |        |     |               |         |         | 10        |             |  |                       | 4.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         |         | 20        |             |  |                       | 3.5     |
|            |                   | 0 %           | SPT    |        |     |               |         |         | 10        |             |  |                       | 3.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         |         | 20        |             |  |                       | 2.5     |
|            |                   | 0 %           | SPT    |        |     |               |         |         | 10        |             |  |                       | 2.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         |         | 21        |             |  |                       | 1.5     |
|            |                   | 0 %           | SPT    |        |     |               |         |         | 10        |             |  |                       | 1.5     |
|            |                   |               |        |        |     |               |         |         | 20        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 26        |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 100       |             |  | 1.5                   |         |
|            |                   |               |        |        |     |               |         |         | 21        |             |  |                       |         |



**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,755 m R.L.: 27 m**  
**E 1,242,444 m** DATUM: **MSL** COORDINATE ORIGIN: **hhGPS**  
 ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |  | DEPTH (m) | GRAPHIC LOG   | SOIL / ROCK DESCRIPTION | GEOLOGICAL UNIT | R.L. (m) |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|--|-----------|---|-------------------------|-----------------|----------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT N  |           |   |                         |                 |          |
|            |                   | 0 %           | VE     |        |     |               |         |  |           | Asphalt.  |                         |                 |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |  | DBH4-0.7  | "Loose" fine to coarse sandy fine to coarse GRAVEL, minor silt, minor clay; dark brownish grey; moist; non-plastic. Gravel; angular to sub-rounded; unweathered; basalt chips, brick fragments.                               | Fill                    | 26.5            |          |
|            |                   | 78 %          | SPT    |        |     |               |         |  |           | 0.90m, dark brown   |                         | 26.0            |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | "Loose" silty fine to coarse sandy fine to coarse GRAVEL, minor clay; light brownish orange; moist; low plasticity. Gravel: angular to sub-rounded; unweathered; basalt chips and rounded to well rounded; weathered; quartz. |                         | 25.5            |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | "Loose" Fine to coarse sandy fine to coarse GRAVEL, minor silt; light brownish grey mottled orange; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.  |                         | 25.0            |          |
|            |                   |               |        |        |     |               |         | 0<br>1<br>5<br>5<br>5<br>5<br>5<br>5<br>N=21 |           | from 3.00m, medium dense  |                         | 24.5            |          |
|            |                   |               |        |        |     |               |         |  | DBH4-4.4  | Medium dense, fine to coarse sandy fine to coarse GRAVEL; light grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.  | Quaternary Alluvium     | 24.0            |          |
|            |                   | 82 %          | SPT    |        |     |               |         | 6<br>8<br>8<br>8<br>7<br>N=31                |           | Stiff, silty clay; light grey; moist; low plasticity.   |                         | 23.5            |          |
|            |                   |               |        |        |     |               |         |  |           | Dense, fine to coarse sandy fine to coarse GRAVEL; light grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.   |                         | 23.0            |          |
|            |                   |               |        |        |     |               |         |  |           |   |                         | 22.5            |          |

DATE STARTED: 26/6/18 DRILLED BY: McNeill Drilling COMMENTS: Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth maps. Borehole terminated at target depth. Groundwater encountered at ~2.0m below ground level (level uncertain due to inability to provide adequate settlement time - borehole reinstatement required). SPT hammer efficiency = 87.8%.  
 DATE FINISHED: 26/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET

A4 Scale 1:25

BECA LIB 1.074.GLB Log BECA MACHINE BOREHOLE 5320381 - I.T. - DEE ST HOTEL.GPJ <DrawingFile> 30/07/2018 09:55 5.30.004 Dajgel Lab and In Situ Tool - DGD Lib BeCa 1.07.4.2016-01-15 Pjt BeCa 1.07.2014-12-16





**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,755 m** R.L.: **27 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,444 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |  | DEPTH (m) | GRAPHIC LOG | SOIL / ROCK DESCRIPTION  | GEOLOGICAL UNIT     | R.L. (m) |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|--|-----------|-------------|--|---------------------|----------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT N  |           |             |  |                     |          |
|            |                   | 100 %         | Sonic  |        |     |               |         | 6<br>8<br>8<br>8<br>8<br>10<br>N=34                    |           | 5.5 - 6.0m  | Dense, fine to coarse sandy fine to coarse GRAVEL; light grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. 5.10m, mottled orange      | Quaternary Alluvium | 21.5     |
|            |                   | 93 %          | SPT    |        |     |               |         |  |           | 6.0 - 6.5m  | 5.60m, light orange mottled grey   |                     | 21.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | 6.5 - 7.0m  | Dense, fine to coarse gravelly fine to coarse SAND, some silt; light orange mottled grey; moist; non-plastic. Gravel: rounded to well rounded; weathered; quartz.          |                     | 20.5     |
|            |                   | 76 %          | SPT    |        |     |               |         | 5<br>8<br>11<br>16<br>19<br>4<br>N=50+<br>for<br>230mm |           | 7.0 - 7.5m  | Very dense, fine to coarse sandy fine to coarse GRAVEL, some silt; light brownish orange; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz. |                     | 20.0     |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | 7.5 - 8.0m  |  |                     | 19.5     |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | 8.0 - 8.5m  |  | 19.0                |          |
|            |                   | 93 %          | SPT    |        |     |               |         | 4<br>8<br>12<br>14<br>18<br>6<br>N=50+<br>for<br>230mm |           | 8.5 - 9.0m  |  | 18.5                |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | 9.0 - 9.5m  |  | 18.0                |          |
|            |                   |               |        |        |     |               |         |  |           | 9.5 - 10.0m |  | 17.5                |          |

DATE STARTED: 26/6/18 DRILLED BY: McNeill Drilling COMMENTS: Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth maps. Borehole terminated at target depth. Groundwater encountered at ~2.0m below ground level (level uncertain due to inability to provide adequate settlement time - borehole reinstatement required). SPT hammer efficiency = 87.8%.  
 DATE FINISHED: 26/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: - / 90°

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET





**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,755 m** R.L.: **27 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,444 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        | IN-SITU TESTS |    |         | SAMPLES  | DEPTH (m) | GRAPHIC LOG | SOIL / ROCK DESCRIPTION | GEOLOGICAL UNIT | R.L. (m) |
|------------|-------------------|---------------|--------|--------|---------------|----|---------|--|-----------|-------------|-------------------------|-----------------|----------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD           | SV | τ (kPa) |  |           |             |                         |                 |          |
|            |                   | 84 %          | SPT    |        |               |    |         | 14<br>14<br>14<br>14<br>8<br>N=50+<br>for<br>290mm     |           |             | Quaternary Alluvium     | 11.5            |          |
|            |                   | 100 %         | Sonic  |        |               |    |         |  |           |             |                         | 11.0            |          |
|            |                   | 0 %           | SPT    |        |               |    |         | 20<br>Bounce<br>for<br>75mm                            |           |             | Quaternary Alluvium     | 10.5            |          |
|            |                   | 100 %         | Sonic  |        |               |    |         |  |           |             |                         | 10.0            |          |
|            |                   | 56 %          | SPT    |        |               |    |         | 1<br>3<br>8<br>14<br>15<br>13<br>N=50+<br>for<br>290mm |           |             | Gore Lignite Measures   | 9.5             |          |
|            |                   | 100 %         | Sonic  |        |               |    |         |  |           |             |                         | 9.0             |          |
|            |                   | 27 %          | SPT    |        |               |    |         | 7<br>20<br>Bounce<br>for<br>150mm                      |           |             | Gore Lignite Measures   | 8.5             |          |
|            |                   |               |        |        |               |    |         |  |           |             |                         | 8.0             |          |
|            |                   |               |        |        |               |    |         |  |           |             | Gore Lignite Measures   | 7.5             |          |
|            |                   |               |        |        |               |    |         |  |           |             |                         |                 |          |

DATE STARTED: 26/6/18 DRILLED BY: McNeill Drilling COMMENTS:  
 DATE FINISHED: 26/6/18 EQUIPMENT: Sonic Coordinates were determined using a hand held GPS. Elevations were obtained  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE from Google Earth maps. Borehole terminated at target depth. Groundwater  
 SHEAR VANE No: DRILL FLUID: Water encountered at ~2.0m below ground level (level uncertain due to inability to provide  
 DIAMETER/INCLINATION: -/ 90° adequate settlement time - borehole reinstatement required). SPT hammer  
 efficiency = 87.8%.

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET





**MACHINE BOREHOLE LOG**

PROJECT: **Dee Street Hotel** JOB NUMBER: **5320381**  
 SITE LOCATION: **Refer Site Plan (Dee St - Don St)** CLIENT: **The Invercargill Licensing Trust**

CIRCUIT: **NZTM** BOREHOLE LOCATION:  
 COORDINATES: **N 4,849,755 m R.L.: 27 m** COORDINATE ORIGIN: **hhGPS**  
**E 1,242,444 m** DATUM: **MSL** ACCURACY: **±5m**

| DRILLING   |                   |               |        |        |     | IN-SITU TESTS |         |  | DEPTH (m) | GRAPHIC LOG | SOIL / ROCK DESCRIPTION  | GEOLOGICAL UNIT | R.L. (m) |
|------------|-------------------|---------------|--------|--------|-----|---------------|---------|--|-----------|-------------|--|-----------------|----------|
| FLUID LOSS | DAILY WATER LEVEL | CORE RECOVERY | METHOD | CASING | RQD | SV            | τ (kPa) | SPT 'N'                                |           |             |  |                 |          |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | 20.5        | Very dense, fine to coarse SAND, minor clay, trace fine gravel; light grey; moist; low plasticity. Gravel: rounded to well rounded; weathered; quartz. |                 | 6.5      |
|            |                   | 51 %          | SPT    |        |     |               |         | 11<br>25<br>50<br>N=50+<br>for<br>75mm |           | 21.0        | Very dense, fine to coarse sandy fine to coarse GRAVEL; light grey; moist; non-plastic (matrix). Gravel: rounded to well rounded; weathered; quartz.   |                 | 6.0      |
|            |                   | 100 %         | Sonic  |        |     |               |         | 7<br>32<br>25<br>Bounce<br>for<br>30mm |           | 21.5        |  |                 | 5.5      |
|            |                   | 0 %           | SPT    |        |     |               |         |  |           | 22.0        |  |                 | 5.0      |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | 22.5        |  |                 | 4.5      |
|            |                   | 100 %         | Sonic  |        |     |               |         |  |           | 23.0        |  | 4.0             |          |
|            |                   | 25 %          | SPT    |        |     |               |         | 17<br>25<br>Bounce<br>for<br>150mm     |           | 23.5        |  | 3.5             |          |
|            |                   |               |        |        |     |               |         |  |           | 24.0        |  | 3.0             |          |
|            |                   |               |        |        |     |               |         |  |           | 24.5        | END OF LOG @ 24.45 m   |                 | 2.5      |

DATE STARTED: 26/6/18 DRILLED BY: McNeill Drilling COMMENTS: Coordinates were determined using a hand held GPS. Elevations were obtained from Google Earth maps. Borehole terminated at target depth. Groundwater encountered at ~2.0m below ground level (level uncertain due to inability to provide adequate settlement time - borehole reinstatement required). SPT hammer efficiency = 87.8%.  
 DATE FINISHED: 26/6/18 EQUIPMENT: Sonic  
 LOGGED BY: DD DRILL METHOD: Sonic/SPT/VE  
 SHEAR VANE No: DRILL FLUID: Water  
 DIAMETER/INCLINATION: -/ 90°

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET

A4 Scale 1:25







**WATER**

Water level on date shown

**METHOD** (shows drilling method)

- OB open barrel
- Wash wash boring
- TT triple tube
- UT thin walled undisturbed tube
- SPT standard penetration test – open nose sampler
- Nc standard penetration test – solid nose sampler
- MA machine auger
- PS piston sample
- PCT percussion – top drive
- PCB percussion – bottom drive
- Conc concentrics
- Sonic sonic
- HA hand auger
- VE vacuum excavation

**SAMPLES**

- Dx Disturbed sample, number x
- Bx Bulk sample, number x
- Ux(d) Undisturbed sample, number x, tube diameter d in mm
- Wx Water sample, number x

**MOISTURE**

- Dry, looks and feels dry
- Moist, no free water on hand when remoulding
- Wet, free water on hand when remoulding
- Saturated, soil below water table

**SOIL AND ROCK DESCRIPTIONS**

**CONSISTENCY**

| Cohesive Soils | Undrained Shear Strength (kPa) |
|----------------|--------------------------------|
| Very soft      | <12                            |
| Soft           | 12 to 25                       |
| Firm           | 25 to 50                       |
| Stiff          | 50 to 100                      |
| Very stiff     | 100 to 200                     |
| Hard           | >200                           |

Soil and Rock Descriptions are generally as described in the NZ Geotechnical Society "Field Description of Soil and Rock – Guideline for the Field Classification and Description of Soil and Rock for Engineering Purposes", dated December 2005.

Vane Shear Strength measurements in accordance with the NZ Geotechnical Society "Guideline for hand held shear vane test" dated August 2001.

**IN SITU TESTS**

- SV = 40/10 In situ shear strength and remoulded shear strength respectively, as measured by Geotechnics/ Pilcon Shear Vane
- $\tau$  = 50/12 Vane shear strength and remoulded vane shear strength respectively, corrected to BS1377
- UTP = Unable To Penetrate with Shear Vane
- N = 15 SPT uncorrected blow count for 300mm penetration
- N<sub>c</sub> = 50+ SPT uncorrected blow count for 300 mm penetration using solid nose sampler

★ **Laboratory Test(s) carried out:**

- AL Atterberg limits
- UU Unconsolidated undrained triaxial
- PSD Particle size
- CU Consolidated undrained triaxial
- CONS Consolidation
- COMP Compaction
- UCS Unconfined compression

**WEATHERING**

- CW Completely weathered
- HW Highly weathered
- MW Moderately weathered
- SW Slightly weathered
- UW Unweathered

| Non-cohesive Soils | SPT – Uncorrected |
|--------------------|-------------------|
| Very loose         | 0 to 4            |
| Loose              | 4 to 10           |
| Medium dense       | 10 to 30          |
| Dense              | 30 to 50          |
| Very dense         | >50               |

**GRAPHIC LOG** (1 or a combination of the following)

|           |        |           |           |                |
|-----------|--------|-----------|-----------|----------------|
| Fill      | Silt   | Cobbles   | Sandstone | Fine igneous   |
| Core loss | Sand   | Boulders  | Limestone | Coarse igneous |
| Organics  | Shells | Mudstone  | Schist    |                |
| Clay      | Gravel | Siltstone | Basalt    |                |

**ORGANIC SOILS**

*Von Post Degree of Humification*

- H1 Completely unconverted and mud-free peat, when pressed gives clear water and plant structure is visible.
- H2 Practically unconverted and mud-free peat, when pressed gives almost clear water and plant structure is visible.
- H3 Very slightly decomposed or very slightly muddy peat, when pressed gives marked muddy water, no peat substance passes through the fingers and plant structure is less visible.
- H4 Slightly decomposed or slightly muddy peat, when pressed gives marked muddy water and plant structure is less visible.
- H5 Moderately decomposed or very muddy peat with growth structure evident but slightly obliterated.
- H6 Moderately decomposed or very muddy peat with indistinct growth structure.
- H7 Fairly well decomposed or very muddy peat but the growth structure can just be seen.
- H8 Well decomposed or very muddy peat with very indistinct growth structure.
- H9 Practically decomposed or mud-like peat in which almost no growth structure is evident.
- H10 Completely decomposed or mud peat where no growth structure can be seen, entire substance passes through the fingers when pressed.





**HAND AUGER LOG**

PROJECT: **ICC Water Tower & Control Building** JOB NUMBER: **4682750**  
 SITE LOCATION: **101 Doon St, Invercargill** CLIENT: **Invercargill City Council**

CIRCUIT: **NZTM** AUGER LOCATION: **North Water Tower (refer site plan)**  
 COORDINATES: **N 4,850,218 m R.L: 16 m COORDINATE ORIGIN: hhGPS**  
**E 1,243,443 m DATUM: NZVD2016 ACCURACY: ±5m**

| DEPTH (m) | SAMPLES                 | GRAPHIC LOG             | SOIL / ROCK DESCRIPTION  | GEOLOGICAL UNIT | Scala (Blows/100mm) | SV | τ (kPa) | WATER LEVEL | R.L (m) |
|-----------|-------------------------|-------------------------|--|-----------------|---------------------|----|---------|-------------|---------|
| 0.5       | [Cross-hatched pattern] | [Cross-hatched pattern] | Loose silty fine SAND, some organics; brown; moist; non-plastic. Organics: grass, rootlets. [Topsoil]  | FILL            | 1                   |    |         |             | 15.5    |
|           |                         |                         | Very loose to loose silty fine to coarse SAND, trace fine gravel; brown mottled orange; moist; non-plastic. Gravel: angular, moderately weathered, black to orange, quartz to brick fragments. |                 | 2                   |    |         |             |         |
|           |                         |                         | From 0.60m: some fine to medium gravel.  |                 | 1                   |    |         |             |         |
|           |                         |                         | From 0.85m: speckled white.  |                 | 1                   |    |         |             |         |
| 1.0       |                         |                         | END OF LOG @ 1 m   |                 | 2                   |    |         | 15.0        |         |
| 1.5       |                         |                         |  |                 | 2                   |    |         |             |         |
| 2.0       |                         |                         |  |                 | 3                   |    |         |             |         |
| 2.5       |                         |                         |  |                 | 4                   |    |         |             |         |
| 3.0       |                         |                         |  |                 | 3                   |    |         |             |         |
| 3.5       |                         |                         |  |                 |                     |    |         |             |         |
| 4.0       |                         |                         |  |                 |                     |    |         |             |         |
| 4.5       |                         |                         |  |                 |                     |    |         |             |         |

DATE AUGERED: **17/6/19** DIAMETER: **50 mm**  
 LOGGED BY: **DD** METHOD: **HA**  
 SHEAR VANE No: **N/A**

COMMENTS:  
 Co-ordinates by hand held GPS to an accuracy of +/-3m. Elevation by topographic maps to an accuracy of +/-5m. Hand auger terminated due to refusal. Scala refusal at 1.0m, 8 consecutive blows with less than 20mm advance. No groundwater encountered.

FOR EXPLANATION OF SYMBOLS AND ABBREVIATIONS SEE KEY SHEET  
 A4 Scale 1:25



| STANDARD TEST                               |                |                        |  |
|---|----------------|------------------------|--|
| SITE Southland Museum                       |                | JOB No                 |  |
| BORE No 1                                   | DATE 30/9/2010 | EQUIP No T555 Schramm  |  |
| CO-ORDS                                     | DATUM          | SURFACE R.L.           |  |
| PLANT & TECHNIQUE                           |                |                        |  |
| ROD mm                                      | CASING 150mm   | G.W.L. 1.6m            |  |
| TECHNICIAN Evan Pascoe                      |                | CHECKED Maurice Pascoe |  |
| TEST SPECIFICATION NZS 4402 Test 6.5.1:1988 |                |                        |  |

| Penetration (blows) | Depth .... 1.5m | Penetration (blows) | Depth ..... | Soil Description          |
|---------------------|-----------------|---------------------|-------------|---------------------------|
| 2 75 mm             | Clay            |                     |             | N = 10<br>N = blows/300mm |
| 2 150               |                 |                     |             |                           |
| 2 225               |                 |                     |             |                           |
| 2 300               |                 |                     |             |                           |
| 2 375               |                 |                     |             |                           |
| 4 450               |                 |                     |             |                           |

| Penetration (blows) | Depth .... 3.0m | Penetration (blows) | Depth ..... | Soil Description          |
|---------------------|-----------------|---------------------|-------------|---------------------------|
| 3 75 mm             | Grey Sand       |                     | 75 mm       | N = 25<br>N = blows/300mm |
| 3 150               |                 |                     | 150         |                           |
| 4 225               |                 |                     | 225         |                           |
| 4 300               |                 |                     | 300         |                           |
| 8 375               |                 |                     | 375         |                           |
| 9 450               |                 |                     | 450         |                           |

| Penetration (blows) | Depth .... 4.5m   | Penetration (blows) | Depth ..... | Soil Description          |
|---------------------|-------------------|---------------------|-------------|---------------------------|
| 3 75 mm             | Silt onto gravels |                     | 75 mm       | N = 30<br>N = blows/300mm |
| 2 150               |                   |                     | 150         |                           |
| 4 225               |                   |                     | 225         |                           |
| 4 300               |                   |                     | 300         |                           |
| 7 375               |                   |                     | 375         |                           |
| 15 450              |                   |                     | 450         |                           |

| Penetration (blows) | Depth .... 6.0m | Penetration (blows) | Depth.... | Soil Description                         |
|---------------------|-----------------|---------------------|-----------|--|
| 5 75 mm             | Gravels         |                     | 75 mm     | N = 60 blows for 300m<br>N = blows/300mm |
| 11 150              |                 |                     | 150       |  |
| 14 225              |                 |                     | 225       |  |
| 30 300              |                 |                     | 300       |  |
|                     |                 |                     | 375       |  |
|                     |                 |                     | 450       |  |

- 0 - 0.4 GRAVEL FILL
- 0.4 - 2.8 YELLOW CLAY
- 2.8 - 4.45 GREY SAND
- 4.45 - 4.5 BLUE SILT
- 4.5 - 6.0 QUARTZ GRAVELS & SAND



| STANDARD                                     |                 | TEST                       |                     |
|--|-----------------|----------------------------|---------------------|
| SITE ...Southland Museum.....                |                 | JOB No .....               |                     |
| BORE No BH2.....                             | DATE 30-09-2010 | EQUIP No T555 Schramm.     |                     |
| CO-ORDS .....                                |                 | DATUM .....                | m SURFACE R.L. .... |
| PLANT & TECHNIQUE .....                      |                 |                            |                     |
| ROD .....mm CASING ...150mm G.W.L. ...1.650m |                 |                            |                     |
| TECHNICIAN .....Evan Pascoe                  |                 | CHECKED.....Maurice Pascoe |                     |
| TEST SPECIFICATION NZS 4402 Test 6.5.1:1988  |                 |                            |                     |

| Penetration (blows) | Depth .... 1.5m<br>Soil Description | Penetration (blows) | Depth .....      |     |
|---------------------|-------------------------------------|---------------------|------------------|-----|
| 1 75 mm             | Clay                                | 75 mm               | Soil Description |     |
| 2 150               |                                     | 150                 |                  |     |
| 1 225               |                                     | 225                 |                  |     |
| 2 300               |                                     | 300                 |                  |     |
| 1 375               |                                     | N =                 |                  | 375 |
| 2 450               |                                     | N = blows/300mm     |                  | 450 |
|                     |                                     |                     | N =              |     |
|                     |                                     |                     | N = blows/300mm  |     |

| Penetration (blows) | Depth .... 3.m<br>Soil Description | Penetration (blows) | Depth .....      |     |
|---------------------|------------------------------------|---------------------|------------------|-----|
| 3 75 mm             | Gray sand                          | 75 mm               | Soil Description |     |
| 4 150               |                                    | 150                 |                  |     |
| 5 225               |                                    | 225                 |                  |     |
| 6 300               |                                    | 300                 |                  |     |
| 7 375               |                                    | N =                 |                  | 375 |
| 8 450               |                                    | N = blows/300mm     |                  | 450 |
|                     |                                    |                     | N =              |     |
|                     |                                    |                     | N = blows/300mm  |     |

| Penetration (blows) | Depth .... 4.5m<br>Soil Description | Penetration (blows) | Depth .....      |     |
|---------------------|-------------------------------------|---------------------|------------------|-----|
| 2 75 mm             | Gray sand into gravel               | 75 mm               | Soil Description |     |
| 2 150               |                                     | 150                 |                  |     |
| 13 225              |                                     | 225                 |                  |     |
| 15 300              |                                     | 300                 |                  |     |
| 20 375              |                                     | N =                 |                  | 375 |
| 25 450              |                                     | N = blows/300mm     |                  | 450 |
|                     |                                     |                     | N =              |     |
|                     |                                     |                     | N = blows/300mm  |     |

| Penetration (blows) | Depth ..... 6m.....<br>Soil Description | Penetration (blows) | Depth....        |     |
|---------------------|---|---------------------|------------------|-----|
| 6 75 mm             | Gravels                                 | 75 mm               | Soil Description |     |
| 7 150               |   | 150                 |                  |     |
| 14 225              |   | 225                 |                  |     |
| 16 300              |   | 300                 |                  |     |
| 17 375              |   | N =                 |                  | 375 |
| 18 450              |   | N = blows/300mm     |                  | 450 |
|                     |   |                     | N =              |     |
|                     |   |                     | N = blows/300mm  |     |

- |            |                       |
|------------|-----------------------|
| 0 - .3m    | Gravel fill           |
| .3 - 2.7m  | Yellow clay           |
| 2.7 - 4.6m | Grey sand             |
| 4.6 - 6.0m | Quartz gravels & sand |




















**APPENDIX 3:**  
Test Pit Logs

## Geotechnical Soil Logging Key

ENGEO borehole and test pit logs are written in general accordance with the New Zealand Geotechnical Society field classification guidelines (2005).  
Please refer to this document for the methods of field classification and description for engineering purposes.

| Grain Size (mm)                                 |      |        |        |        |        |        |        | Additional Info |              |                      |
|---|------|--------|--------|--------|--------|--------|--------|-----------------|--------------|----------------------|
| 0.06    0.2    0.6    2    6    20    60    200 |      |        |        |        |        |        |        |                 |              |                      |
| SILT<br>and<br>CLAY                             | SAND |        |        | GRAVEL |        |        | COBBLE | BOULDER         | ▼            | Standing water level |
|   | Fine | Medium | Coarse | Fine   | Medium | Coarse |        |                 | UTP          | Unable to Penetrate  |
|   |      |        |        |        |        |        |        | NA              | Not Assessed |                      |

| Graphic Logs   |                         |  |  |  |   |              |                                      |  |  |  |   |
|--|-------------------------|--|--|--|---|--------------|--------------------------------------|--|--|--|---|
| The graphic log shows soil types and their corresponding UCS classification  |                         |  |  |  |   |              |                                      |  |  |  |   |
| Granular Soil (>65% of soil >0.06 mm)  |                         |  |  |  | Cohesive Soil (>35% of soil <0.06 mm)   |              |                                      |  |  |  |   |
| GW   | Well graded GRAVEL      |  |  |  |    | MH           | High plasticity SILT                 |  |  |  |    |
| GP   | Poorly graded GRAVEL    |  |  |  |    | ML           | Low plasticity SILT                  |  |  |  |    |
| GM   | Silty GRAVEL            |  |  |  |    | CH           | High plasticity CLAY                 |  |  |  |    |
| GC   | Clayey GRAVEL           |  |  |  |    | CL           | Low plasticity CLAY                  |  |  |  |    |
| SW   | Well graded SAND        |  |  |  |    | Organic Soil |                                      |  |  |  |   |
| SP   | Poorly graded SAND      |  |  |  |    | OH           | High Plasticity organic SILT or CLAY |  |  |  |    |
| SM   | Silty SAND              |  |  |  |    | OL           | Low plasticity organic SILT or CLAY  |  |  |  |    |
| SC   | Clayey SAND             |  |  |  |   | PT           | Peat                                 |  |  |  |   |
| Other Soils  |                         |  |  |  |   |              |                                      |  |  |  |   |
| TS/BTS   | Topsoil/ Buried Topsoil |  |  |  |  | F            | Fill                                 |  |  |  |  |
| G = Gravel    W = Well Graded    P = Poorly Graded    C = Clay    S = Sand    M = Silt    H = High Plasticity    L = Low Plasticity    O = Organic |                         |  |  |  |   |              |                                      |  |  |  |   |

| Cohesive Soils - Consistency Index |            |                                |  |
|------------------------------------|------------|--------------------------------|--|
|                                    |            | Undrained shear strength (kPa) | Field Diagnostic Features  |
| VS                                 | Very Soft  | <12                            | Easily exudes between fingers when squeezed                              |
| S                                  | Soft       | 12 – 25                        | Easily indented by fingers   |
| F                                  | Firm       | 25 – 50                        | Indented by strong finger pressure and can be indented by thumb pressure |
| St                                 | Stiff      | 50 – 100                       | Cannot be indented by thumb pressure                                     |
| VSt                                | Very Stiff | 100 – 200                      | Can be indented by thumb nail  |
| H                                  | Hard       | 200+                           | Difficult to indent by thumb nail  |

| Moisture Content |           |  |
|------------------|-----------|--|
| D                | Dry       | Looks and feels dry  |
| M                | Moist     | Feels cool and darkened in colour and granular soils tend to be cohere   |
| W                | Wet       | Feels cool and darkened in colour. Granular soils tend to cohere and free water forms when remoulding cohesive soils |
| S                | Saturated | Feels cool, darkened in colour and free water present on the sample  |

| Granular Soils - Density Index |              |                              |                                   |
|--------------------------------|--------------|------------------------------|-----------------------------------|
|                                |              | SPT 'N' Value (blows /300mm) | Scala Penetrometer (blows/100 mm) |
| VL                             | Very loose   | <4                           | 0 - 2                             |
| L                              | Loose        | 4 – 10                       | 1 – 3                             |
| MD                             | Medium Dense | 10 - 30                      | 3 - 7                             |
| D                              | Dense        | 30 - 50                      | 7 – 17                            |
| VD                             | Very Dense   | >50                          | >17                               |

| Proportional Terms Definition |                |           |                 |
|-------------------------------|----------------|-----------|-----------------|
| Fraction                      | Term           | % of Soil | Example         |
| Major                         | (UPPERCASE)    | >50       | GRAVEL          |
| Subordinate                   | (lowercase)y   | 20 - 50   | Sandy           |
| Minor                         | With some....  | 12 - 20   | With some sand  |
|                               | With minor.... | 5 - 12    | With minor sand |
|                               | With trace.... | <5        | With trace sand |

| Soil Structure |  |                     |   |
|----------------|--|---------------------|---|
| Zoning         |  | Cementing           |   |
| Layers         | Continuous across exposure or sample       | Weakly Cemented     | Easily broken up by hand in air or water                        |
| Lenses         | Discontinuous layers of lenticular shape   | Moderately cemented | Effort is required to break up the soil by hand in air or water |
| Pockets        | Irregular inclusions of different material |                     |   |

108 Gala Street, Queens Park  
Invercargill  
17651

Client : ICC  
Date : 06/09/2020  
Max Test Pit Depth : 2 m  
Digger Type/Size : Bucket Excavator  
Bucket Type/Size : Soil/Rock Bucket

Shear Vane No : 2534  
Logged By : BRCO  
Reviewed By : SSM  
Latitude : -46.40537  
Longitude : 168.3533

| Depth (m BGL) | Excavatability (Relative Scale) |        | USCS Symbol | DESCRIPTION   | Graphic Symbol              | Elevation (mRL) | Water Level | Moisture Cond. | Consistency/<br>Density Index | Shear Vane<br>Peak/Remoulded<br>(kPa) | Scala Penetrometer |  |  |  |  |  |  |
|---------------|---------------------------------|--------|-------------|---|-----------------------------|-----------------|-------------|----------------|-------------------------------|---------------------------------------|--------------------|--|--|--|--|--|--|
|               | Easier                          | Harder |             |   |                             |                 |             |                |                               |                                       | Blows per 100mm    |  |  |  |  |  |  |
| 0.0 - 0.5     | FILL                            |        | GW          | Sandy fine to coarse GRAVEL, dark grey. Tightly packed, dry, well graded. Gravel, fine to coarse, subangular to subrounded. [FILL].<br>Grades to yellow brown.  | [Cross-hatched pattern]     |                 |             | D              | TP                            |                                       |                    |  |  |  |  |  |  |
| 0.5 - 0.6     |                                 |        | GW          | ASHPALT and medium to coarse GRAVEL, black. Tightly packed, dry, well graded. Gravel, subrounded to subangular. [FILL].   | [Cross-hatched pattern]     |                 |             | D              | TP                            | 92/21                                 |                    |  |  |  |  |  |  |
| 0.6 - 0.9     |                                 |        | CH          | Silty CLAY with trace organics, grey. Stiff, moist, high plasticity. Organics, amorphous. [ALLUVIUM].<br>Laboratory data @ 0.5 m : Fines with minor sand; LL-55, PL-32, PI-23.  | [Light blue vertical lines] |                 |             | M              | F                             | 140/38                                |                    |  |  |  |  |  |  |
| 0.9 - 2.0     | ALLUVIUM                        |        | ML          | SILT with trace clay, yellow brown. Stiff to very stiff, moist, low plasticity. [ALLUVIUM].<br>0.9 m : seepage from base / side of excavation.<br>Laboratory data @ 0.5 m : Fines with minor sand; LL-43, PL-28, PI-15. | [Light blue vertical lines] | 15              | ▼           | M              | St - VSt                      | 92/27                                 |                    |  |  |  |  |  |  |
|               |                                 |        |             | Depth of Excavation: 2 m<br>Termination Condition: Target depth   |                             | 14              |             |                |                               |                                       |                    |  |  |  |  |  |  |

GEOTECH TEST PIT LOG - PHOTOS 17651 - SMAG TEST PITS.GPJ - NZ MASTER DATA TEMPLATE.GDT 19/11/20



Test pit met target depth at 2 m.  
Scala Penetrometer met target depth at 2 m.

LL - Liquid Limit; PL - Plastic Limit; PI - Plasticity Index



108 Gala Street, Queens Park  
Invercargill  
17651

Client : ICC  
Date : 06/09/2020  
Max Test Pit Depth : 2 m  
Digger Type/Size : Bucket Excavator  
Bucket Type/Size : Rock Bucket

Shear Vane No : 2534  
Logged By : BRCCO  
Reviewed By : SSM  
Latitude : -46.40503  
Longitude : 168.35377

| Depth (m BGL) | Material | Excavability (Relative Scale) |        | USCS Symbol | DESCRIPTION  | Graphic Symbol | Elevation (mRL) | Water Level | Moisture Cond. | Consistency/<br>Density Index | Shear Vane<br>Peak/Remoulded<br>(kPa) | Scala Penetrometer |  |  |  |  |
|---------------|----------|-------------------------------|--------|-------------|--|----------------|-----------------|-------------|----------------|-------------------------------|---------------------------------------|--------------------|--|--|--|--|
|               |          | Easier                        | Harder |             |  |                |                 |             |                |                               |                                       | Blows per 100mm    |  |  |  |  |
| 0.0 - 0.5     | TOPSOIL  |                               |        | OL          | Organic SILT, dark brown. Firm, moist, low plasticity. [TOPSOIL].  |                |                 |             | M              | F                             |                                       |                    |  |  |  |  |
| 0.5 - 0.8     | FILL     |                               |        | OL          | Organic SILT with minor to some gravel. Firm, moist, non-plastic. Gravel, medium to coarse, subrounded. [FILL].  |                |                 |             | M              | F                             |                                       |                    |  |  |  |  |
| 0.8 - 1.0     |          |                               |        | SW          | Silty fine to coarse SAND with some charcoal and trace to minor gravel, black. Loose, moist, well graded. Gravel, fine to coarse, subrounded to subangular, schist. [FILL].  |                |                 |             | M              | L                             |                                       |                    |  |  |  |  |
| 1.0 - 1.4     | ALLUVIUM |                               |        | OL          | Organic SILT with minor organics, dark brown. Firm, moist, non-plastic. Organics, roots up to 5 cm diameter. [FILL].   |                | 15              |             | M              | F                             | 142/28                                |                    |  |  |  |  |
| 1.4 - 2.0     |          |                               |        | ML          | SILT with trace organics, grey with some orange/brown mottling. Stiff to very stiff, moist, low plasticity. Organics, amorphous and fibrous. [ALLUVIUM].<br>1.4 m : Minor seepage from side of excavation<br>Laboratory data @ 1.5 m : Fines with minor sand; LL-28, PL-21, PI-7.<br>Laboratory data @ 0.5 m : Fines with minor sand; LL-32, PL-22, PI-10. |                | 14              |             | M              | St - VSt                      | 115/24                                |                    |  |  |  |  |
| 2.0 - 2.5     |          |                               |        |             | Depth of Excavation: 2 m<br>Termination Condition: Target depth  |                |                 |             |                |                               |                                       |                    |  |  |  |  |

GEOTECH TEST PIT LOG - PHOTOS - SMAG TEST PITS.GPJ - NZ MASTER DATA TEMPLATE.GDT - 19/11/20



Test pit met target depth at 2 m.  
Scala Penetrometer met target depth at 2 m.


LL - Liquid Limit; PL - Plastic Limit; PI - Plasticity Index

**APPENDIX 4:**  
Laboratory Testing Results



## TEST REPORT – SOUTHLAND MUSEUM INVESTIGATIONS

|                      |  |                      |           |
|----------------------|--|----------------------|-----------|
| Client Details:      | ENGEO, 25 Glenda Drive, Frankton, Queenstown | Attention:           | S. Murray |
| Job Description:     | Southland Museum Investigations              |                      |           |
| Sample Description:  | SILT with minor sand                         | Client Reference No: | 17651     |
| Sample Source:       | TP01 @ 0.5m                                  | Sample Label No:     | N/A       |
| Date & Time Sampled: | Unknown                                      | Sampled By:          | Unknown   |
| Sample Method:       | Test Pit *                                   | Date Received:       | 28-Oct-20 |



| WATER CONTENT, PLASTICITY INDEX & SOLID DENSITY RESULTS<br>(NZS 4402:1986, Test 2.1, 2.2, 2.3, 2.4 & 2.7.2)                                   |                       |
|---|-----------------------|
| Water Content: ("All In" As Received)   | 38.0 %                |
| Liquid Limit: (LL)  | 55                    |
| Plastic Limit: (PL)   | 32                    |
| Plasticity Index: (PI)  | 23                    |
| Solid Density "All In" (vacuum method):   | 2.69 t/m <sup>3</sup> |
| <i>Note: The sample was received in a natural state. The plasticity index material tested was the fraction passing the 425 µm test sieve.</i> |                       |

## Notes:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method \* and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 29-Oct-20 to 2-Nov-20

Checked By:




Test results indicated as not accredited are outside the scope of the laboratory's accreditation





## TEST REPORT – SOUTHLAND MUSEUM INVESTIGATIONS

|                      |  |                      |           |
|----------------------|--|----------------------|-----------|
| Client Details:      | ENGEO, 25 Glenda Drive, Frankton, Queenstown | Attention:           | S. Murray |
| Job Description:     | Southland Museum Investigations              |                      |           |
| Sample Description:  | SILT with minor sand                         | Client Reference No: | 17651     |
| Sample Source:       | TP01 @ 0.9m - 1.0m                           | Sample Label No:     | N/A       |
| Date & Time Sampled: | Unknown                                      | Sampled By:          | Unknown   |
| Sample Method:       | Test Pit *                                   | Date Received:       | 28-Oct-20 |



| WATER CONTENT & PLASTICITY INDEX RESULTS - NZS 4402:1986, Test 2.1, 2.2, 2.3 & 2.4  |        |
|---|--------|
| Water Content: ("All In" As Received)   | 36.5 % |
| Liquid Limit: (LL)  | 43     |
| Plastic Limit: (PL)   | 28     |
| Plasticity Index: (PI)  | 15     |
| <i>Note: The sample was received in a natural state. The plasticity index material tested was the fraction passing the 425 µm test sieve.</i> |        |

## Notes:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method \* and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 29-Oct-20 to 2-Nov-20

Checked By:




Test results indicated as not accredited are outside the scope of the laboratory's accreditation



## TEST REPORT – SOUTHLAND MUSEUM INVESTIGATIONS

|                      |  |                      |           |
|----------------------|--|----------------------|-----------|
| Client Details:      | ENGEO, 25 Glenda Drive, Frankton, Queenstown | Attention:           | S. Murray |
| Job Description:     | Southland Museum Investigations              |                      |           |
| Sample Description:  | SILT with minor sand                         | Client Reference No: | 17651     |
| Sample Source:       | TP02 @ 1.5m                                  | Sample Label No:     | N/A       |
| Date & Time Sampled: | Unknown                                      | Sampled By:          | Unknown   |
| Sample Method:       | Test Pit *                                   | Date Received:       | 28-Oct-20 |



| WATER CONTENT, PLASTICITY INDEX & SOLID DENSITY RESULTS<br>(NZS 4402:1986, Test 2.1, 2.2, 2.3, 2.4 & 2.7.2)                                   |                       |
|---|-----------------------|
| Water Content: ("All In" As Received)   | 23.1 %                |
| Liquid Limit: (LL)  | 28                    |
| Plastic Limit: (PL)   | 21                    |
| Plasticity Index: (PI)  | 7                     |
| Solid Density "All In" (vacuum method):   | 2.74 t/m <sup>3</sup> |
| <i>Note: The sample was received in a natural state. The plasticity index material tested was the fraction passing the 425 µm test sieve.</i> |                       |

## Notes:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method \* and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 29-Oct-20 to 2-Nov-20

Checked By:




Test results indicated as not accredited are outside the scope of the laboratory's accreditation



## TEST REPORT – SOUTHLAND MUSEUM INVESTIGATIONS

|                                 |  |                             |           |
|---------------------------------|--|-----------------------------|-----------|
| <b>Client Details:</b>          | ENGEO, 25 Glenda Drive, Frankton, Queenstown | <b>Attention:</b>           | S. Murray |
| <b>Job Description:</b>         | Southland Museum Investigations              |                             |           |
| <b>Sample Description:</b>      | SILT with minor sand                         | <b>Client Reference No:</b> | 17651     |
| <b>Sample Source:</b>           | TP02 @ 1.9m                                  | <b>Sample Label No:</b>     | N/A       |
| <b>Date &amp; Time Sampled:</b> | Unknown                                      | <b>Sampled By:</b>          | Unknown   |
| <b>Sample Method:</b>           | Test Pit *                                   | <b>Date Received:</b>       | 28-Oct-20 |



| WATER CONTENT & PLASTICITY INDEX RESULTS - NZS 4402:1986, Test 2.1, 2.2, 2.3 & 2.4 |        |
|--|--------|
| <b>Water Content: ("All In" As Received)</b>                                       | 24.7 % |
| <b>Liquid Limit: (LL)</b>  | 32     |
| <b>Plastic Limit: (PL)</b>   | 22     |
| <b>Plasticity Index: (PI)</b>  | 10     |

*Note: The sample was received in a natural state. The plasticity index material tested was the fraction passing the 425 µm test sieve.*

## Notes:

- Information contained in this report which is Not IANZ Accredited relates to the sample descriptions based on NZ Geotechnical Society Guidelines 2005, the sample method \* and sampling.
- This report may not be reproduced except in full.

Tested By: L.T. Smith

Date: 29-Oct-20 to 2-Nov-20

Checked By:

Approved Signatory

A.P. Julius  
Laboratory Manager

Test results indicated as not accredited are outside the scope of the laboratory's accreditation

No 434

**Specialist Quality Assurance Service in Aggregate, Concrete and Soils Testing**


"Central Testing Services operates as a trading trust through Central Testing Services Limited as the sole trustee."



**APPENDIX 5:**

Liquefaction Assessment Results

### CPT basic interpretation plots




#### Input parameters and analysis data

|                                |                   |                           |              |                             |            |
|--------------------------------|-------------------|---------------------------|--------------|-----------------------------|------------|
| Analysis method:               | B&I (2014)        | Depth to GWT (erthq.):    | 1.00 m       | Fill weight:                | N/A        |
| Fines correction method:       | B&I (2014)        | Average results interval: | 3            | Transition detect. applied: | No         |
| Points to test:                | Based on Ic value | Ic cut-off value:         | 2.60         | $K_v$ applied:              | Yes        |
| Earthquake magnitude $M_w$ :   | 6.10              | Unit weight calculation:  | Based on SBT | Clay like behavior applied: | Sands only |
| Peak ground acceleration:      | 0.18              | Use fill:                 | No           | Limit depth applied:        | No         |
| Depth to water table (insitu): | 1.00 m            | Fill height:              | N/A          | Limit depth:                | N/A        |

#### SBT legend

|                           |                             |                            |
|---------------------------|-----------------------------|----------------------------|
| 1. Sensitive fine grained | 4. Clayey silt to silty     | 7. Gravely sand to sand    |
| 2. Organic material       | 5. Silty sand to sandy silt | 8. Very stiff sand to      |
| 3. Clay to silty clay     | 6. Clean sand to silty sand | 9. Very stiff fine grained |

### Liquefaction analysis overall plots



**Input parameters and analysis data**

|                                |                   |                           |              |                             |            |
|--------------------------------|-------------------|---------------------------|--------------|-----------------------------|------------|
| Analysis method:               | B&I (2014)        | Depth to GWT (erthq.):    | 1.00 m       | Fill weight:                | N/A        |
| Fines correction method:       | B&I (2014)        | Average results interval: | 3            | Transition detect. applied: | No         |
| Points to test:                | Based on Ic value | Ic cut-off value:         | 2.60         | $K_f$ applied:              | Yes        |
| Earthquake magnitude $M_w$ :   | 6.10              | Unit weight calculation:  | Based on SBT | Clay like behavior applied: | Sands only |
| Peak ground acceleration:      | 0.18              | Use fill:                 | No           | Limit depth applied:        | No         |
| Depth to water table (insitu): | 1.00 m            | Fill height:              | N/A          | Limit depth:                | N/A        |

**F.S. color scheme**


- Almost certain it will liquefy
- Very likely to liquefy
- Liquefaction and no liq. are equally likely
- Unlike to liquefy
- Almost certain it will not liquefy

**LPI color scheme**

- Very high risk
- High risk
- Low risk



### CPT basic interpretation plots




#### Input parameters and analysis data

|                                |                   |                           |              |                             |            |
|--------------------------------|-------------------|---------------------------|--------------|-----------------------------|------------|
| Analysis method:               | B&I (2014)        | Depth to GWT (erthq.):    | 1.00 m       | Fill weight:                | N/A        |
| Fines correction method:       | B&I (2014)        | Average results interval: | 3            | Transition detect. applied: | No         |
| Points to test:                | Based on Ic value | Ic cut-off value:         | 2.60         | $K_0$ applied:              | Yes        |
| Earthquake magnitude $M_w$ :   | 6.10              | Unit weight calculation:  | Based on SBT | Clay like behavior applied: | Sands only |
| Peak ground acceleration:      | 0.18              | Use fill:                 | No           | Limit depth applied:        | No         |
| Depth to water table (insitu): | 1.00 m            | Fill height:              | N/A          | Limit depth:                | N/A        |

#### SBT legend

|                           |                             |                            |
|---------------------------|-----------------------------|----------------------------|
| 1. Sensitive fine grained | 4. Clayey silt to silty     | 7. Gravely sand to sand    |
| 2. Organic material       | 5. Silty sand to sandy silt | 8. Very stiff sand to      |
| 3. Clay to silty clay     | 6. Clean sand to silty sand | 9. Very stiff fine grained |

### Liquefaction analysis overall plots



**Input parameters and analysis data**

|                                |                   |                           |              |                             |            |
|--------------------------------|-------------------|---------------------------|--------------|-----------------------------|------------|
| Analysis method:               | B&I (2014)        | Depth to GWT (erthq.):    | 1.00 m       | Fill weight:                | N/A        |
| Fines correction method:       | B&I (2014)        | Average results interval: | 3            | Transition detect. applied: | No         |
| Points to test:                | Based on Ic value | Ic cut-off value:         | 2.60         | $K_{\sigma}$ applied:       | Yes        |
| Earthquake magnitude $M_w$ :   | 6.10              | Unit weight calculation:  | Based on SBT | Clay like behavior applied: | Sands only |
| Peak ground acceleration:      | 0.18              | Use fill:                 | No           | Limit depth applied:        | No         |
| Depth to water table (insitu): | 1.00 m            | Fill height:              | N/A          | Limit depth:                | N/A        |


**F.S. color scheme**

- Almost certain it will liquefy
- Very likely to liquefy
- Liquefaction and no liq. are equally likely
- Unlike to liquefy
- Almost certain it will not liquefy

**LPI color scheme**

- Very high risk
- High risk
- Low risk

### CPT basic interpretation plots



#### Input parameters and analysis data


|                                |                   |                           |              |                             |            |
|--------------------------------|-------------------|---------------------------|--------------|-----------------------------|------------|
| Analysis method:               | B&I (2014)        | Depth to GWT (erthq.):    | 1.00 m       | Fill weight:                | N/A        |
| Fines correction method:       | B&I (2014)        | Average results interval: | 3            | Transition detect. applied: | No         |
| Points to test:                | Based on Ic value | Ic cut-off value:         | 2.60         | $K_v$ applied:              | Yes        |
| Earthquake magnitude $M_w$ :   | 6.10              | Unit weight calculation:  | Based on SBT | Clay like behavior applied: | Sands only |
| Peak ground acceleration:      | 0.09              | Use fill:                 | No           | Limit depth applied:        | No         |
| Depth to water table (insitu): | 1.00 m            | Fill height:              | N/A          | Limit depth:                | N/A        |

#### SBT legend

|                           |                             |                            |
|---------------------------|-----------------------------|----------------------------|
| 1. Sensitive fine grained | 4. Clayey silt to silty     | 7. Gravely sand to sand    |
| 2. Organic material       | 5. Silty sand to sandy silt | 8. Very stiff sand to      |
| 3. Clay to silty clay     | 6. Clean sand to silty sand | 9. Very stiff fine grained |



### Liquefaction analysis overall plots



**Input parameters and analysis data**

|                                |                   |                           |              |                             |            |
|--------------------------------|-------------------|---------------------------|--------------|-----------------------------|------------|
| Analysis method:               | B&I (2014)        | Depth to GWT (erthq.):    | 1.00 m       | Fill weight:                | N/A        |
| Fines correction method:       | B&I (2014)        | Average results interval: | 3            | Transition detect. applied: | No         |
| Points to test:                | Based on Ic value | Ic cut-off value:         | 2.60         | $K_{\sigma}$ applied:       | Yes        |
| Earthquake magnitude $M_w$ :   | 6.10              | Unit weight calculation:  | Based on SBT | Clay like behavior applied: | Sands only |
| Peak ground acceleration:      | 0.09              | Use fill:                 | No           | Limit depth applied:        | No         |
| Depth to water table (insitu): | 1.00 m            | Fill height:              | N/A          | Limit depth:                | N/A        |


**F.S. color scheme**

- Almost certain it will liquefy
- Very likely to liquefy
- Liquefaction and no liq. are equally likely
- Unlike to liquefy
- Almost certain it will not liquefy

**LPI color scheme**

- Very high risk
- High risk
- Low risk

### CPT basic interpretation plots




#### Input parameters and analysis data

|                                       |                   |                           |              |                             |            |
|---------------------------------------|-------------------|---------------------------|--------------|-----------------------------|------------|
| Analysis method:                      | B&I (2014)        | Depth to GWT (erthq.):    | 1.00 m       | Fill weight:                | N/A        |
| Fines correction method:              | B&I (2014)        | Average results interval: | 3            | Transition detect. applied: | No         |
| Points to test:                       | Based on Ic value | Ic cut-off value:         | 2.60         | K <sub>0</sub> applied:     | Yes        |
| Earthquake magnitude M <sub>w</sub> : | 6.10              | Unit weight calculation:  | Based on SBT | Clay like behavior applied: | Sands only |
| Peak ground acceleration:             | 0.09              | Use fill:                 | No           | Limit depth applied:        | No         |
| Depth to water table (insitu):        | 1.00 m            | Fill height:              | N/A          | Limit depth:                | N/A        |

#### SBT legend

|                           |                             |                            |
|---------------------------|-----------------------------|----------------------------|
| 1. Sensitive fine grained | 4. Clayey silt to silty     | 7. Gravely sand to sand    |
| 2. Organic material       | 5. Silty sand to sandy silt | 8. Very stiff sand to      |
| 3. Clay to silty clay     | 6. Clean sand to silty sand | 9. Very stiff fine grained |

### Liquefaction analysis overall plots



#### Input parameters and analysis data

|                                |                   |                           |              |                             |            |
|--------------------------------|-------------------|---------------------------|--------------|-----------------------------|------------|
| Analysis method:               | B&I (2014)        | Depth to GWT (erthq.):    | 1.00 m       | Fill weight:                | N/A        |
| Fines correction method:       | B&I (2014)        | Average results interval: | 3            | Transition detect. applied: | No         |
| Points to test:                | Based on Ic value | Ic cut-off value:         | 2.60         | $K_D$ applied:              | Yes        |
| Earthquake magnitude $M_w$ :   | 6.10              | Unit weight calculation:  | Based on SBT | Clay like behavior applied: | Sands only |
| Peak ground acceleration:      | 0.09              | Use fill:                 | No           | Limit depth applied:        | No         |
| Depth to water table (insitu): | 1.00 m            | Fill height:              | N/A          | Limit depth:                | N/A        |

#### F.S. color scheme


- Almost certain it will liquefy
- Very likely to liquefy
- Liquefaction and no liq. are equally likely
- Unlike to liquefy
- Almost certain it will not liquefy

#### LPI color scheme

- Very high risk
- High risk
- Low risk



### CPT basic interpretation plots




#### Input parameters and analysis data

|                                |                   |                           |              |                             |            |
|--------------------------------|-------------------|---------------------------|--------------|-----------------------------|------------|
| Analysis method:               | B&I (2014)        | Depth to GWT (erthq.):    | 1.00 m       | Fill weight:                | N/A        |
| Fines correction method:       | B&I (2014)        | Average results interval: | 3            | Transition detect. applied: | No         |
| Points to test:                | Based on Ic value | Ic cut-off value:         | 2.60         | $K_v$ applied:              | Yes        |
| Earthquake magnitude $M_w$ :   | 6.10              | Unit weight calculation:  | Based on SBT | Clay like behavior applied: | Sands only |
| Peak ground acceleration:      | 0.26              | Use fill:                 | No           | Limit depth applied:        | No         |
| Depth to water table (insitu): | 1.00 m            | Fill height:              | N/A          | Limit depth:                | N/A        |

#### SBT legend

|                           |                             |                            |
|---------------------------|-----------------------------|----------------------------|
| 1. Sensitive fine grained | 4. Clayey silt to silty     | 7. Gravely sand to sand    |
| 2. Organic material       | 5. Silty sand to sandy silt | 8. Very stiff sand to      |
| 3. Clay to silty clay     | 6. Clean sand to silty sand | 9. Very stiff fine grained |

### Liquefaction analysis overall plots



**Input parameters and analysis data**

|                                |                   |                           |              |                             |            |
|--------------------------------|-------------------|---------------------------|--------------|-----------------------------|------------|
| Analysis method:               | B&I (2014)        | Depth to GWT (erthq.):    | 1.00 m       | Fill weight:                | N/A        |
| Fines correction method:       | B&I (2014)        | Average results interval: | 3            | Transition detect. applied: | No         |
| Points to test:                | Based on Ic value | Ic cut-off value:         | 2.60         | $K_{\sigma}$ applied:       | Yes        |
| Earthquake magnitude $M_w$ :   | 6.10              | Unit weight calculation:  | Based on SBT | Clay like behavior applied: | Sands only |
| Peak ground acceleration:      | 0.26              | Use fill:                 | No           | Limit depth applied:        | No         |
| Depth to water table (insitu): | 1.00 m            | Fill height:              | N/A          | Limit depth:                | N/A        |


**F.S. color scheme**

- Almost certain it will liquefy
- Very likely to liquefy
- Liquefaction and no liq. are equally likely
- Unlike to liquefy
- Almost certain it will not liquefy

**LPI color scheme**

- Very high risk
- High risk
- Low risk

### CPT basic interpretation plots



#### Input parameters and analysis data


|                                |                   |                           |              |                             |            |
|--------------------------------|-------------------|---------------------------|--------------|-----------------------------|------------|
| Analysis method:               | B&I (2014)        | Depth to GWT (erthq.):    | 1.00 m       | Fill weight:                | N/A        |
| Fines correction method:       | B&I (2014)        | Average results interval: | 3            | Transition detect. applied: | No         |
| Points to test:                | Based on Ic value | Ic cut-off value:         | 2.60         | $K_f$ applied:              | Yes        |
| Earthquake magnitude $M_w$ :   | 6.10              | Unit weight calculation:  | Based on SBT | Clay like behavior applied: | Sands only |
| Peak ground acceleration:      | 0.26              | Use fill:                 | No           | Limit depth applied:        | No         |
| Depth to water table (insitu): | 1.00 m            | Fill height:              | N/A          | Limit depth:                | N/A        |

#### SBT legend

|                           |                             |                            |
|---------------------------|-----------------------------|----------------------------|
| 1. Sensitive fine grained | 4. Clayey silt to silty     | 7. Gravely sand to sand    |
| 2. Organic material       | 5. Silty sand to sandy silt | 8. Very stiff sand to      |
| 3. Clay to silty clay     | 6. Clean sand to silty sand | 9. Very stiff fine grained |



### Liquefaction analysis overall plots



#### Input parameters and analysis data

|                                |                   |                           |              |                             |            |
|--------------------------------|-------------------|---------------------------|--------------|-----------------------------|------------|
| Analysis method:               | B&I (2014)        | Depth to GWT (erthq.):    | 1.00 m       | Fill weight:                | N/A        |
| Fines correction method:       | B&I (2014)        | Average results interval: | 3            | Transition detect. applied: | No         |
| Points to test:                | Based on Ic value | Ic cut-off value:         | 2.60         | $K_v$ applied:              | Yes        |
| Earthquake magnitude $M_w$ :   | 6.10              | Unit weight calculation:  | Based on SBT | Clay like behavior applied: | Sands only |
| Peak ground acceleration:      | 0.26              | Use fill:                 | No           | Limit depth applied:        | No         |
| Depth to water table (insitu): | 1.00 m            | Fill height:              | N/A          | Limit depth:                | N/A        |

#### F.S. color scheme

- Almost certain it will liquefy
- Very likely to liquefy
- Liquefaction and no liq. are equally likely
- Unlike to liquefy
- Almost certain it will not liquefy

#### LPI color scheme

- Very high risk
- High risk
- Low risk

# Structural Upgrade Works

Architectural Report



## Southland Museum & Art Gallery

**Prepared For**

Invercargill City Council

**Document Revision Status**

Revision A : 13.11.2020

**Document Control**

Prepared by:  
Jonathan Goss  
Warren and Mahoney Architects

Approved by:  
Ian Adamson  
Warren and Mahoney Architects

On behalf of Warren and Mahoney  
Architects Limited

**Contact**

Warren and Mahoney Architects Ltd  
Level 1, 1-7 Earl Street, PO Box 1102  
Queenstown 9348, New Zealand  
Phone +64 3 450 2290



# Contents

|   |    |
|---|----|
| INTRODUCTION  | 4  |
| OPTION 1/2: BUILDING COMPLIANT: 34/67% NBS & MIN REFURBISHMENT  | 5  |
| APPENDIX 1. OUTLINE SCOPE OF WORKS - STRUCTURAL WALL INSERTIONS | 15 |
| APPENDIX 2. ACCESSIBILITY ASSESSMENT REPORT                     | 20 |
| APPENDIX 3. WC CALCULATIONS                                     | 25 |



# Introduction

## THE BUILDING:

The Southland Museum and Art Gallery, located at 108 Gala Street, Invercargill, consists of three independent structures and the remains of a fourth. These are the original building, which was constructed in 1940; the addition constructed in 1960 to the north-west of the original building, and another addition built in 1988 to the east of the 1960 building. This final addition included the construction of a pyramid that enclosed all of the buildings.

## PURPOSE:

The purpose of this report is an initial assessment of the scope of architectural & interior refurbishment that would be required for NBS 34% and 67% structural seismic upgrade of the Southland Museum & Art Gallery (SMAG) building and the upgrades required to meet, as far as is reasonable practicable, the requirements for accessibility and facilities under NZ Building Code and compliance with the Fire Engineers report. This report forms part of building options report prepared by The Building Information Group and should be read in conjunction with the Structural, Fire, Mechanical, Electrical and geotechnical reports provided.

This report is based on an initial site walk through-out the building carried out on Monday 10th August 2020 along with review of the Matterport 3D scan of the existing building provided by Invercargill City Council. The scope of this report is limited to the facilities viewed and observations made. A further detailed full building delapidation survey would be required to confirm whether the building meets all the requirements of the Building Code.

## BUILDING CODE COMPLIANCE:

This report has been prepared based on the requirements of clause D1/AS1, part F4/AS1, G1/AS1, and NZS 4121:2001 - this latter document being the reference standard in section 119 of the Building Act 2004 as the means of determining compliance for access and facilities for persons with disabilities.

It is intended that any new work will comply with NZS 4121 with respect to accessible routes, corridors, doorways, doors, and toilet facilities. For the existing building, facilities compliance has been assessed with regard to requirements and being reasonably practicable.

## ASSUMPTIONS:

- Minimum Works only - Scope only includes areas that have been directly affected by the required Structural & Fire compliance upgrade works. This is not a refurbishment of spaces, rather a reinstatement.
- Those areas that have been identified as Non-compliant with respect to accessibility, but are not directly affected by the required Structural & Fire upgrade works have been assumed to comply on an 'As near as reasonably practical' (ANARP) basis - ie. Existing Accessible WC's.
- Maximum design occupancy has been assumed as 825p in accordance with the Fire Engineers Design Advice. These occupancies need to be checked and confirmed by the Museum management to be appropriate. Note: these occupancies are significantly more than what is currently stated on the BWO (500). Current WC provision needs further analysis.
- 34% vs 67% NBS - Works associated with increased structural compliance do not materially affect the architectural scope as the change between 34-67% structurally involves more steel reinforcing in walls, footing & beams in the same locations and extent as per the 34% scheme.
- Architectural scope assumes that current museum layout is to remain and that museum displays and BOH layouts are not changed.
- Due to the structural works and fire compliance the pyramid roof and secondary structure assumed to be replaced.
- Vertical circulation (Lift) - while non-compliant, is assumed to remain on ANARP approach.

# Southland Museum & Art Gallery

## Architectural Report

### Option 1/2:

- Building Compliant to 34% / 67%  
NBS
- Minimum Refurbishment






# Option 1/2: 34/67% NBS

(Minimum Refurbishment)

**LEGEND**

- Existing Retained (Black Lines)
- Wall to be removed
- Scope of works Area
- New Structural wall
- New Fire Rated walls & doors
- Floor Finishes to be repaired/replaced - Note: All floor finishes to meet a minimum critical radinat heat flux of 1.2 kW/m2 in accordance with Fire Engineers advice.
- Ceiling Finishes upgraded to meet code - Note: All ceiling finishes to be Group 2 surface finish in accordance with Fire Engineers advice.




**GF - Floor plan**

# Option 1/2: 34/67% NBS

(Minimum Refurbishment)

**LEGEND**

- Existing Retained (Black Lines)
- Wall to be removed
- Scope of works Area
- New Structural wall
- New Fire Rated walls & doors
- Floor Finishes to be repaired/replaced - Note: All floor finishes to meet a minimum critical radinat heat flux of 1.2 kW/m2 in accordance with Fire Engineers advice.
- Ceiling Finishes upgraded to meet code - Note: All ceiling finishes to be Group 2 surface finish in accordance with Fire Engineers advice.
- New Structural beam












**GF - Ceiling plan**

# Option 1/2: 34/67% NBS

(Minimum Refurbishment)

## LEGEND

|  |   |
|--|---|
|  | Existing Retained (Black Lines)   |
|  | Wall to be removed  |
|  | Scope of works Area   |
|  | New Structural wall   |
|  | New Fire Rated walls & doors  |
|  | Floor Finishes to be repaired/replaced - Note: All floor finishes to meet a minimum critical radiant heat flux of 1.2 kW/m2 in accordance with Fire Engineers advice. |
|  | Ceiling Finishes upgraded to meet code - Note: All ceiling finishes to be Group 2 surface finish in accordance with Fire Engineers advice.                            |



**Level 1 - Floor plan**













# Option 1/2:

## 34/67% NBS

(Minimum Refurbishment)

### LEGEND

|  |   |
|--|---|
|  | Existing Retained (Black Lines)   |
|  | Wall to be removed  |
|  | Scope of works Area   |
|  | New Structural wall   |
|  | New Fire Rated walls & doors  |
|  | Floor Finishes to be repaired/replaced - Note: All floor finishes to meet a minimum critical radiant heat flux of 1.2 kW/m2 in accordance with Fire Engineers advice. |
|  | Ceiling Finishes upgraded to meet code - Note: All ceiling finishes to be Group 2 surface finish in accordance with Fire Engineers advice.                            |
|  | New Structural beam   |












Level 1 - Ceiling plan

# Option 1/2: 34/67% NBS

(Minimum Refurbishment)

**LEGEND**

-  Existing Retained (Black Lines)
-  Wall to be removed
-  Scope of works Area
-  New Structural wall
-  New Fire Rated walls & doors
-  Floor Finishes to be repaired/replaced - Note: All floor finishes to meet a minimum critical radinat heat flux of 1.2 kW/m2 in accordance with Fire Engineers advice.
-  Ceiling Finishes upgraded to meet code - Note: All ceiling finishes to be Group 2 surface finish in accordance with Fire Engineers advice.
-  New Structural beam











Second Floor


# Option 1/2:

## 34/67% NBS


(Minimum Refurbishment)

### LEGEND

|  |   |
|--|---|
|  | Existing Retained (Black Lines)   |
|  | Wall to be removed  |
|  | Scope of works Area   |
|  | New Structural wall   |
|  | New Fire Rated walls & doors  |
|  | Floor Finishes to be repaired/replaced - Note: All floor finishes to meet a minimum critical radiant heat flux of 1.2 kW/m2 in accordance with Fire Engineers advice. |
|  | Ceiling Finishes upgraded to meet code - Note: All ceiling finishes to be Group 2 surface finish in accordance with Fire Engineers advice.                            |
|  | New Structural beam   |



SECTION A-A











SECTION B-B




# Option 1/2: 1940's Building


## 34/67% NBS

(Minimum Refurbishment)

| LEGEND   |   |
|--|---|
|  | Existing Retained (Black Lines)   |
|  | Wall to be removed  |
|  | Scope of works Area   |
|  | New Structural wall   |
|  | New Fire Rated walls & doors  |
|  | Floor Finishes to be repaired/replaced - Note: All floor finishes to meet a minimum critical radiant heat flux of 1.2 kW/m2 in accordance with Fire Engineers advice. |
|  | Ceiling Finishes upgraded to meet code - Note: All ceiling finishes to be Group 2 surface finish in accordance with Fire Engineers advice.                            |
|  | Replace existing timber framed floor where removed to provide access for new foundation beams - allow to replace carpet tile floor finish.                            |



GF - Floor plan












GF - Ceiling plan

# Option 1/2: 1940's Building


## 34/67% NBS

(Minimum Refurbishment)

| LEGEND   |  |
|--|--|
|  | Existing Retained (Black Lines)  |
|  | Wall to be removed   |
|  | Scope of works Area  |
|  | New Structural wall  |
|  | New Fire Rated walls & doors   |
|  | Floor Finishes to be replaced - Note: All floor finishes to meet a minimum critical radinat heat flux of 1.2 kW/m2 in accordance with Fire Engineers advice. |
|  | Ceiling Finishes replaced to meet code - Note: All ceiling finishes to be Group 2 surface finish in accordance with Fire Engineers advice.                   |
|  | Replace existing timber framed floor where removed to provide access for new foundation beams - allow to replace carpet tile floor finish.                   |



**Level 1 - Floor plan**



**Level 1 - Ceiling plan**

# Option 1/2: 34/67% NBS

(Minimum Refurbishment)

## SCOPE OF WORKS

### 1a New Structural wall & Foundation beam

New in-situ reinforced concrete wall and foundation beam - Refer to structural engineers details and specification - Existing floor to be removed to allow for new concrete foundation and floor to be reinstated.

### 1b New Structural wall

New in-situ reinforced concrete wall. Refer to structural engineers details and specification.

### 2 New Stair

Replace/upgrade existing stair w/ new Accessible compliant stair (Rise: Min150mm/ Max 180mm x 310mm min tread, Handrail @ 900-1000mm) and 16mm Fyreline to U/S of stair and support in accordance with Fire Engineers advice.

### 3 Southern Mezzanine Floor

Reline the underside of the floor with 16mm Fyreline. Ensure any structural steel support beams are concealed above this fyreline layer. The existing RHS posts supporting the steel beams shall be lined all around with 16mm fyreline on timber blocking.

### 4 Remove Wall - Structurally Weak

Demolish existing full height wall. Patch existing floor covering where wall removed or flooring damaged during demolition. Make good and paint soffit and columns.

### 5 Fire rated walls and doors

Upgrade existing wall linings, doors to form new fire separation / enclosure in accordance with Fire Engineers advice.

### 6 Replace/upgrade existing ceiling

Replace existing ceilings were removed to facilitate structural works. All new ceiling finishes to meet Group 2 surface finish in accordance with Fire Engineers advice and NZBC.

### 7 Replace floor finishes

Remove and salvage existing carpet tiles for reinstatement or replace with new to match where removed to enable structural or fire upgrades.

### 8 Accessible Lift

Existing non-compliant lift to remain - ANARP applied for consenting purposes.

### 9 New 850min egress door/opening

Create new egress route door opening to provide access around new structural wall to existing means of escape stair.

### 10 Replace existing roofing system

Removal of existing roof required to allow for structural connections to be strengthened. Replace existing Bondor panels with Kingspan Architectural wall panels on new steel purlins.

### 11 Upgrade Accessible Stairs

Upgrade existing stair as near as reasonably practical (ANARP) to Building Code compliant stair (Rise: Min150mm/ Max 180mm x 310mm min tread, Handrail @ 900-1000mm).

### 12 Accessible WC upgrade

Upgrade existing Accessible WC's as near as reasonably practical (ANARP) to meet Building code requirements.

### 13 Existing walls & partitions

Reinstate / replace existing wall where partially demolished to allow for structural upgrade.

### 14 Remove existing brick veneer

All existing brick veneer cladding to 1940's building to be removed - make good / strap & line existing walls.

### 15 Structural ceiling diaphragm

New structural plywood ceiling diaphragm to underside of the existing roof. Refer to structural engineers details and specification.

### 16 New Concrete Beams

New in-situ reinforced concrete beams cast between ribs of existing TT floor units - Refer to structural engineers details & specification.

## NOTES:

Architectural report to be read in conjunction with Structural, Fire, Building Services and Geotechnical reports.



# Southland Museum & Art Gallery





Architectural Report

**Appendix 1.**





**Outline Scope of works**

- Strutural wall insertions





| Location   | Scope of work  | Description  | Notes  |
|--|--|--|--|
| GF- Structure / Fire / Accessibility<br><br>GRID 3 / C-E | RECEPTION STAIR<br>                                      | New structural wall & foundation beam required.<br><br><b>Demolition:</b><br>- Remove existing stair.<br>- Cut out existing floor for new structural footing.<br><br><b>New Works:</b><br>- Form new structural flooring and wall to Structural engineers specification.<br>- Form new accessible compliant stair and balustrade with Fire rated lining to underside to fire engineers specification.<br>- reinstate floor coverings to new section of floor and new stair.<br>- Strap & line structural wall and paint. | Head room issue to be resolved at later design stage.  |
| GF - Structure<br><br>GRID 5 / B-D                       | GALLERY 2 WALL REMOVAL<br>                              | Remove existing wall due to structural weakness & safety hazard.<br><br><b>Demolition:</b><br>- Demolish existing full height wall on Grid 5 between grids B-D.<br><br><b>New Works:</b><br>- Patch existing floor covering where wall removed or flooring damaged during demolition<br>- Make good and paint soffit and columns.  |  |
| GF - Structure<br><br>GRID 7 / B-D                       | EX CHILDREN GALLERY      GALLERY 2<br>                 | Remove existing wall due to structural weakness & safety hazard.<br><br><b>Demolition:</b><br>- Demolish existing full height wall on Grid 7 between grids B-D.<br><br><b>New Works:</b><br>- Replace wall with new full height PB lined timber partition w/ new double door to storage area.<br>Patch existing floor covering where wall removed or flooring damaged during demolition<br>- Make good and paint soffit and columns.<br>- Paint new wall both sides  |  |
|  | Store room - structural wall removal & replacement<br> |  | Review services connections - electrical, HVAC & Plumbing interface with existing wall removal. Make good where necessary. |



| Location   | Scope of work  | Description   | Notes  |
|--|--|---|--|
| GF- Structure<br>GRID 8 / C-E<br>NEW STRUCTURAL WALL AND FOOTING | RECEPTION STAIR<br>        | New structural wall & foundation beam required.<br><br><b>Demolition:</b><br>- Cut out existing floor for new structural footing.<br>- Cut back existing partition<br><br><b>New Works:</b><br>- Form new structural flooring and wall to Structural engineers specification.<br>- Reinstate floor coverings to new section of floor<br>- Strap & line structural wall and paint.<br>- Re-instate       | Retention of existing partition to be reviewed |
| GF - Structure<br>GRID B / 5-7                                   | GALLERY 2<br>             | New structural wall & foundation beam required.<br><br><b>Demolition:</b><br>- Cut out existing floor for new structural footing.<br>- Cut back existing wall/ partition<br><br><b>New Works:</b><br>- Form new structural flooring and wall to Structural engineers specification.<br>- Reinstate floor coverings to new section of floor<br>- Strap & line structural wall and paint.<br>- Re-instate |  |
|  | TUATARIUM<br>            |   |  |
| GF - Structure<br>GRID E / 7-8                                   | EX. CHILDREN GALLERY<br> | New structural wall & foundation beam required.<br><br><b>Demolition:</b><br>- Cut out existing floor for new structural footing.<br>- Cut back existing wall/ partition<br><br><b>New Works:</b><br>- Form new structural flooring and wall to Structural engineers specification.<br>- Reinstate floor coverings to new section of floor<br>- Strap & line structural wall and paint.<br>- Re-instate |  |



| Location  | Scope of work  | Description   | Notes |
|---|--|---|-------|
| <p>GF - Structure</p> <p>GRID F / 3-5</p> <p>NEW STRUCTURAL WALL AND FOOTING</p>              | <p>OFFICE CORRIDOR</p>                 | <p>New structural wall &amp; foundation beam required.</p> <p><b>Demolition:</b></p> <ul style="list-style-type: none"> <li>- Cut out existing floor for new structural footing.</li> <li>- Remove existing stair to mezzanine to allow access.</li> <li>- Remove existing brick cladding.</li> <li>- Removal of existing ceiling to allow for connection of new structural wall to beam above CL.</li> </ul> <p><b>New Works:</b></p> <ul style="list-style-type: none"> <li>- Form new structural flooring and wall to Structural engineers specification.</li> <li>- Reinstate floor coverings to new section of floor</li> <li>- Strap &amp; line structural wall and paint.</li> <li>- New Fire rated lining to u/s of mezzanine floor.</li> <li>- New painted PB suspended ceiling.</li> <li>- Replace lighting.</li> </ul> |       |
|   | <p>MEZZ STAIR</p>                     |   |       |
| <p>LEVEL 1 - Structure</p> <p>GRID 3 / C-D</p> <p>NEW STRUCTURAL WALL AND FOOTING</p>         | <p>STAIR CORE / WHALING GALLERY</p>  | <p>New structural wall &amp; foundation beam required.</p> <p><b>Demolition:</b></p> <ul style="list-style-type: none"> <li>- Remove ceiling to provide access to beam over.</li> <li>- Cut back existing wall/ partition around stair.</li> <li>-</li> </ul> <p><b>New Works:</b></p> <ul style="list-style-type: none"> <li>- Form new structural wall to Structural engineers specification.</li> <li>- Reinstate floor coverings /replace where damaged or removed.</li> <li>- Strap &amp; line structural wall and paint.</li> <li>- Repair/ reinstate stair and handrail</li> <li>REplace/ repair ceiling grid localised to works.</li> </ul>   |       |
| <p>SOUTHLAND MUSEUM &amp; ART GALLERY / Structural Upgrade / Architectural Report / Rev A</p> | <p>STAIR CORE / WHALING GALLERY</p>  |   |       |

| Location   | Scope of work   | Description   | Notes |
|--|---|---|-------|
| LEVEL 1 - Structure<br>GRID F / 3-5<br>NEW STRUCTURAL WALL | OFFICE CORRIDOR<br> | OFFICE CORRIDOR<br>New structural wall & foundation beam required.<br><br><b>Demolition:</b> <ul style="list-style-type: none"> <li>- Cut out existing floor for new structural footing.</li> <li>- Remove existing stair to mezzanine to allow access.</li> <li>- Remove existing brick cladding.</li> <li>- Removal of existing ceiling to allow for connection of new structural wall to beam above CL.</li> </ul> <b>New Works:</b> <ul style="list-style-type: none"> <li>- Form new structural footing and wall to Structural engineers specification.</li> <li>- Reinstate floor coverings to new section of floor</li> <li>- Strap &amp; line structural wall and paint.</li> <li>- New Fire rated lining to u/s of mezzanine floor.</li> <li>- New painted PB suspended ceiling.</li> <li>- Replace lighting.</li> </ul> |       |
| LEVEL 1 - Structure<br>GRID F / 3-5<br>NEW STRUCTURAL WALL | ARCHIVE<br>        |   |       |
|  |   |   |       |
|  |   |   |       |

# Southland Museum & Art Gallery

Architectural Report

Appendix 2.  
Accessibility Report





# Appendix 2.

- Move freely inside and to use the facilities within the building or facility, except as provided for in this part of the standard
- Operate electronic access mechanisms and systems.

These criteria are generally met throughout by the existing building, with critical exceptions with regards to the provision of accessible stairs and ramps on MOE routes, as noted in the following table.

## REPORT

|                     |  |
|---------------------|--|
| <b>Project</b>      | 9344 Southland Museum and Art Gallery                      |
| <b>Subject</b>      | Accessibility GAP analysis – Initial findings              |
| <b>Date / time</b>  | 17 August 2020   |
| <b>Prepared</b>     | on behalf of Warren and Mahoney Architects New Zealand Ltd |
| <b>Distribution</b> | Tess Browne – TBIG<br>Nick Hamlin – Maxxis Projects        |

### 1. PURPOSE:

The purpose of this report is an initial assessment of the work that would be required for the various levels of development of the Southland Museum & Art Gallery (SMAG) building and to establish if it generally meets, as far as is reasonable practicable, the requirements for access and facilities for the disabled. This report forms part of building options report prepared by The Building Information Group.

This report is based on an initial site walk through-out the building carried out on Monday 10<sup>th</sup> August and the scope of the report is limited to the facilities viewed and observations made. A further full detailed building survey would be required to confirm whether the building meets all the requirements of the Building Code with respect to accessibility.

### 2. THE BUILDING:

The Southland Museum and Art Gallery, located on Gala Street at Invercargill, consists of three independent structures and the remains of a fourth. These are the original building, which was constructed in 1940; the addition constructed in 1960 to the northwest of the original building, and another addition built in 1988 to the east of the 1960 building. This final addition included the construction of a pyramid that enclosed all of the buildings.

### 3. BUILDING CODE COMPLIANCE:

This report has been prepared based on the requirements of clause D1/AS1, part F4/AS1, G1/AS1, and NZS 4121:2001 - this latter document being the reference standard in section 119 of the Building Act 2004 as the means of determining compliance for access and facilities for persons with disabilities.

It is intended that any new work will comply with NZS 4121 with respect to accessible routes, corridors, doorways, doors, and toilet facilities. For the existing building, facilities compliance has been assessed with regard to requirements and being reasonably practicable as set out in the tables below.

### 4. CODE REQUIREMENTS - EXISTING CONDITIONS:

#### 4.1 ACCESSIBLE ROUTES - GENERALLY:

It is required that people with disabilities shall be able to:

- Park in accessible car parks
- Approach the accessible main entrance (or entrances) by footpath on an accessible route
- Enter the building or facility at an entrance, which has a level threshold, or which is approached via an incline or ramp of appropriate gradient

### 5. ACCESSIBILITY GAP ANALYSIS:

| REQUIRED FEATURE   | CURRENT SITUATION<br>(Existing Building)                         | Upgrade Action<br>proposed under<br>Sections 112 or 115 of<br>the Building Act.<br>(Existing Buildings Only) |
|--|--|--|
| <b>CAR PARKS (NZBC D1.3.5 &amp; D1.3.6, D1/AS1/10, NZS 4121 SECTIONS 5 &amp; F3)</b>   |  |  |
| Provide at the ratio of 1 for up to 20, 2 for up to 50, plus 1 more for every additional 50 parks (or part thereof) (NZS 4121). Although this differs from our Proposed City Plan, our Planners will accept this Standard. | Complies   |  |
| Identified by the symbol of access (on ground or post).  | Complies   |  |
| Location of accessible car park is either visible from a vehicle at the entrance to the car park area, or is sign posted from the entrance to the parking area.  | Complies   |  |
| Min. 3500mm width (NZS 4121). Min. 3200mm width (AS2890.1 Fig. 2.2) but 3500mm if beside an obstruction (D1/AS1/10.1.1 Comment)  | Appears to comply  |  |
| Located on an accessible route, as close as possible to the building accessible entry.   | Complies – located directly adjacent to the accessible entrance. |  |
| Located on a surface with a max. 1:50 slope.   | Complies   |  |
| Located to avoid conflict between vehicles and people, and provided with direct access to an accessible route without having to pass behind parked cars.   | Complies   |  |
| <b>RAMPS AND FOOTPATHS (NZBC D1, D1/AS1/2.3, 3.0 &amp; 6.0, NZS 4121 SECTION 6)</b>  | N/A (Outside of scope of review – Building only reviewed)        |  |
| <b>STEP RAMPS (NZS 4121 SECTION 6)</b>   |  |  |
| Ramps have a max. Gradient of 1:12(preferably 1:14)  | Non-Compliant  |  |
| Ramps have landings top and bottom, extending 1200mm beyond any doorway or door swing. Landings may have a maximum gradient, in the direction of travel, of 1:50   | Non-compliant  |  |
| All ramps have any upstand or low rail to prevent wheel-chair wheel from running off the edge.   | N/A  |  |
| Ramps steeper than 1:20 have handrails both sides, continuing for 300mm beyond head and foot of ramp, plus an intermediate safety rail where not against a wall or barrier (NZS 4121 Fig. 12)                              | Non-Compliant  |  |
| Height of handrails is between 840mm and 1000mm vertically above “plane” surface of ramp   | Non-compliant  |  |

# Appendix 2.

WARREN AND MAHONEY®

RPT0001\_SMAG\_ACCE  
SSIBILITY GAP  
ANALYSIS\_AUGUST  
2020

|   |  |  |
|---|--|--|
| Handrail diameter is between 32mm and 50mm (or to Fig. 26(b) D1/AS1)  | TBC  |  |
| Handrails have projecting ends (NZS 4121 Fig. 13)   | Non-compliant  |  |
| Ramp landings (and rest areas) allow 1200mm space clear of door swings  | Non-compliant  |  |
| Max. rise between landings is 750mm   | Complies   |  |
| <b>MAIN ENTRANCE AND ALL ACCESSIBLE ROUTES, INCLUDING CORRIDORS, DOORWAYS AND DOORS (NZBC D1.3.4(f), D1 AS1/7.0, FIG 27, NZS 4121 SECTION 7)</b>                              |  |  |
| The main entrance is on the accessible route.   | Complies   |  |
| If the main entrance is not accessible, it has signage indicating location of accessible entrance.  | Complies   |  |
| Preferably there are no thresholds in doorway. If they cannot be avoided, they are max. 20mm high, or 56mm high is a 1:8 max. ramp is provided both sides (NZS 4121 Fig. 17). | Complies   |  |
| There are accessible routes extending from the accessible entry to all spaces that are required to be accessible, 1200mm min. width.  | Non-compliant – lift lobby entrance L1                               |  |
| If existing corridors are less than 1200mm wide, doorways off it are made wider to compensate.  | N/A  |  |
| Doorways have 760mm min. clear opening (unless from narrow corridors where wider clear openings are required).  | Appears to comply – not all doors checked as part of initial review. |  |
| Double doors have at least one leaf which provides 760mm min. clear opening.  | Appears to comply – not all doors checked as part of initial review. |  |
| Doors are colour-contrasted with their surroundings.  | Complies   |  |
| Doors are dual swing and have visibility glazing panels.  | N/A  |  |
| Doors with full height glazing have manifestation markings 7001000mm above floor.   | N/A  |  |
| Clear space between successive doors is 1200mm min. (Fig. 27 D1/AS1).   | Non-compliant – Male WC lobby  |  |
| Where doors open towards wheelchair, an unobstructed wall space not less than 300mm wide is required at side of door adjacent to door handle.                                 | Appears to comply – not all doors checked as part of initial review. |  |
| Forces required to open non-fire doors are within limits.   | Not tested   |  |
| <b>PUBLIC FACILITIES (NZBC G5.3.4, NZS 4121 SECTION 11)</b>   |  |  |
| Where public counters or desks are provided in reception areas, bars, shops & supermarkets, at least one is accessible for both the public and for the staff using it.        | Non-Compliant  |  |

WARREN AND MAHONEY®

RPT0001\_SMAG\_ACCE  
SSIBILITY GAP  
ANALYSIS\_AUGUST  
2020

|  |                     |  |
|--|---------------------|--|
| Accessible portion of counter has top of work surface 775mm max. above floor, with 675mm min. height clearance under for a depth of 540mm.   | Non-Compliant       |  |
| Public telephones comply with NZS 4121 Section 11.2.   | N/A                 |  |
| <b>LIFTS (NZBC D1.3.4 (c), D2.3.5, D2/AS1/71, NZS 4121 SECTION 9)</b>  |                     |  |
| Lifts are required as follows:   |                     |  |
| <input type="checkbox"/> in all buildings with four or more floors   | N/A                 |  |
| <input type="checkbox"/> in a three floor building when the total gross floor area of the two upper floors is 500m <sup>2</sup> or more and the design occupancy exceeds 50 persons  | N/A                 |  |
| <input type="checkbox"/> in a two floor building when the gross floor area of the upper floor is 400m <sup>2</sup> or more and the design occupancy exceeds 40 persons   | Complies            |  |
| <input type="checkbox"/> notwithstanding any of the above, a lift is required if an upper floor is used for: a place of assembly for 250 or more persons, public reception area for a bank, central and local government offices and facilities (including libraries), medical and dental rooms, health care centres | N/A                 |  |
| At least one lift is on the accessible route.  | Complies            |  |
| Lobbies have 1800mm min. unobstructed depth in front of lift doors.  | Complies            |  |
| Car floor has 1400mm x 1400mm min. internal dimensions.  | Complies (TBC)      |  |
| Doors have 900mm min. clear opening.   | Complies            |  |
| Doors are readily distinguishable from their surroundings.   | Complies            |  |
| Doors remain open for at least 5 seconds before starting to close.   | Not tested          |  |
| Car has handrails on walls to NZBC D1/6.0 or NZS 4121 Fig 26.  | Non-compliant (TBC) |  |
| All controls are located between 900mm and 1350mm above the floor.   | Appears to comply   |  |
| All controls have tactile features.  | Not reviewed        |  |
| Lift indicators are provided as NZS 4121:2001 cl. 9.2.5.   | Not reviewed        |  |
| <b>STAIRS (NZBC D1.3.4 (g)(h)(i), D1/AS1/4.0, 4.2, 4.4, 4.5, NZS 4121 SECTION 8)</b>   |                     |  |
| All multi-storeyed buildings that are required to be accessible have at least one accessible stair.  | Non-compliant       |  |
| Stair treads 310mm min.; Risers 180mm max. (of uniform height over each flight).   | Non-compliant       |  |
| Stair has 900mm min. width between handrails.  | Complies            |  |
| Landings have 900mm min. depth (1200mm recommended)  | Appears to comply   |  |
| Max. total rise of 2500mm between landings.  | Not reviewed        |  |

# Appendix 2.

|  |                                     |  |
|--|-------------------------------------|--|
| No open risers, no winders, no spiral stairs.  | Complies                            |  |
| Nosing's are rounded and colour contrasted with rest of tread.   | Complies                            |  |
| Colour-contrasted change of floor surface texture are provided at head and foot of stair.                            | Non-compliant                       |  |
| <b>STAIR HANDRAILS (NZBC D1.3.4 (i), D1/AS1/6.1, NZS 4121 SECTION 8.6)</b>   |                                     |  |
| Are provided on both sides of the stair.   | Complies                            |  |
| Have no obstruction to the passage of the hand along the rail.   | Complies (TBC)                      |  |
| Are continuous around landings (except at doorways).   | Non-compliant                       |  |
| Extend 610mm min. beyond the foot of the stair and 300mm min. beyond the head of the stair.                          | Non-compliant                       |  |
| At the same slope as the pitch line.   | Complies                            |  |
| Between 900mm and 1000mm above pitch line.   | Non-compliant                       |  |
| Profiles are to D1/AS1 Fig. 26(b)  | Complies (TBC)                      |  |
| Have no projecting ends, and have domed buttons 150mm from the ends (NZS 4121 Fig. 23).                              | Non-compliant                       |  |
| <b>TOILET FACILITIES (NZBC D1.3.2(c) &amp; G1.1 &amp; 1.3.4 G1/AS1, NZS 4121 SECTION 10)</b>                         |                                     |  |
| Accessible toilets are on the accessible route.  | Complies                            |  |
| Route to accessible toilets does not traverse different tenancies.   | Complies                            |  |
| Minimum dimensions of space are 1900mm x 1600mm and the layout of fittings is correct.                               | Non-compliant                       |  |
| In certain large buildings having more than 300 occupants, accessible toilets are evenly distributed.                | N/A                                 |  |
| If doors are hinged, they swing outwards unless the space is sufficiently large (sliding doors are also acceptable). | Complies                            |  |
| Door has 760mm min. clear opening (with 1200mm clear space in any lobby between door swing arcs).                    | Non-compliant                       |  |
| If hinged, the door has a grab rail on inner face.   | Non-compliant                       |  |
| Indicator bolt is of sufficient size so as to be usable by person with limited hand movement.                        | Non-compliant                       |  |
| Horizontal leg of grab rail beside WC pan is fixed 700mm above floor.  | Appears compliant (to be confirmed) |  |
| Vertical leg of grab rail is fixed between 150mm and 250mm from front of WC pan.                                     | Appears compliant (to be confirmed) |  |
| Top of WC pan seat is 460mm above floor level.   | Non-compliant                       |  |
| Front edge of WC pan is 700-750mm from wall behind it.   | Non-compliant                       |  |
| Toilet paper holder is located in the correct zone.  | Compliant                           |  |

|   |  |  |
|---|--|--|
| Wash basin has 675mm min. underside clearance from floor, and is located 300mm min. from the front of the WC pan.                   | Non-compliant                            |  |
| Taps on wash basins have capstan or lever handles (hot tap to left of cold tap).  | Non-compliant                            |  |
| Any nappy changing tables do not intrude into the wheelchair manoeuvring space.   | N/A                                      |  |
| <b>DOOR &amp; WINDOW CONTROLS AND LIGHT SWITCHES (NZBC D1.3.4 (f), G9/AS1, NZS 4121 SECTIONS 4, 7 &amp; C5)</b>                     |  |  |
| Doors can be opened with one hand.  | Appears Complaint – not all doors tested |  |
| Door handles are fixed between 900mm and 1200mm (1000 optimum) above floor.   | Appears Complaint – not all doors tested |  |
| Door handles are level action, with end returned towards door (knob handles are not permitted).                                     | N/A                                      |  |
| Door closers have min. tension required to bring door to closed position.   | Appears Complaint – not all doors tested |  |
| Electronic access units are located as NZS 4121 clause 4.11.5.  | Not reviewed                             |  |
| Window locking & opening controls are located between 900mm & 1200mm above the floor.   | Not reviewed                             |  |
| Light switches throughout building are horizontally aligned with door handles.  | Not reviewed                             |  |
| Socket outlets are located 500-1200mm above the floor.  | Not reviewed                             |  |
| <b>VISIBILITY FACTORS (NZBC F2, G7 AND G8, NZS 4121 215, D1/AS1/1.5.4 &amp; 1.8)</b>  |  |  |
| All signs, information boards and all elements of accessible routes are well illuminated.   | Non-compliant / not reviewed             |  |
| <b>SIGNS (BUILDING ACT CL. 47A(5), NZBC G5.3, 5.3.6 &amp; F8.3.4, F8/AS1/5.0, NZS SECTIONS 3.6 &amp; 4.8)</b>                       |  |  |
| Signs are positioned on walls, doors, etc between 1400mm and 1700mm above the floor.  | TBC                                      |  |
| International symbol of access is displayed outside the building or so as to be visible from outside it.                            | Complies                                 |  |
| Access symbol on main information board(s) identifies location of lift, accessible routes, toilets, rooms with listening aids, etc. | Non-Compliant                            |  |
| Accessible toilets / showers are identified with an access symbol on entrance door.   | TBC                                      |  |
| All symbols have correct proportional layout, lettering and colour contrast with background.  | TBC                                      |  |
| Identify facilities:  |  |  |
| <input type="checkbox"/> accessible car park spaces   | Complies                                 |  |
| <input type="checkbox"/> accessible entrance  | Complies                                 |  |
| <input type="checkbox"/> services available in building   | Non-Compliant                            |  |



# Appendix 2.

WARREN AND MAHONEY®

RPT0001\_SMAG\_ACCE  
SSIBILITY GAP  
ANALYSIS\_AUGUST  
2020

|   |  |  |
|---|--|--|
| Handrail diameter is between 32mm and 50mm (or to Fig. 26(b) D1/AS1)  | TBC  |  |
| Handrails have projecting ends (NZS 4121 Fig. 13)   | Non-compliant  |  |
| Ramp landings (and rest areas) allow 1200mm space clear of door swings  | Non-compliant  |  |
| Max. rise between landings is 750mm   | Complies   |  |
| <b>MAIN ENTRANCE AND ALL ACCESSIBLE ROUTES, INCLUDING CORRIDORS, DOORWAYS AND DOORS (NZBC D1.3.4(f), D1 AS1/7.0, FIG 27, NZS 4121 SECTION 7)</b>                              |  |  |
| The main entrance is on the accessible route.   | Complies   |  |
| If the main entrance is not accessible, it has signage indicating location of accessible entrance.  | Complies   |  |
| Preferably there are no thresholds in doorway. If they cannot be avoided, they are max. 20mm high, or 56mm high is a 1:8 max. ramp is provided both sides (NZS 4121 Fig. 17). | Complies   |  |
| There are accessible routes extending from the accessible entry to all spaces that are required to be accessible, 1200mm min. width.  | Non-compliant – lift lobby entrance L1                               |  |
| If existing corridors are less than 1200mm wide, doorways off it are made wider to compensate.  | N/A  |  |
| Doorways have 760mm min. clear opening (unless from narrow corridors where wider clear openings are required).  | Appears to comply – not all doors checked as part of initial review. |  |
| Double doors have at least one leaf which provides 760mm min. clear opening.  | Appears to comply – not all doors checked as part of initial review. |  |
| Doors are colour-contrasted with their surroundings.  | Complies   |  |
| Doors are dual swing and have visibility glazing panels.  | N/A  |  |
| Doors with full height glazing have manifestation markings 7001000mm above floor.   | N/A  |  |
| Clear space between successive doors is 1200mm min. (Fig. 27 D1/AS1).   | Non-compliant – Male WC lobby  |  |
| Where doors open towards wheelchair, an unobstructed wall space not less than 300mm wide is required at side of door adjacent to door handle.                                 | Appears to comply – not all doors checked as part of initial review. |  |
| Forces required to open non-fire doors are within limits.   | Not tested   |  |
| <b>PUBLIC FACILITIES (NZBC G5.3.4, NZS 4121 SECTION 11)</b>   |  |  |
| Where public counters or desks are provided in reception areas, bars, shops & supermarkets, at least one is accessible for both the public and for the staff using it.        | Non-Compliant  |  |

WARREN AND MAHONEY®

RPT0001\_SMAG\_ACCE  
SSIBILITY GAP  
ANALYSIS\_AUGUST  
2020

|  |                     |  |
|--|---------------------|--|
| Accessible portion of counter has top of work surface 775mm max. above floor, with 675mm min. height clearance under for a depth of 540mm.   | Non-Compliant       |  |
| Public telephones comply with NZS 4121 Section 11.2.   | N/A                 |  |
| <b>LIFTS (NZBC D1.3.4 (c), D2.3.5, D2/AS1/71, NZS 4121 SECTION 9)</b>  |                     |  |
| Lifts are required as follows:   |                     |  |
| <input type="checkbox"/> in all buildings with four or more floors   | N/A                 |  |
| <input type="checkbox"/> in a three floor building when the total gross floor area of the two upper floors is 500m <sup>2</sup> or more and the design occupancy exceeds 50 persons  | N/A                 |  |
| <input type="checkbox"/> in a two floor building when the gross floor area of the upper floor is 400m <sup>2</sup> or more and the design occupancy exceeds 40 persons   | Complies            |  |
| <input type="checkbox"/> notwithstanding any of the above, a lift is required if an upper floor is used for: a place of assembly for 250 or more persons, public reception area for a bank, central and local government offices and facilities (including libraries), medical and dental rooms, health care centres | N/A                 |  |
| At least one lift is on the accessible route.  | Complies            |  |
| Lobbies have 1800mm min. unobstructed depth in front of lift doors.  | Complies            |  |
| Car floor has 1400mm x 1400mm min. internal dimensions.  | Complies (TBC)      |  |
| Doors have 900mm min. clear opening.   | Complies            |  |
| Doors are readily distinguishable from their surroundings.   | Complies            |  |
| Doors remain open for at least 5 seconds before starting to close.   | Not tested          |  |
| Car has handrails on walls to NZBC D1/6.0 or NZS 4121 Fig 26.  | Non-compliant (TBC) |  |
| All controls are located between 900mm and 1350mm above the floor.   | Appears to comply   |  |
| All controls have tactile features.  | Not reviewed        |  |
| Lift indicators are provided as NZS 4121:2001 cl. 9.2.5.   | Not reviewed        |  |
| <b>STAIRS (NZBC D1.3.4 (g)(h)(i), D1/AS1/4.0, 4.2, 4.4, 4.5, NZS 4121 SECTION 8)</b>   |                     |  |
| All multi-storeyed buildings that are required to be accessible have at least one accessible stair.  | Non-compliant       |  |
| Stair treads 310mm min.; Risers 180mm max. (of uniform height over each flight).   | Non-compliant       |  |
| Stair has 900mm min. width between handrails.  | Complies            |  |
| Landings have 900mm min. depth (1200mm recommended)  | Appears to comply   |  |
| Max. total rise of 2500mm between landings.  | Not reviewed        |  |

# Appendix 3.

## Architectural Report

## Appendix 3. WC Calculations

### BUILDING PERFORMANCE

#### Calculator for toilet pans, basins and urinals

|   |        |
|---|--------|
| Building use                                    | Museum |
| Is the number of people for the building known? | Yes    |
| Number of occupants                             | 825    |
| Population of the building use                  | 825    |

Results as of 21 October 2020 at 04:29:00 p.m.

| <b>Option 1 - Unisex</b> | <b>Number</b> |
|--------------------------|---------------|
| Facilities               | 4             |
| Accessible facilities    | 2             |

#### **Option 2 - Single Sex pans only**

|                       |   |
|-----------------------|---|
| Female                |   |
| Pans                  | 3 |
| Accessible facilities | 1 |
| Basins                | 2 |
| Male                  |   |
| Pans                  | 2 |
| Accessible facilities | 1 |
| Basins                | 2 |

#### **Option 3 - Single sex with pans and urinal for males**

|                       |   |
|-----------------------|---|
| Female                |   |
| Pans                  | 3 |
| Accessible facilities | 1 |
| Basins                | 2 |
| Male                  |   |
| Pans                  | 2 |
| Accessible facilities | 1 |
| Urinals               | 1 |
| Basins                | 2 |

#### **Option 4 - Single sex pans only, plus accessible unisex**

|                       |   |
|-----------------------|---|
| Female                |   |
| Pans                  | 3 |
| Basins                | 1 |
| Male                  |   |
| Pans                  | 2 |
| Basins                | 1 |
| Unisex                |   |
| Accessible facilities | 2 |

#### **Option 5 - Single sex with pans and urinals for males, plus accessible unisex**

|                       |   |
|-----------------------|---|
| Female                |   |
| Pans                  | 3 |
| Basins                | 1 |
| Male                  |   |
| Pans                  | 3 |
| Urinals               | 1 |
| Basins                | 1 |
| Unisex                |   |
| Accessible facilities | 2 |

The calculator is intended as a guide only and is issued as a guidance material under s175 of the Building Act 2004. While the Department has taken care in producing this calculator, this calculator is not a substitute for professional advice, and advice should be sought on establishing compliance with the relevant building code clauses.

<http://www.building.govt.nz>

# DESIGN ADVICE MEMO

## FIRE



Memo No **F01**  
Job Name **Southland Museum & Art Gallery**  
Job No **200848/F**  
Date **14 August 2020**  
To **TBIG**  
Email **t.browne@tbig.co.nz, nick@maxisprojects.co.nz**  
Attention **Tess Browne, Nick Hamlin**  
Copies to Client  
QS  
Architect

P **03 366 1777**

W **www.pfc.co.nz**

383 Colombo St, Sydenham,  
Christchurch

PO Box 7110, Sydenham 8240  
Christchurch

Signature **David James**

---

## Fire Safety & Egress

### 1. Introduction

This purpose of this Design Memo is to identify the **Fire Safety & Egress** upgrade work that would be required for the various levels of development of the SMAG building. Refer also to Fire drawings F1-F3 attached.

### 2. Strengthen to 34% NBS

A building consent is required even if the building were to be strengthened to only 34% NBS. As required by Section 112 of the Building Act, a consent can only be granted if the Council is satisfied that the building will comply as near as is reasonably practicable (ANARP) with the Means of Escape provisions of the Building Code.

Because of the geometry of the building, an analysis using the Building Code's Verification Method would be required.

The following is the Fire Safety upgrade work that would be expected to be required for the building to comply ANARP with the Fire Code using a C/VM2 approach. This requires a computer analysis of the building, and negotiation with the Council, peer reviewer and FENZ, none of which has been carried out at this stage.

#### Building Use & Design Occupancies:

The use and design occupancies of the various floors are as follows:

2nd floor: storage - occupancy 10

1st floor: museum - occupancy 250

Ground: museum, exhibition, classroom, workshops, offices - occupancy 565

These occupancies need to be checked and confirmed by the Museum management to be appropriate. Note these occupancies are significantly more than what is currently stated on the BWOF (500).

It is critical that the total building occupancy is less than **1000**.

#### Fire Cells:

Because of the difficulty in ensuring the edges of the two upper floors are tight and fire stopped where they meet the Bondor roof, the entire building is considered to be in one single firecell (excluding the stairs and Boiler Room). This allows separating walls, gaps in walls and floors, service penetrations, mechanical ducting etc to remain unrated.



### Sprinkler System:

The building is fully sprinkler protected. The museum areas are protected to ELH and the storage areas are protected to OH3.

The control valves and Fire Service Inlet are in the SVR on the east side of the building.

The water supply is from the 150mm diameter townmain in Gala St. The water supply includes a diesel booster pump in the valveroom.

A monitored backflow preventer is required at the street boundary, including concrete slab and cage.

Any defect items on the latest biennial survey must be attended to.

The sprinkler pipework and heads will require modifying to allow for the structural strengthening.

Seismic restraint of the system will also need to be included.

### Fire Alarm System:

A manual fire alarm system presently exists throughout, including manual call points and a fire alarm panel at the SW main entrance. Some very old smoke and heat detectors exist.

A new Type 4 analogue addressable smoke detection system shall be installed throughout the building, including a new analogue addressable fire alarm panel and new analogue addressable call points and detectors. Remove the existing fire alarm equipment including the old smoke & heat detectors and alarm panel.

### Internal Fire Hydrant System:

An internal fire hydrant is required in the main central stair, with hydrant outlets on each of the 3 floors.

The Fire Service Inlet for this system shall be located under the existing sprinkler FSI.

Include a vertical test pipe alongside the vertical riser in the stair, with outlet at the FSI.

### Air Handling Systems:

Connect the air handling systems to the fire alarm system so that, on fire alarm activation, the air handling systems shut down.

### Fire Hose Reels & Fire Extinguishers:

All existing fire hose reels may be removed entirely.

Add new fire extinguishers in:

- all plant rooms
- workshops
- adjacent to switchboards
- kitchens

### Smoke Extract:

There is some existing smoke extract system activated by the fire alarm. This needs investigating.

A smoke extract system may be required above the western Reception/Exhibition area. The system is needed to ensure the smoke layer on Ground floor is sufficiently high to allow people to egress down the western stair. A make-up air supply via the auto entry door is required.

### Upper Floors:

The 2 upper floors are concrete supported on concrete beams and concrete columns.

Fire stopping is not required to service penetrations through these floors.

### Southern Mezzanine Floor:

This floor is presently lined on its underside with plasterboard. Reline the underside of the floor with 16mm fyreline. Ensure any structural steel support beams are concealed above this fyreline layer.

The existing RHS posts supporting the steel beams shall be lined all around with 16mm fyreline on timber blocking.

### Central Stair:

The central stair is 1530mm wide and must be fire separated on all 3 floors to achieve a 60/60/- FRR.

Some walls are concrete. The timber framed walls shall be relined on both sides with 13mm fyreline, and shall extend up to the underside of the floor above. Create a fire rated lid on top of the stair, lined on its topside and underside with 16mm fyreline.

Doors into the stair on all 3 floors shall be replaced with new -/60/-sm firedoors with magnetic hold open devices, door closers, roller ball latching etc. No locking is permitted.

All displays and combustible items shall be removed from this stair on all floors including the exit route on Ground floor. This also includes the display cupboard and glass door at the midlanding between 1st and 2nd floors.

The walls shall be extended in the subfloor space to the ground with timber framing lined both sides with Hardiflex.

Service penetrations through these walls must be fire stopped including fire dampers to mechanical ducts.

#### Western Stair:

The western stair is 1060mm wide from 2nd to 1st floor, and 1730mm wide from 1st to Ground floor.

This stair need not be fire or smoke rated on any floor. Existing walls and doors surrounding the stair on 1st and 2nd floors may remain as is. The stair is completely open on Ground floor and shall remain as is.

Line the underside of the stair soffit between ground and 1st floors with 16mm fyreline. Line the underside of the support walls with 16mm fyreline both sides.

#### Observatory Stair:

Replace this stair altogether with a new galvanised steel stair, 1m wide, if this space is to continue to be accessed.

#### Southern Mezzanine floor stairs:

Line the underside of the these two stairs with 16mm fyreline.

Line the underside of the support walls with 16mm fyreline both sides.

#### External Walls:

External walls need not be fire rated to protect neighbouring property, as the neighbouring property is Public Open space.

#### Exit Signs:

Maintained illuminated Exit signs are required as shown on the Fire plans. These may be green writing on black background.

Remove all existing Exit signs.

#### Emergency Lighting:

New emergency lighting is required to all:

- public spaces
- stairs, including the observatory stair
- egress routes from the base of all stairs to outside
- internal and external ramps and steps

#### Lift:

The liftshaft need not be fire or smoke rated. This may remain as is.

#### Egress Doors:

Refer to the Fire plans. The hardware to some doors shall be upgraded to include:

NL = no latch

CR = crash bar

Otherwise egress doors shall include keyless hardware on the inside.

If electronic access control is provided to exit doors, these must also include EMREX breakglass on the inside. If crash bars are also required, the crash bars must deactivate the mag lock.

#### Surface Finishes:

All internal ceilings shall include a Group 2 surface finish. Remove existing pinex ceilings, including in the Education Centre.

All internal walls shall include a Group 3 surface finish.

Flooring shall include a critical radiant heat flux of at least 1.2 kW/m<sup>2</sup>.

#### Roof:

The Bondor roof is acceptable from a Fire Code point of view. However, the building's insurers need to comment that it is acceptable to them. FENZ also shall comment. Replacement of the roof with Kingspan may be required.

#### Boiler Room:

The walls surrounding the boiler room shall be fire rated to 90/90/90 FRR. Walls shall be lined both sides with 16mm fyreline. The door shall be replaced with a -/90/-sm fire door. Services penetrations through the fire rated walls shall be fire stopped.

### **3. Upgrade to Building Code Standard**

The same work as in Section 2 above is required.

### **4. Upgrade to TENNZ Guidelines and/or Fit for Purpose**

The Guidelines prepared by Touring Exhibitions Network of New Zealand require that the building be sprinkler protected and include a smoke detection system. This is already included in Section 2 above.



# DESIGN ADVICE MEMO

## MULTIDISCIPLINE



Memo No **MEHA 01**  
Job Name **Southland Museum & Art Gallery (SMAG)**  
Job No **200848/MEHA**  
Date **17 August 2020**  
To **TBIG**  
Email **t.browne@tbig.co.nz, nick@maxisprojects.co.nz**  
Attention **Tess Browne, Nick Hamlin**  
Copies to Client  
QS  
Architect

P **03 366 1777**

W **www.pfc.co.nz**

383 Colombo St, Sydenham,  
Christchurch

PO Box 7110, Sydenham 8240  
Christchurch

Signature **Tim White**

---

## Building Services - Mechanical, Electrical, Hydraulics and Acoustics

### 1. Introduction

This purpose of this Design Memo is to identify the **Mechanical, Electrical, Hydraulics and Acoustics** upgrade work that would be required for the various levels of development of the SMAG building.

Descriptions are provided as a high level summary only; further design work is required on the relevant items once the scope of works has been defined in further detail.

### 2. Strengthen to 34% NBS (only)

A building consent is required even if the building were to be strengthened to only 34% NBS. As required by Section 112 of the Building Act, a consent can only be granted if the Council is satisfied that the building will comply as near as is reasonably practicable (ANARP) with the Means of Escape and Accessibility provisions of the Building Code.

#### Emergency Lighting:

As noted in the Fire Engineering Design Memo F01, new emergency lighting would be required to provide coverage to various areas of the building, as well as illuminated exit signage as per the fire engineering drawings F1-F3.

Some existing emergency lighting is present but is outdated technology requiring regular maintenance to maintain compliance, and would not provide adequate coverage to most areas as required by current standards. For a facility of this size we would also strongly recommend that an automated emergency lighting testing system is deployed to ensure and simplify on-going compliance.

#### Accessibility - Stairs:

Building Code clause D1 requires stairs to be illuminated to a minimum of 150 lux (average). From an initial visual inspection, several of the existing stairways appear to not meet this requirement and therefore additional/new general lighting would be required specifically over stairs.

#### Other Services:

No other services works would be required to achieve this minimum standard only, but there are significant compromises and limitations within the current building with regards to being fit for purpose as a modern museum space and these would of course remain if no further upgrades are pursued.

It is noted that other services such as electrical RCD protection, hydraulic services and ventilation do not comply with the current building code but are not technically required to be upgraded under this level of consent.

### 3. Upgrade to Building Code Standard - All services

In addition to the works described within Section 2 above, the following would be required to achieve compliance with the building code for all services.

#### Lighting:

The only mandatory building code requirement for general lighting is that all occupied spaces achieve a minimum illuminance level of 20 lux. From an initial visual inspection, this should be achieved by existing lighting.

#### RCD protection:

For the safety of occupants, RCD (residual current device) protection is required to all general power circuits within wet areas (such as kitchens, toilets etc.) and to all areas primarily used by children. RCD protection can be added to local socket outlets or at the respective distribution board.

#### Seismic Restraint:

There appears to be essentially no seismic restraint to existing services. A full investigation, design and installation of seismic restraint in compliance with NZS4219 for all services such as mechanical plant and ducts, suspended lighting, suspended pipework etc. would be required in order to comply with current standards.

#### Ventilation:

Following a site inspection and a review of the existing mechanical services drawings it is unlikely that the existing systems meet building code requirements for ventilation. The drawings provided don't specifically state the outdoor air supplied by the main air handling unit, but an assessment of the duct sizing suggests a maximum of approximately 2500l/s of fresh air will enter the building. The BWOFF on site stated a maximum of 500 people within the building. NZS 4303 requires 8l/s/person of outdoor air which would require 4000l/s of fresh air required for this number of people. If the building was to meet building code fresh air requirements, the ventilation system would require upgrading. This would require new fresh air handling systems and likely require an upgrade in central plant capacity to allow for cooling and heating of the additional fresh air.

We note that the fundamental issues within the mechanical system would not be solved by this upgrade. Temperature and humidity control issues would remain which will not meet best practice for museum environment control (TENNZ guidelines).

#### Incoming Water Supply:

A compliant boundary backflow prevention device is required on the incoming water supply. This device is subject to annual testing as part of the building WOF.

#### Domestic Hot Water:

Hot water temperature at personal hygiene fixtures, i.e. wash hand basins is required to be no more than 55°C by code.

#### Café Kitchen Drainage:

Comment was made during the initial site inspecting that there are issues with the drainage from the existing café kitchen. We are unsure exactly what the issues are or works which may be required to resolve them, but this should be investigated further.

#### Toilet Facilities Alterations:

It is understood that changes to the existing toilet facilities have already been discussed and even if these are not required for accessibility compliance, changes are strongly desired by staff and members of the public. Further investigation of existing and design for new mechanical ventilation/extract, hydraulics services and possibly also electrical services (e.g. hand driers) would be required as part of these alterations.

### 4. Upgrade to TENNZ Guidelines and/or Fit for Purpose

The Guidelines prepared by Touring Exhibitions Network of New Zealand provide advice regarding a number of services and are considered a benchmark for best practice within a museum facility.

Meeting these guidelines not only provides a more comfortable, more engaging and more functional facility but also enables SMAG greater ability to attract high value or popular items/collections which otherwise may not be offered.

Other 'fit for purpose' items are also outlined below which may not be specifically mentioned in the TENNZ guidelines but would be strongly recommended to be incorporated within a new (or 'as new') museum/art gallery facility.

These items are in addition to, or an extension of, the works described within Section 2 and 3 above.

#### Power Supply:

If heating plant was to be upgraded and/or was to transition more towards electrically supplied plant, such as heat pumps, then the incoming power supply rating would require further investigation.

#### Electrical Reticulation:

The existing Main Switchboard appears to be circa 1990s and generally in good order. Egress from the room housing the switchboard does not comply with current electrical standards, which requires two means of escape with door swings in the direction of egress.

One distribution board was noted as being relatively new but the majority of existing switchboards appear to be circa 1960s and contain obsolete circuit protection. One was located at the top of a stair which would be considered a safety hazard.

It is recommended that all existing 1960s era distribution boards are replaced, including some being relocated.

#### Lighting:

TENNZ notes 100 lux to be provided to photographic prints. Other standards/design guidelines also recommend 50 lux to paintings, in combination with lower background illuminance. TENNZ and other guidelines also discuss the minimisation of exposure to UV spectrum light which can be achieved using specific, modern LED luminaires.

The existing lighting creates significant glare in many areas which detracts from viewing of exhibitions and collections, as the human eye has to constantly adjust and re-adjust. This can also cause significant discomfort or headaches to photo-sensitive people.

Staff also made comment that many of the existing lighting tracks are generally not in optimal locations.

Some LED lighting appears to have been installed but the much of the general lighting is older technology which is less energy efficient and has a higher maintenance cost than modern LED fixtures.

#### Lighting Control:

Existing lighting controls are manual ON/OFF switching only. A lighting control system with the ability to control and dim lighting to various areas would significantly enhance the functionality and flexibility of the facility.

#### Flexible Power:

Very few general power outlets were observed from the initial visual inspection. Modern facilities typically require/expect general power to be readily available for use within exhibitions/displays/artworks which have a powered or internally lit component, and this was verified with SMAG staff as highly desirable in order to deliver a modern museum/art gallery experience once the building is able to be re-opened.

#### Data/Communications:

The existing communications system was not inspected in detail, but consideration should be given to the potential to upgrade incoming communications infrastructure, connectivity and wireless network coverage throughout the facility.

#### Security/CCTV:

TENNZ guidelines require CCTV coverage of exhibitions at all times and restricted access to works during packing/unpacking. CCTV is also required in storage areas, which is not currently provided.

An existing electronic access control system exists but expansion of this system should be considered to provide greater control/flexibility to secure different areas of the building.

There is an existing coax based CCTV system, but coverage is not extensive and the system is not of the type which would be expected for a modern facility.

#### AV/PA System:

The clarity and reliability of the existing PA system is not fit for purpose, based on feedback from staff. The system also appears to be outdated.

No specific AV system is present to accommodate interactive/technology displays etc.

### Mechanical Services:

To meet the requirements of the TENNZ guidelines, the entire mechanical system would need to be replaced with new. The current chiller/heatpump is a 4-pipe system which provides simultaneous heating and cooling. Based on discussions with the asset manager of the site, this system cannot produce chilled water at temperatures cold enough to provide adequate dehumidification.

The general requirements of the TEENZ for environment control are as follows:

- Temperature: 20-22°C +/- 3°C
- Humidity: 52% +/- 7% with no more than 5% within a 24 hour period

Note that the above standard is required to be met for various important artefacts, archives and collections to be displayed at SMAG. Other facilities will require these standards to be met. Without adherence to this, the Southland Museum and Art Gallery will not be allowed to accommodate and display collections that they may wish to.

A new mechanical system to meet the above standards will include the following; a separate heat pump for heating water and a chiller for chilled water, new humidifiers, dehumidifiers, air handling units, fan coil units and associated ancillaries such as pipework, ductwork, buffer tanks etc.

It also needs to be noted that the stringent environmental control requirements of the TENNZ will only be met if the architectural design of the facility is also improved. For example, the current leaking roof will allow too much moisture into the space to accurately control humidity. Additional design elements such as ante rooms and well-sealed air tight spaces are also required for accurate temperature and humidity control.

### Acoustic Performance:

We consider that there is potential to inadvertently make the acoustics worse through the structural strengthening/minimum code improvements to other services. The following high level considerations are based on a bare minimum of achieving compliance in a “no worse than existing” scenario, examples of which are raised below:

- Where surface finishes are removed/replaced, acoustic consideration will be required to ensure the overall functionality of space is not worsened. One example would be the removal of carpet for other flooring surfaces, carpet is useful acoustic absorber as well as providing a degree of resiliency for footfall noise on suspended floors.
- Pinex ceilings (as identified as an issue in the Fire Engineering Design Memo F01) will provide some acoustic benefit over a plasterboard ceiling; therefore a like for like replacement might include direct fixed acoustic panel absorbers.
- Where linings are removed/replaced, these should be replaced like for like or with a material with a greater density to preserve/improve the sound insulation performance.
- Acoustical performance of high rated partitioning systems (floors/walls) can be dependent on structural isolation of elements. Where elements are tied together for structural/seismic strengthening purposes these will require significant consideration to avoid introducing additional problematic areas.
- If/where mechanical plant is replaced and/or rehoused; consideration will be required for compliance with boundary noise criteria in adjacent sites. We note that the Mechanical Services Engineer may look to provide a greater amount of free area for airflow reasons, this can reduce acoustic screening and result in increased noise levels for neighbouring properties but also on the building it serves.

Other options for further improvement to acoustic performance could be considered in coordination with architectural/other services alterations to the building should this be desired.



Invercargill City Council (ICC)

Southland Museum and Art Gallery (SMAG) - Options Summary

- i) The following cost table summarises RLB's recent costings for SMAG. All estimates shown below are 'order of costs' only, as such we recommend that cost sensitivities are applied to any overarching cost model/ report.
- ii) Costs have been formed on a number of assumptions and clarifications. Please refer to each separate estimate for this detail.

| Ref   | Cost Centre   | Existing Building Cost Options |                            |                                 | New Build Cost Options                                      |                                 |                               |   |                             |                           | RLB Comments         |  |
|---|---|--------------------------------|----------------------------|---------------------------------|---|---------------------------------|-------------------------------|---|-----------------------------|---------------------------|----------------------|--|
|   |   | 34% Option (Minimal Works)     | 67% Option (Minimal Works) | 67% Option (Full Refurbishment) | Demolish Existing Pyramid & New Build Museum (Location TBC) |                                 |                               | Demolish Existing Pyramid & New Build Museum (Location TBC) |                             |                           |                      |  |
|   |   |                                |                            |                                 | Low<br>4,575m2 (Inc Storage)                                | Medium<br>4,575m2 (Inc Storage) | High<br>4,575m2 (Inc Storage) | Low<br>5,300m2 + Storage                                    | Medium<br>5,300m2 + Storage | High<br>5,300m2 + Storage |                      |  |
| 1   | De-Cant of Artefacts and Exhibition Fit Out                         | Excluded                       | Excluded                   | Excluded                        | Excluded  | Excluded                        | Excluded                      | Excluded  | Excluded                    | Excluded                  | Excluded             | We assume that the de-canting of artifacts and exhibition space will be carried out by ICC direct and this cost isn't capitalised against the project? Parties to discuss with ICC.    |
| 2   | De-Cant of Existing Temporary Buildings (Adjacent SMAG) & Make Good | Excluded                       | Excluded                   | Excluded                        | Excluded  | Excluded                        | Excluded                      | Excluded  | Excluded                    | Excluded                  | Excluded             |  |
| 3   | Tuatara Relocation Costs and Temporary Facilities                   | Excluded                       | Excluded                   | Excluded                        | Excluded  | Excluded                        | Excluded                      | Excluded  | Excluded                    | Excluded                  | Excluded             | Discuss with ICC. Reasonable level of cost variability depending on requirements.  |
| <b>Construction Works:-</b>                             |   |                                |                            |                                 |   |                                 |                               |   |                             |                           |                      |  |
| 4   | Construction Works to Existing Museum                               | \$13,310,000                   | \$14,190,000               | \$25,200,000                    | N/A   | N/A                             | N/A                           | N/A   | N/A                         | N/A                       | N/A                  |  |
| 5   | Demolition of Existing Pyramid & Site Make Good                     | N/A                            | N/A                        | N/A                             | \$1,490,000   | \$1,490,000                     | \$1,490,000                   | \$1,490,000   | \$1,490,000                 | \$1,490,000               | \$1,490,000          |  |
| 6   | Infrastructure for New Museum                                       | N/A                            | N/A                        | N/A                             | \$670,000   | \$820,000                       | \$970,000                     | \$670,000   | \$820,000                   | \$970,000                 | \$970,000            |  |
| 7   | New Build Museum  | N/A                            | N/A                        | N/A                             | \$28,600,000  | \$33,170,000                    | \$40,040,000                  | \$33,130,000  | \$38,430,000                | \$46,380,000              | \$46,380,000         |  |
| 8   | External Works  | Excluded                       | Excluded                   | \$700,000                       | \$400,000   | \$900,000                       | \$1,400,000                   | \$500,000   | \$1,000,000                 | \$1,500,000               | \$1,500,000          |  |
| 9   | Compliance Risk Scope   | Excluded                       | Excluded                   | \$790,000                       | N/A   | N/A                             | N/A                           | N/A   | N/A                         | N/A                       | N/A                  |  |
| 10  | General Betterment Works  | Excluded                       | Excluded                   | Included                        | N/A   | N/A                             | N/A                           | N/A   | N/A                         | N/A                       | N/A                  |  |
| <b>Specialist Fit Out Works:-</b>                       |   |                                |                            |                                 |   |                                 |                               |   |                             |                           |                      |  |
| 11  | New Exhibition Fit Out  | Excluded                       | Excluded                   | \$6,800,000                     | \$3,780,000   | \$6,800,000                     | \$9,820,000                   | \$4,380,000   | \$7,880,000                 | \$11,370,000              | \$11,370,000         | Assumed 33% of the building floor area is to have exhibition space.  |
| 12  | Furniture, Furniture and Equipment (FF&E)                           | Excluded                       | Excluded                   | \$900,000                       | \$400,000   | \$900,000                       | \$1,400,000                   | \$500,000   | \$1,000,000                 | \$1,500,000               | \$1,500,000          | Cost put forward in the 'low' category assume the re-use of some existing FF&E. Medium and high categories assume new.   |
| 13  | IT Equipment  | Excluded                       | Excluded                   | \$200,000                       | \$200,000   | \$200,000                       | \$200,000                     | \$250,000   | \$250,000                   | \$250,000                 | \$250,000            | Budget allowance.  |
| <b>Storage Facilities for Artefacts:-</b>               |   |                                |                            |                                 |   |                                 |                               |   |                             |                           |                      |  |
| 14  | Temporary Storage   | \$4,500,000                    | \$4,500,000                | \$4,500,000                     | \$4,500,000   | \$4,500,000                     | \$4,500,000                   | N/A   | N/A                         | N/A                       | N/A                  | Budget allowance.  |
| 15  | Separate Permanent Storage - Assumed New 1,000m2 Building           | N/A                            | N/A                        | N/A                             | N/A   | N/A                             | N/A                           | \$4,500,000   | \$4,500,000                 | \$4,500,000               | \$4,500,000          | Includes provision for infrastructure and some external work requirements.   |
| 16  | Reinstatement of Artefacts  | Excluded                       | Excluded                   | Excluded                        | Excluded  | Excluded                        | Excluded                      | Excluded  | Excluded                    | Excluded                  | Excluded             | We assume that the reinstatement of artifacts and exhibition space will be carried out by ICC direct and this cost isn't capitalised against the project? Parties to discuss with ICC. |
| <b>Sub-Total Construction Cost Only (GST Exclusive)</b> |   | <b>\$17,810,000</b>            | <b>\$18,690,000</b>        | <b>\$39,090,000</b>             | <b>\$40,040,000</b>   | <b>\$48,780,000</b>             | <b>\$59,820,000</b>           | <b>\$45,420,000</b>   | <b>\$55,370,000</b>         | <b>\$67,960,000</b>       | <b>\$67,960,000</b>  |  |
| 17  | Market Escalation to Q4 2024 Only                                   | \$1,350,000                    | \$1,430,000                | \$2,450,000                     | \$4,400,000   | \$5,370,000                     | \$6,580,000                   | \$5,000,000   | \$6,090,000                 | \$7,480,000               | \$7,480,000          |  |
| <b>Sub-Total Construction Cost Only (GST Exclusive)</b> |   | <b>\$19,160,000</b>            | <b>\$20,120,000</b>        | <b>\$41,540,000</b>             | <b>\$44,440,000</b>   | <b>\$54,150,000</b>             | <b>\$66,400,000</b>           | <b>\$50,420,000</b>   | <b>\$61,460,000</b>         | <b>\$75,440,000</b>       | <b>\$75,440,000</b>  |  |
| <b>Design and Management Fees:-</b>                     |   |                                |                            |                                 |   |                                 |                               |   |                             |                           |                      |  |
| 18  | Historical Fee Spend to Q3 2020                                     | Excluded                       | Excluded                   | Excluded                        | Excluded  | Excluded                        | Excluded                      | Excluded  | Excluded                    | Excluded                  | Excluded             |  |
| 19  | Consultant Fees From Q3 2020 Onwards - New Building & Storage       | \$2,750,000                    | \$2,900,000                | \$4,600,000                     | \$5,970,000   | \$7,300,000                     | \$9,170,000                   | \$6,750,000   | \$8,260,000                 | \$10,400,000              | \$10,400,000         |  |
| 20  | Consultant Fees From Q3 2020 Onwards - Exhibition Fit Out & FF&E    | N/A                            | N/A                        | N/A                             | \$400,000   | \$500,000                       | \$600,000                     | \$400,000   | \$500,000                   | \$600,000                 | \$600,000            |  |
| <b>Other Body Costs:-</b>                               |   |                                |                            |                                 |   |                                 |                               |   |                             |                           |                      |  |
| 21  | ICC Internal Costs  | Excluded                       | Excluded                   | Excluded                        | Excluded  | Excluded                        | Excluded                      | Excluded  | Excluded                    | Excluded                  | Excluded             |  |
| 22  | Southland Museum & Gallery Trust Costs                              | Excluded                       | Excluded                   | Excluded                        | Excluded  | Excluded                        | Excluded                      | Excluded  | Excluded                    | Excluded                  | Excluded             |  |
| 23  | Iwi Costs   | Excluded                       | Excluded                   | Excluded                        | Excluded  | Excluded                        | Excluded                      | Excluded  | Excluded                    | Excluded                  | Excluded             |  |
| 24  | Local Authority Fees/Charges/Insurances                             | \$450,000                      | \$450,000                  | \$620,000                       | \$780,000   | \$950,000                       | \$1,160,000                   | \$880,000   | \$1,080,000                 | \$1,320,000               | \$1,320,000          | Includes Resource Consent, Demolition Consent, Building Consent(s) and Development Contributions.  |
| 25  | Contingency   | \$3,000,000                    | \$3,200,000                | \$5,760,000                     | \$10,320,000  | \$12,580,000                    | \$15,470,000                  | \$11,690,000  | \$14,260,000                | \$17,550,000              | \$17,550,000         |  |
| <b>Total Project Cost (GST Exclusive)</b>               |   | <b>\$25,360,000</b>            | <b>\$26,670,000</b>        | <b>\$52,520,000</b>             | <b>\$61,910,000</b>   | <b>\$75,480,000</b>             | <b>\$92,800,000</b>           | <b>\$70,140,000</b>   | <b>\$85,560,000</b>         | <b>\$105,310,000</b>      | <b>\$105,310,000</b> |  |

## RLB Key Clarifications / Assumptions

---

### Procurement:-

- a) We have assumed that the works will be procured in a 'traditional' form whereby ICC maintain design control.
- b) We have assumed that any construction works will be competitively tendered.

### Programme:-

- c) Costs assume that the new Museum and Art Gallery will be complete and open by no later than Q4 2024.

### Covid:-

- d) We advise that at the time of preparing this cost table the impacts of COVID 19 remain fluid. Even though New Zealand is currently operating under Alert 1, we note that the full effects of COVID 19 on the construction industry are yet to fully materialise. The ongoing consequences of this pandemic are likely to influence CAPEX. Some key issues include but are not limited to:-
  - i) General market economy changes.
  - ii) Border closures affecting supply of labour in particular.
  - iii) Exchange rate fluctuations.
  - iv) Off shore manufacturing capacity and timing of delivery.
  - v) Local and national logistics including delivery of materials and supplies etc.

### RLB Exclusions

- 1) GST.
- 2) Land purchase costs.
- 3) Finance / funding costs.
- 4) ICC internal costs.
- 5) Legal fees.
- 6) Stakeholder engagement and consequential effects.
- 7) Market escalation costs beyond Q4 2024.
- 8) Assumed all new build options are designed to IL3
- 9) Exclusions listed in above table.