



Notes

1. Unsealed surfaces. Backfill to surface with specified material and ram hard.
2. Lean-mix concrete to be 10 parts aggregate to 1 part cement to be placed fairly dry and rammed hard.

Not to scale